

Curtins Consulting										Page 1	
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG											
Date 04/04/2022 15:49 File stage 3 01.04.22.MDX											
Designed by Marta.Wolska Checked by											
Micro Drainage						Network 2018.1.1					
<u>STORM SEWER DESIGN by the Modified Rational Method</u>											
<u>Network Design Table for Storm</u>											
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.000	13.471	0.225	60.0	0.015	5.00	0.0	0.600	o	100	Pipe/Conduit	
S2.000	6.448	0.107	60.0	0.009	5.00	0.0	0.600	o	100	Pipe/Conduit	
S1.001	5.789	0.058	99.8	0.009	0.00	0.0	0.600	o	150	Pipe/Conduit	
S1.002	1.673	0.837	2.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
S1.003	3.333	0.033	100.0	0.031	0.00	0.0	0.600	o	300	Pipe/Conduit	
S1.004	7.195	0.072	100.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
S1.005	13.086	0.131	100.0	0.032	0.00	0.0	0.600	o	300	Pipe/Conduit	
S1.006	13.403	0.134	100.0	0.048	0.00	0.0	0.600	o	300	Pipe/Conduit	
S3.000	14.622	0.146	100.2	0.015	5.00	0.0	0.600	o	150	Pipe/Conduit	
S3.001	19.143	0.191	100.0	0.010	0.00	0.0	0.600	o	150	Pipe/Conduit	
S3.002	8.429	0.084	100.0	0.010	0.00	0.0	0.600	o	150	Pipe/Conduit	
S3.003	7.660	0.034	225.3	0.010	0.00	0.0	0.600	o	225	Pipe/Conduit	
S4.000	6.926	0.115	60.0	0.020	5.00	0.0	0.600	o	150	Pipe/Conduit	
<u>Network Results Table</u>											
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)	
S1.000	50.00	5.23	33.710	0.015	0.0	0.0	0.0	1.00	7.8	2.0	
S2.000	50.00	5.11	33.710	0.009	0.0	0.0	0.0	1.00	7.8	1.2	
S1.001	50.00	5.32	33.435	0.033	0.0	0.0	0.0	1.01	17.8	4.5	
S1.002	50.00	5.33	33.377	0.033	0.0	0.0	0.0	7.18	127.0	4.5	
S1.003	50.00	5.36	32.150	0.064	0.0	0.0	0.0	1.57	111.1	8.7	
S1.004	50.00	5.44	32.117	0.064	0.0	0.0	0.0	1.57	111.1	8.7	
S1.005	50.00	5.58	32.045	0.096	0.0	0.0	0.0	1.57	111.1	13.0	
S1.006	50.00	5.72	31.914	0.144	0.0	0.0	0.0	1.57	111.1	19.5	
S3.000	50.00	5.24	32.300	0.015	0.0	0.0	0.0	1.00	17.7	2.0	
S3.001	50.00	5.56	32.154	0.025	0.0	0.0	0.0	1.00	17.8	3.4	
S3.002	50.00	5.70	31.963	0.035	0.0	0.0	0.0	1.00	17.8	4.7	
S3.003	50.00	5.85	31.000	0.045	0.0	0.0	0.0	0.87	34.5	6.1	
S4.000	50.00	5.09	32.230	0.020	0.0	0.0	0.0	1.30	23.0	2.7	
©1982-2018 Innovyze											

Curtins Consulting								Page 4
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG								
Date 04/04/2022 15:49 File stage 3 01.04.22.MDX				Designed by Marta.Wolska Checked by				
Micro Drainage				Network 2018.1.1				
PIPELINE SCHEDULES for Storm								
Upstream Manhole								
PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.000	o	100	S1	34.270	33.710	0.460	Open Manhole	450
S2.000	o	100	S2a	34.270	33.710	0.460	Open Manhole	450
S1.001	o	150	S2	34.270	33.435	0.685	Open Manhole	450
S1.002	o	150	S vertical	34.270	33.377	0.743	Open Manhole	150
S1.003	o	300	S3	32.800	32.150	0.350	Open Manhole	600
S1.004	o	300	S4	32.800	32.117	0.383	Open Manhole	600
S1.005	o	300	Sjunction	32.800	32.045	0.455	Junction	
S1.006	o	300	S5	32.800	31.914	0.586	Open Manhole	600
S3.000	o	150	S6	32.800	32.300	0.350	Open Manhole	450
S3.001	o	150	S7	32.800	32.154	0.496	Open Manhole	450
S3.002	o	150	S8	32.800	31.963	0.687	Open Manhole	450
S3.003	o	225	S9	32.800	31.000	1.575	Open Manhole	600
S4.000	o	150	S10	32.800	32.230	0.420	Open Manhole	450
Downstream Manhole								
PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.000	13.471	60.0	S2	34.270	33.485	0.685	Open Manhole	450
S2.000	6.448	60.0	S2	34.270	33.603	0.567	Open Manhole	450
S1.001	5.789	99.8	S vertical	34.270	33.377	0.743	Open Manhole	150
S1.002	1.673	2.0	S3	32.800	32.540	0.110	Open Manhole	600
S1.003	3.333	100.0	S4	32.800	32.117	0.383	Open Manhole	600
S1.004	7.195	100.0	Sjunction	32.800	32.045	0.455	Junction	
S1.005	13.086	100.0	S5	32.800	31.914	0.586	Open Manhole	600
S1.006	13.403	100.0	S tank	32.800	31.780	0.720	Open Manhole	1200
S3.000	14.622	100.2	S7	32.800	32.154	0.496	Open Manhole	450
S3.001	19.143	100.0	S8	32.800	31.963	0.687	Open Manhole	450
S3.002	8.429	100.0	S9	32.800	31.878	0.772	Open Manhole	600
S3.003	7.660	225.3	S tank	32.800	30.966	1.609	Open Manhole	1200
S4.000	6.926	60.0	S11	32.800	32.115	0.535	Open Manhole	600
©1982-2018 Innovyze								

Curtins Consulting		Page 6
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG		
Date 04/04/2022 15:49 File stage 3 01.04.22.MDX		
Designed by Marta.Wolska Checked by		
Micro Drainage		Network 2018.1.1

Area Summary for Storm

Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)
1.000	-	-	100	0.015	0.015	0.015
2.000	-	-	100	0.009	0.009	0.009
1.001	-	-	100	0.009	0.009	0.009
1.002	-	-	100	0.000	0.000	0.000
1.003	-	-	100	0.031	0.031	0.031
1.004	-	-	100	0.000	0.000	0.000
1.005	-	-	100	0.032	0.032	0.032
1.006	-	-	100	0.048	0.048	0.048
3.000	-	-	100	0.015	0.015	0.015
3.001	-	-	100	0.010	0.010	0.010
3.002	-	-	100	0.010	0.010	0.010
3.003	-	-	100	0.010	0.010	0.010
4.000	-	-	100	0.020	0.020	0.020
5.000	-	-	100	0.019	0.019	0.019
4.001	-	-	100	0.000	0.000	0.000
6.000	-	-	100	0.019	0.019	0.019
4.002	-	-	100	0.000	0.000	0.000
7.000	-	-	100	0.053	0.053	0.053
4.003	-	-	100	0.026	0.026	0.026
1.007	-	-	100	0.041	0.041	0.041
				Total	Total	Total
				0.367	0.367	0.367

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
S1.007	S	33.000	30.826	0.000	0	0

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start (mins)	0	Inlet Coeffiecient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1

Number of Input Hydrographs	0	Number of Offline Controls	0	Number of Time/Area Diagrams	0
Number of Online Controls	1	Number of Storage Structures	1	Number of Real Time Controls	0

Synthetic Rainfall Details

©1982-2018 Innovyze

Curtins Consulting		Page 7																				
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG																						
Date 04/04/2022 15:49 File stage 3 01.04.22.MDX	Designed by Marta.Wolska Checked by																					
Micro Drainage	Network 2018.1.1																					
Synthetic Rainfall Details <table><tr><td>Rainfall Model</td><td>FSR</td><td>Profile Type</td><td>Summer</td></tr><tr><td>Return Period (years)</td><td>100</td><td>Cv (Summer)</td><td>0.750</td></tr><tr><td>Region</td><td>England and Wales</td><td>Cv (Winter)</td><td>0.840</td></tr><tr><td>M5-60 (mm)</td><td>18.000</td><td>Storm Duration (mins)</td><td>30</td></tr><tr><td>Ratio R</td><td>0.361</td><td></td><td></td></tr></table>			Rainfall Model	FSR	Profile Type	Summer	Return Period (years)	100	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	18.000	Storm Duration (mins)	30	Ratio R	0.361		
Rainfall Model	FSR	Profile Type	Summer																			
Return Period (years)	100	Cv (Summer)	0.750																			
Region	England and Wales	Cv (Winter)	0.840																			
M5-60 (mm)	18.000	Storm Duration (mins)	30																			
Ratio R	0.361																					
©1982-2018 Innovyze																						

Curtins Consulting		Page 8
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG		
Date 04/04/2022 15:49 File stage 3 01.04.22.MDX	Designed by Marta.Wolska Checked by	
Micro Drainage	Network 2018.1.1	
<u>Online Controls for Storm</u> <u>Pump Manhole: S tank, DS/PN: S1.007, Volume (m³): 3.8</u> Invert Level (m) 30.842 Depth (m) Flow (l/s) 1.390 23.4000		
©1982-2018 Innovyze		

Curtins Consulting		Page 11
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG		
Date 04/04/2022 15:49	Designed by Marta.Wolska	
File stage 3 01.04.22.MDX	Checked by	
Micro Drainage		Network 2018.1.1

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Water		Surcharged		Flooded		Pipe		Status	Level Exceeded
		Level (m)	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Flow (l/s)				
S1.000	S1	33.748	-0.062	0.000	0.31		2.3			OK	
S2.000	S2a	33.740	-0.070	0.000	0.20		1.4			OK	
S1.001	S2	33.495	-0.091	0.000	0.33		4.8			OK	
S1.002	S vertical	33.407	-0.121	0.000	0.08		4.8			OK	
S1.003	S3	32.226	-0.224	0.000	0.14		8.7			OK	
S1.004	S4	32.189	-0.228	0.000	0.13		8.8			OK	
S1.005	Sjunction	32.120	-0.225	0.000	0.14		12.8			OK*	
S1.006	S5	32.007	-0.207	0.000	0.21		18.9			OK	
S3.000	S6	32.337	-0.113	0.000	0.14		2.3			OK	
S3.001	S7	32.201	-0.103	0.000	0.21		3.5			OK	
S3.002	S8	32.020	-0.092	0.000	0.31		4.8			OK	
S3.003	S9	31.231	0.006	0.000	0.09		2.4			SURCHARGED	
S4.000	S10	32.270	-0.110	0.000	0.16		3.1			OK	
S5.000	S11a	32.292	-0.048	0.000	0.52		2.9			OK	
S4.001	S11	32.086	-0.171	0.000	0.13		5.9			OK	
S6.000	S12a	32.279	-0.061	0.000	0.32		2.9			OK	

Curtins Consulting		Page 14
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG		
Date 04/04/2022 15:49	Designed by Marta.Wolska	
File stage 3 01.04.22.MDX	Checked by	
Micro Drainage		Network 2018.1.1

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
S1.000	S1	33.776	-0.034	0.000	0.76		5.6	OK	
S2.000	S2a	33.759	-0.051	0.000	0.48		3.4	OK	
S1.001	S2	33.544	-0.041	0.000	0.86		12.7	OK	
S1.002	S vertical	33.426	-0.102	0.000	0.22		12.6	OK	
S1.003	S3	32.286	-0.164	0.000	0.42		25.6	OK	
S1.004	S4	32.245	-0.171	0.000	0.38		25.4	OK	
S1.005	Sjunction	32.182	-0.163	0.000	0.42		38.5	OK*	
S1.006	S5	32.090	-0.124	0.000	0.63		58.0	OK	
S3.000	S6	32.361	-0.089	0.000	0.34		5.6	OK	
S3.001	S7	32.237	-0.067	0.000	0.58		9.7	OK	
S3.002	S8	32.074	-0.039	0.000	0.89		13.8	OK	
S3.003	S9	31.762	0.537	0.000	0.26		7.3	SURCHARGED	
S4.000	S10	32.295	-0.085	0.000	0.38		7.5	OK	
S5.000	S11a	32.388	0.048	0.000	1.26		7.0	SURCHARGED	
S4.001	S11	32.118	-0.139	0.000	0.31		14.4	OK	
S6.000	S12a	32.308	-0.032	0.000	0.79		7.1	OK	

Curtins Consulting		Page 17
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG		
Date 04/04/2022 15:49	Designed by Marta.Wolska	
File stage 3 01.04.22.MDX	Checked by	
Micro Drainage		Network 2018.1.1

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
S1.000	S1	34.037	0.227	0.000	1.31		9.7	FLOOD RISK	
S2.000	S2a	33.783	-0.027	0.000	0.87		6.1	OK	
S1.001	S2	33.654	0.069	0.000	1.47		21.7	SURCHARGED	
S1.002	S vertical	33.442	-0.085	0.000	0.38		21.9	OK	
S1.003	S3	32.682	0.232	0.000	0.32		19.7	FLOOD RISK	
S1.004	S4	32.681	0.264	0.000	0.29		19.7	FLOOD RISK	
S1.005	S junction	32.345	0.000	0.000	0.26		23.3	SURCHARGED*	
S1.006	S5	32.675	0.461	0.000	0.46		42.4	FLOOD RISK	
S3.000	S6	32.686	0.236	0.000	0.28		4.6	FLOOD RISK	
S3.001	S7	32.685	0.381	0.000	0.46		7.7	FLOOD RISK	
S3.002	S8	32.679	0.566	0.000	0.65		10.2	FLOOD RISK	
S3.003	S9	32.672	1.447	0.000	0.46		12.6	FLOOD RISK	
S4.000	S10	32.693	0.313	0.000	0.31		6.2	FLOOD RISK	
S5.000	S11a	32.697	0.357	0.000	1.04		5.8	FLOOD RISK	
S4.001	S11	32.690	0.433	0.000	0.25		11.5	FLOOD RISK	
S6.000	S12a	32.693	0.353	0.000	0.65		5.8	FLOOD RISK	

