

**Description of landscaping Works:**

- Area to be cordoned off and made safe.
- Materials to be taken to working area and prepped.
- Ground to be dug and prepared for planting.
- Plants to be planted as per Quote.
- Job to be completed, cordoned areas to be removed.
- Area to be cleared and cleaned.

Description of Maintenance Works:

Future maintenance to include a 3-month watering plan weekly, also included into Plot xs site SLA a comprehensive maintenance package to keep the hedge kept no higher than the existing fence line, also to be kept two feet off the security fencing encroaching onto the residential side to allow maintenance access. The visits will be carried out monthly and revised every three years to see if the schedule needs to be upped to provide sufficient maintenance for the hedging.

The hedge will be cut regularly to help prevent nesting and any un-used nests and nest in the building process will be removed to keep the bird population down in the hedge line, all within line with the (Wildlife and countryside act).

Description of starling nesting prevention:

The hedging will be regularly checked monthly for nesting.

Whilst checking for nesting if we find eggs or young birds in the hedging, we will leave them be. We must wait about 12 days for eggs to hatch and up to 3 weeks for young to leave the nest. We will check the nest frequently—once the young leave the nest, we remove the nesting material, and seal the openings with netting.

The best practice to reduce starling nesting is prevention, checking the hedge line monthly and removing building materials before nests are completed will be the best practice to prevent the starlings from nesting and as described above, if nesting accrues it will be removed appropriately and promptly.

Location:

Plot X, Car Park, Airport

**Start date
and time:** TBC**finished deadline
date:** TBC

Works**Supervisor:** Kristian Lawrence/Jack Jeffery**Role:** Project Managers

**Telephone:** 07722681946**e-mail:** lewiscarrington@pegasuslandscapes.co.uk**1. Personnel Details**

*Lewis Carrington - Project Manager
Roger Carrington – Designer/Project Manager
John Jeffery – Supervising Manager
Mark Wilson – Team leader
Kris Lawrence – Landscaping Manager
Ramtin Musah – Labourer
Jack Jeffery – Maintenance Manager*

2. Overview of Work

The logistics of each individual job is explained in the quote or upon request the timing/Deadline for completion of works is 3 calendar Days from the start date of works. This may change depending on weather conditions.

3. Resources Required

Access to power and a water supply is not required on site.

4. Risk Assessment

The risk assessment document reference is (Pegasus TBC)

5. Control Measures

All staff are trained in there required fields to carry out working activities, staff are insured, and the relevant public liability is in place. Staff are supplied and must wear full PPE during all working activities whilst on site. A full first aid kit is readily available.

6. Personal Protective Equipment

Pegasus landscapes PPE i.e., masks, protective gloves, goggles are bought in for each landscaping job and disposed of after every use to guarantee 100% working order PPE. Personal PPE of the staff is of top spec standard wearing Safety boots, Toughened safety trousers and Husqvarna reflective Kevlar sleeved jackets. All other PPE is available and kept on site.

Prepared by:	Lewis Carrington	Position:	Director/Project Manager
Date:	13/12/2021	Signature:	L Carrington

Reviewed by:	Kristian Lawrence	Position:	Landscape Manager
--------------	-------------------	-----------	-------------------



Date:	13/12/2021	Signature:	K Lawrence
-------	------------	------------	------------