



Condenser to be wall mounted at high level leaving 2500mm clear space below and in security cages.
All condense water to be connected to local SVP.
All external pipe work to be on tray and fitted with protective capping.

