jmarchitects

WINDOW SCHEDULE

3A
54 Princess Street
Manchester
M1 6HS

T: 0161 200 6300
F: 0161 200 6301

Contract No: 17 St.John Street, Manchester

Client: Private Client

Schedule no:

Rev: 02 - 17.02.2022

NOTE: - All window proposals to be approved by planning and conservation.

REFERENCE NO.	FLOOR	ELEVATION	EXISTING	PROPOSED
BASEMENT FLOOR				
W-B0-001	Basement	Front (North)	High level window. Painted timber.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. P6B rated glazing to be used. - TO BE APPROVED BY CONSERVATION
W-B0-002	Basement	Front (North)	High level window. Painted timber.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. P6B rated glazing to be used. - TO BE APPROVED BY CONSERVATION
W-B0-003	Basement	Rear (South)	Painted timber.	Existing window to be carefully removed and stored and opening to be overbaorded.
GROUND FLOOR				
W-G0-001	Ground Floor	Front (North)	Painted timber hung sash window, 4 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. P6B rated glazing to be used. - TO BE APPROVED BY CONSERVATION
W-G0-002	Ground Floor	Front (North)	Painted timber hung sash window, 4 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. P6B rated glazing to be used. - TO BE APPROVED BY CONSERVATION
W-G0-003	Ground Floor	Rear (West)	Soft wood painted.	Window to be removed and replaced with new internal timber doors.
W-G0-004	Ground Floor	Rear (West)	Soft wood painted.	Window to be removed and replaced with new internal timber doors.
W-G0-005	Ground Floor	Rear (East)	Steel frame painted.	To be removed and replaced with new timber frame window to match the original style windows.
FIRST FLOOR				
W-01-001	First Floor	Front (North)	Painted timber hung sash window, 4 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. SBD rated with 6.8mm laminate.
W-01-002	First Floor	Front (North)	Painted timber hung sash window, 4 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. SBD rated with 6.8mm laminate.
W-01-003	First Floor	Front (North)	Painted timber hung sash window, 4 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. SBD rated with 6.8mm laminate.
W-01-004	First Floor	Rear (East)	Painted timber hung sash window, 8 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. SBD rated with 6.8mm laminate.
W-01-005	First Floor	Rear (West)	Painted timber hung sash window, 16 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. SBD rated with 6.8mm laminate.
W-01-006	First Floor	Rear (West)	Painted timber hung sash window, 12 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. SBD rated with 6.8mm laminate.
SECOND FLOOR				
W-02-001	Second floor	Front (North)	Painted timber hung sash window, 6 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. SBD rated with 6.8mm laminate.
W-02-002	Second floor	Front (North)	Painted timber hung sash window, 6 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. SBD rated with 6.8mm laminate.
W-02-003	Second floor	Front (North)	Painted timber hung sash window, 6 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. SBD rated with 6.8mm laminate.
W-02-004	Second floor	Rear (South)	Painted timber hung sash window, 8 panes, original box frame.	Existing window to be retained and refurbished. Proposed slim line secondary security clear glazing (Selectaglaze-Series 41 single side hung or Granada Glazing) to be installed internally. SBD rated with 6.8mm laminate.
W-02-005	Second floor	Rear (West)	uPVC sliding white	Existing window to be replaced with new to match original style. 6.8mm laminate.