NORTH

0 1 2 3 4 5 m 10 15 20

368 WELDMESH SCREEN FENCE TO CORNER OF SERVICE YARD

NATIVE SHRUB PLANTING

TIMBER SLATTED SEATS ON 400mm HIGH CONCRETE WALL

368 WELDMESH FENCE 2.4m TO SECURE PERIMETER OF ACADEMY

SECURE PEDESTRIAN GATE ACCESS FROM ACADEMY GROUNDS CONNECTED TO EXISTING PATH NETWORK

WOODEN CYCLE SHELTER WITH GREEN ROOF FOR 16 CYCLES - SECURABLE AND VISIBLE FROM OFFICES
Access into the proposed bicycle store to operate on an access control system, with access restricted to genuine users.

MIXED EXTRA HEAVY STANDARD TREE PLANTING TO BOUNDARY TO REPLACE FELLED TREES

8Nr EXISTING TREES TO BE FELLED

NATIVE HEDGE PLANTING TO BOUNDARY TO REPLACE EXISTING SCRUB

AIR HANDLING UNIT COMPOUND SCREENED BY 2m HIGH 358 HIGH SECURITY WELDMESH FENCE PANELS

CANOPY OVER

2.4m 358 HIGH SECURITY WELDMESH FENCE WITH DOUBLE VEHICLE ACCESS GATE

2.4m 358 HIGH SECURITY WELDMESH FENCE WITH ACCESS GATE FOR SCHOOL USE

S/STEEL SHEFFIELD CYCLE RACKS FOR 18 CYCLES

22m LIGHTING COLUMN

EMERGENCY AMBULANCE ACCESS ON TO PITCH

RUN-OFF AND LINESMAN AREA SURFACED IN 3G SYNTHETIC GRASS AND SHOCKPAD TO WRA STANDARDS

NEW 6m BALL STOP NETTING TO MATCH EXISTING AT OTHER END OF PITCH

3.1m

40.0m

1.0m

EXISTING GOALS MOVED

PEDESTRIAN ASPHALT WITH OCCASIONAL VEHICULAR USE FOR MAINTENANCE

EXISTING PITCH EXTENDED TO 65 X 89M PLUS 6m DEAD BALL ZONE AND 3m RUN-OFF ALL ROUND

DUEX SPORTS SPECTATOR RAIL

4No. 15m SPORTS LIGHTING COLUMNS TO SOUTH SIDE OF PITCH

RAISED TURF MOUND, UPTO 1.5m HIGH, WITH 150mm GRANITE FINISH KERB TO EDGE

RAISED TURF MOUND, UPTO 1.2m HIGH, WITH 150mm GRANITE FINISH KERB TO EDGE

FOOTWAY MARKING ON EXISTING CAR PARK AS EXTENSION TO ACCESSIBLE BAYS

MAINTENANCE/SERVICE ACCESS ROAD IN VEHICULAR ASPHALT

REMOVABLE BOLLARDS

CONSERVATION KERB WITH 150mm UPSTAND

DRAINAGE CHANNEL

SERVICE AND DROP-OFF LAYBY

ORNAMENTAL SHRUB PLANTING

S/STEEL BOLLARDS

PAVIOR EDGE DETAIL

VEHICULAR ASPHALT

TIMBER SLATTED BENCH SEAT WITH ADJACENT STEEL LITTER BIN

CONSERVATION KERB WITH 150mm UPSTAND

PAVIOR STRETCHER BOND DETAIL IN DARK COLOUR

REMOVABLE BOLLARDS

387090,874 , 397808,229

DROPPED KERB

DROPPER KERB

GRANITE FINISH UNIT PAVING IN FOUR COLOURS

STEPS DOWN WITH TACTILE PAVING TO TOP AND BOTTOM AND HANDRAILS TO SIDES AND CENTRE

EXISTING CAR PARK PLANTING

EXISTING CAR PARK PLANTING

EXISTING FOOTWAY ENHANCED WITH CROSSING MARKINGS

PROPOSED EHS TREES, UNDERGROUND GUYING

MAINTENANCE ACCESS AND DELIVERIES

REMOVABLE BOLLARDS

ROAD RAISED TO PAVEMENT LEVEL

DROP KERB

FLUSH KERB EDGE TO TIE-IN TO EXISTING SURFACING

EXISTING PAVING

20m TRAVEL DISTANCE FROM BIN STORE TO EXISTING DROPPED KERB

SECURE BIN STORE SURROUNDED BY 2m 358 SECURITY WELDMESH PANELS SURFACED IN PEDESTRIAN ASPHALT TO HOUSE 6 1100Ltr EUROBINS Incl. RECYCLING BINS

WOODEN CYCLE SHELTER WITH GREEN ROOF FOR 16 CYCLES - VISIBLE FROM MAIN CIRCULATION SPACE

ROAD-SIDE FENCE AND SHRUBS REMOVED EXISTING TREES, GRASS AND PERIMETER KERB TO BE RETAINED

GREEN WALL S/STEEL VERTICAL CLIMBER SUPPORTS FIXED TO ELEVATION AT 1m CENTRES

2.4m WELDMESH PERIMETER FENCE, TO MATCH EXISTING, WITH DOUBLE VEHICLE ACCESS GATE

EMERGENCY AMBULANCE ACCESS ON TO PITCH

22m LIGHTING COLUMN

EXISTING BALL STOP FENCE MOVED

3.7m

EXISTING GOALS MOVED

2.0m

14

15

17

31

LEGEND

- Unit Paving: Tobermore Braemar Slabs 600x300x80mm thick
  - Iona White
  - Islay Rose
  - Jura Grey
  - Alto Silver
  - Arran Stone
  - Cara Slate.
- Unit Paving Details: Tobermore Braemar Slabs 200x100x80mm thick
  - Innis Grey
- Asphalt Vehicular Paving to Engineer's Spec
- Asphalt Pedesrian Paving to Engineer's Spec
- Synthetic Turf 3G to WRA Standards along Touchline
- High Quality Amenity Turf
- Ornamental Shrub Planting
- Existing Planting

05	Enlarged to A3 - Whole of site boundary included Issued for PLANNING.	29 Nov 21	GW
04	Northern boundary simplified Issued for PLANNING.	22 Nov 21	GW
03	Gate and native hedging added to northern boundary Maintenance access to front of building increased to 2m	02 Nov 21	GW
02	Cycle parking added, paving set out to unit sizes	28 Oct 21	GW
01	AHU Enclosure, site furniture and slab hatching added	19 Oct 21	GW

original by GW 17-10-21

STERRY-WALTERS PARTNERSHIP LTD
Landscape and Sports Facilities Consultants
Ashbocking, Ipswich, Suffolk, IP6 9JY
Tel. 01868 860470 M.07779 795443
www.sterry-walters.com

Client: OURLEAGUE

Project: RFL NATIONAL HUB
GREY MARE LANE, MANCHESTER

Drawing Title: SITE PLAN

S-WP Project Number: 2021.09.13
Scale: 1:200
Plot Size: ISO full bleed A0 (841.00 x 1189.00 MM)
Plot Date: 29 November 2021

Drawing Number

Project	Consultant	Volume	Level	Type	Role	Number	Status
RFLH	SWP	- 00	- EX	- DR	- L	- 9001	- S4

RIBA Stage: 3 - PLANNING
Revision: 05

This drawing is to be read in conjunction with all related Architectural and Engineering drawings and specifications. All dimensions must be checked and verified on site before commencing any work or producing shop drawings.
DO NOT SCALE FROM THIS DRAWING
WORK TO FIGURED DIMENSIONS ONLY
The originator should be notified immediately of any discrepancy.
This drawing is copyright and remains the property of
The Sterry-Walters Partnership Ltd