



Schedule of Works

200	Disassemble, Removal and Alteration Works
201	Disassemble Existing Bay Window Roof
202	Remove and Retain Existing Primary and Secondary Casement Windows
203	Remove and Retain Internal Pendant Light Fitting
204	Remove and Retain Skirtings
205	Remove and Retain Flooring Boards and Floor Covering
206	Remove and Retain Internal Cornices
207	Remove Internal Plaster Ceiling
208	Remove and Retain localised areas of brickwork for Temporary Works Propping
209	Disassemble Facade Brickwork
210	Remove and Retain Existing Stone Window Lintels
211	Remove and Retain Existing Stone Window Cills
212	Remove / Disassemble Brick Relieving Arch
213	Remove Timber Beam/s
214	Alter Floor Joists



Existing Ground Floor Plan with Alterations Work

Scale 1:50

9298-BA - B1 - ZZ - DR - A - (01)011 - P1