






FLOORS




Existing floor retained and cleaned
No additional works.



Existing Carpet Tiles - Retained


Carpet: Interface
Range: Composure
Colour: Transcribe - Ref: 4169007



New Carpet Tiles


Carpet: Interface
Range: Composure
Colour: Transcribe - Ref: 4169007
NBS: M50/130

Allowance for new replacement carpet tiles to floor junctions between existing partitions to be removed and new walls to be installed.




Existing Feature Carpet Tiles - Retained

Carpet: Shaw
Range: Haven identity tile
Colour: Greige - 335516



Existing Vinyl Tile Flooring - Retained

Vinyl: Polyflor
Range: Expona Commercial
Colour: Light Grey Concrete - Code 5067




New Vinyl Tile Flooring

Vinyl: Polyflor
Range: Expona Commercial
Colour: Light Grey Concrete - Code 5067
NBS: **M50/110**



Allowance for new replacement vinyl tiles to floor junctions between existing partitions to be removed and new walls to be installed.



New Vinyl Sheet Safety Flooring

Vinyl: Polyflor
Range: Polysafe Standard PUR
Colour: Ash Grey 4540
NBS: **M50/151**

General Notes:

- Existing floor to 2nd floor level is a raised access type. An allowance it to be made for replacing damaged floor panels, or areas where existing finish cannot be removed. Approx 10%
- Existing floor finishes that are removed are to be taken back by the flooring manufacturer as part of their recycling scheme.
- All new finishes to 2nd floor are to be in tile format applied to raised access panels.
- Install self levelling screed to any new floor finish (Ref: C & G). **NBS M50/465**
- Note: Floor Reference F (used to match existing) only achieves a slip resistance value of R10

Tender Issue		09.02.2022			
Rev.	Description	Date			
Client					
Manchester Metropolitan University					
Project					
MSA Decant Appraisal					
Drawing Title					
2nd Floor Floor Finishes					
Drawn by	JKB	Checked by	SB	Date	31.01.2022
Status	D2	Scale	A1	1:125	
Job no.	Dwg no.	Rev.			
11264	CAA-05-02-DR-A-015002	P1			
Cassidy+ Ashton				C+A	
www.cassidyashton.co.uk					
Architecture + Building Surveying + Town Planning					
7 East Cliff, Preston, Lancashire, PR1 3JE				01772 258 356	
10 Hunters Walk, Canal Street, Chester, CH1 4EB				01244 402 900	