








KEY LANDSCAPING - SOFT LANDSCAPE

-  **Proposed Native Multistem Tree in planting bed**
Species - Birch and Hazel 2 - 2.5m high. Where required to protect services & prevent heave, trees should be planted with a linear root barrier.
-  **Proposed Multistem Tree in open ground**
Species - Birch and Hazel 2 - 2.5m high
-  **Proposed Multistem Large Shrub**
Species - Cornus Kousa
-  **Proposed Native Woodland Edge Planting - Total Area 141m²**
Trees and shrubs to be planted in areas shown at 1.5 x 1.5m c/c to comprise locally native 60-80cm BR whips and 175-200cm feathered whips.
-  **Proposed Single Species Ornamental Hedge**
Hedges to be Yew planted as 40 Lt 80/100cm in pre grown troughs
-  **Proposed Ornamental Planting - Total Area 139m²**
Shrubs to be planted as 3L pots at 3-5 per sqm Mixture of ornamental / hardy shrubs suitable for site conditions to give white / green / purple colour palette.
-  **Proposed Wildflower Meadow - Total Area 402m²**
Areas to be seeded with Emorsgate EM3 Special General Purpose Meadow Mixture
-  **Proposed Native Bulbs - Total Area 31m²**
Areas as indicated to be planted with swathes of native bulbs to include snowdrop, bluebell and crocus
-  **Proposed Green roof to bin / bike store - Total Area 46m²**



DEP LANDSCAPE ARCHITECTURE LTD

2 COMMERCIAL STREET
MANCHESTER, M15 4RQ
T: 0161 2419878
E: info@dep.co.uk
W: www.dep.co.uk

Client

Quorum

Project

Ashbrook, Heald Green

Description

Soft Landscaping

Status

For Planning

Scale

1 : 200@A1

Drawn

BH

Job number

5011 02

Drawing number

Date

March 22

Revision

Copyright DEP Landscape Architecture Ltd

All levels and dimensions to be checked on site by contractor prior to commencement; Any variations to be reported to the client. This drawing is to be read in conjunction with all others relating to the project and all information derived accordingly; any anomalies to be reported to the client. Do not scale from this drawing. Use figured dimensions only. Work shown on this drawings to be carried out in accordance with current British Standards and Codes of Practice.

© Copyright to DEP Landscape Architecture Limited. The information shown on this drawing shall not be reproduced or copied in any form without prior written consent from DEP Landscape Architecture Limited.

NATIVE WOODLAND MIX - Planted at 1 per sq.m and to be protected with spiral bound shrub guards					
SHRUBS					
Ca	Corylus avellana	BR	60-80	10%	14
Cs	Cornus sanguinea	BR	60-80	10%	14
Cmo	Crataegus monogyna	BR	60-80	20%	28
Ia	Ilex aquifolium	2L C	40-60	5%	7
Msy	Malus sylvestris	BR	60-80	5%	7
Rc	Rosa canina	BR	60-80	10%	14
Sn	Sambucus nigra	BR	60-80	10%	14
Vo	Viburnum opulus	BR	60-80	5%	7
TREES					
Bp	Betula pendula	Feathered whip	175-200	5%	7
Fs	Fagus sylvatica	Feathered whip	175-200	5%	7
Pa	Prunus avium	Feathered whip	175-200	5%	7
Qr	Quercus robur	Feathered whip	175-200	5%	7
Sau	Sorbus aucuparia	Feathered whip	175-200	5%	7

FEATURE TREE PLANTING					
Abb	Species	Size	Height (cm)	Root	Number
Ca ms	Corylus avellana	multi stem	200-250	RB	6
Bp ms	Betula pendula	multi stem	200-250	RB	16
ORNAMENTAL HEDGEROW					
Abb	Species	Size	Height (cm)	Density	Number
Tb	Taxus baccata	40L	80-100	1m trough	45
WILDFLOWER MIX (TOTAL AREA: 2703m2)					
Product		Area		Density	Kg
EM3 special general purpose meadow mixture		2703		4g/m2	0.0

BULBS			
Abb	Species	Size	Number
Gn	Galanthus nivalis	bulb	650
Hns	Hyacinthiodes non scripta	bulb	325
Ca	Colchicum autumnale	bulm	325

ORNAMENTAL SHRUB PLANTING				
Abb	Species	Size	Height (cm)	Density
Hr	Hebe rakaiensis	3L	40-50	4 sq.m
HmZ	Hydrangea macrophylla 'Zebra'	3L	20-30	3 sq.m
CAP	Choysia ternata 'Aztec Pearl'	3L	20-30	3 sq.m
EFEG	Euonymus 'Emerald n Gold'	3L	20-30	4 sq.m
Hy	Hebe youngii	3L	20-30	3 sq.m
Cc	Cornus canadensis	3L	40-50	5 sq.m
LaH	Lavandula angustifolia Hidcote	3L	20-30	4 sq.m
HRE	Hebe Red Edge	3L	30-40	4 sq.m
Ctr	Ceanothus thyrsiflorus repens	3L	30-40	4 sq.m
CK	Cornus kousa chinensis	35-45Lt		nr