



Osborne Yard, Manchester

Outline Drainage Strategy

Project No: 2006-06
August 2020
Rev: 00



This report been prepared for the sole benefit, use and information of Cert Property for the purposes set out in the report or instructions commissioning it. The liability of **renaissance** in respect of the information contained in the report will not extend to any third party. This document should not be used in whole or part by any third parties without the express written permission of **renaissance**. If any unauthorised third party comes into possession of this report, they rely on it at their own risk and Renaissance do not owe them any Duty of Care.

author	Nuala Powell
signature	
date	24.08.2020
approved	Helen Gribbon
signature	
date	27.08.2020

Contact Details:-

Helen Gribbon | Director
MIStructE, CEng, BEng, MScArch

Carvers Warehouse, 77 Dale Street
Manchester, M1 2HG

e: helengribbon@renaissance-ltd.com

Revision	Description	Issued by	Date	Checked
00	Issued for RIBA Stage 3	N Powell	27.08.2020	H Gribbon



CONTENTS

1.0	INTRODUCTION	1
1.1	PURPOSE OF THIS REPORT	1
2.0	THE SITE	2
2.1	SITE LOCATION.....	2
2.2	SITE DESCRIPTION	2
2.3	EXISTING SITE DRAINAGE	3
2.4	GEOLOGY.....	3
2.5	HYDROLOGY	3
2.6	PROPOSED DEVELOPMENT	3
3.0	EXISTING & PROPOSED SURFACE WATER DISCHARGE RATES	5
3.1	PRE-DEVELOPMENT SURFACE WATER RUN-OFF RATES.....	5
3.2	PROPOSED SURFACE WATER DISCHARGE RATES & ATTENUATION REQUIREMENTS ...	6
4.0	SURFACE WATER DISCHARGE & SUDS ASSESSMENT.....	8
4.1	SURFACE WATER DISCHARGE ASSESSMENT	8
4.2	SUSTAINABLE URBAN DRAINAGE	8
4.3	WATER QUALITY ASSESSMENT.....	9
4.4	SUDS MANAGEMENT PLAN	9
5.0	OUTLINE DRAINAGE STRATEGY.....	10
5.1	SURFACE WATER SYSTEM	10
5.2	FOUL WATER SYSTEM	11
5.3	PHASING & SURFACE WATER MANAGEMENT DURING CONSTRUCTION.....	11
6.0	CONCLUSION.....	ERROR! BOOKMARK NOT DEFINED.2

APPENDICES

APPENDIX A	Existing Topographical Survey
APPENDIX B	United Utilities Water Sewer Records
APPENDIX C	Existing Site Permeable Areas & Outline Attenuation Summary
APPENDIX D	Outline Drainage Strategy
APPENDIX E	Micro Drainage Pre-Development Surface Water Run-off



1.0 INTRODUCTION

1.1 Purpose of this report

This Outline Surface Water Drainage Strategy has been prepared to support the planning application for the proposed development for Osborne Yard, Manchester.

The assessment includes: a summary of the site, an estimate of the existing and proposed surface water discharge rates, infiltration assessment, SUDs assessment, and outline drainage proposals and performance criteria.

This report should be read in conjunction with the Flood Risk Assessment, Renaissance, July 2020.

The proposals within this report are intended to demonstrate the feasibility of the overarching drainage strategy to support the planning proposal.

2.0 THE SITE

2.1 Site Location

The proposed development site is located off Oldham Rd, Manchester.

The site location is described below:

- Post Code M40 7PS
- OS X (Easting) 385590
- OS Y (Northing) 399569
- Nat. Grid SJ855995

The site location is illustrated in Figure 2.1 below.



Imagery ©2020 Google, Imagery ©2020 Infoterra Ltd & Bluesky

Figure 2.1: Site Location

2.2 Site Description

The site is circa 0.212 hectares and comprises of mainly a carwash facility which is surrounded by unused land.

The site is set within a mixed commercial and residential area. Helga Street borders the site along its north-eastern boundary and Oldham Road along its eastern side. There are retail and commercial units to the southwest and the Network Rail Collyhurst Compound runs at high level behind masonry retaining wall along the western side of the site.

The two buildings that border the site are one and two storeys, respectively. The first is a steel structure used as a garage for repairing vehicles and the second is a masonry building with retail units.

The site is mostly flat as can be seen from the topographical survey in Appendix A. There is extensive vegetation and trees to the north of the site. To the south of the car wash facility, the site has dense vegetation against the rear wall.

The overall site is not enclosed by a wall or fence; however, low level steel fences surround the car wash facility as a demarcation of space and offer no security. There are various entry points onto the site off Oldham Road.

2.3 Existing Site Drainage

The existing site is 60% impermeable with associated existing drainage. Based on the United Utility drawing (Appendix B) the existing foul and surface water from the site discharges to the United Utilities (UU) combined sewer along Oldham Road.

2.4 Geology

Made Ground: British Geological Survey does not indicate made ground, however based on the historical mapping and the development that has taken place, made ground deposits are highly likely to be present.

Although not indicated to be present on site, a large area of made ground is indicated to abut the site to the north-west. This is likely associated with the railway and storage yard.

Superficial Deposits: The site is indicated to be underlain by glacial till. This stratum typically comprises clay to sandy clay, unsorted, with gravels, cobbles and some boulders.

Solid Geology: The deeper solid geology underlying the superficial deposits is indicated to be part of the Pennine Upper Coal Measures which typically comprises mudstone, siltstone, sandstone and coal seams. An extract from the 1:50,000 scale BGS Geological Map Sheet 85 Manchester showing the location of the site.

The bedrock of the Pennine Upper Coal Measures Formation is indicated to dip at an angle of 15° towards the south-west. The closest dip measurement to the site as recorded on BGS mapping is an angle of 5° towards the south-west. However, as this dip is within the Collyhurst Sandstone Formation, which unconformably overlies the Pennine Upper Coal Measures, it is not considered to be representative of the solid geology underlying the site.

A number of coal seams are indicated to be present close to the site within the Pennine Upper Coal Measures Formation. In addition, there are seams present within a potentially influencing distance of the site which are recorded to have been worked by the Bradford Colliery.

2.5 Hydrology

The nearest watercourse to the site is the River Irk, which lies at a distance of 705m north-west of the site and flow direction is indicated to be from north to south.

There are no surface water features located within 250m.

The nearest Water Framework Directive (WFD) Surface Water Body is the River Medlock (Lumb Brook to Irwell), located 1086m SE, with a 'good' chemical rating and a 'moderate' ecological rating (2016).

There are no surface water abstractions within 2000m of the site.

The closest licenced discharged consent is historical, located 219m SE for sewer storm overflow into the River Irk. The closest active licenced discharge consent is located 418m NE and relates to sewer storm overflow into the River Irk.



Information obtained from the Environment Agency (EA) Risk of Flooding from Rivers and the Sea (RoFRaS) database indicates that the site is not at risk of flooding from rivers and sea.

Groundwater flooding is defined as the emergence of groundwater at the ground surface or the rising of groundwater into man-made ground under conditions where the normal range of groundwater levels is exceeded. Data within the environmental searches, obtained from Ambiantal Risk Analytics, indicate the maximum groundwater flooding risk at the site is low.

2.6 Proposed Development

The proposed development is for a residential end use comprising a 6-storey apartment block with up to 90 No. 1-3 bedroom apartments, with an area of landscaping at first floor level. Refer to Elevate Architects drawings submitted for planning for details.

The proposals are to work within the existing site levels where possible. The new building will typically have ground floor levels that approximately tie into existing external levels.

3.0 EXISTING & PROPOSED SURFACE WATER DISCHARGE RATES

3.1 Pre-Development Surface Water Run-Off Rates

The existing developed site area is 2,260m² (0.226 ha) and is considered 60% impermeable in its current condition. The brownfield areas consists of positively drained hard-standing and buildings with areas of vegetation throughout the other area of the site.

3.1.1 Existing Brownfield Run-Off Rates

To estimate the pre-development surface water discharge into the existing drainage system a mock network has been simulated in industry approved Micro Drainage Software (Appendix E) which is presented in the Table 3.1. The system is based on a single 225 dia connection to the existing surface water system. A critical 60 minute duration has been assumed to obtain the predevelopment rates.

A 50% betterment to brownfield run-off rates is proposed in line with Manchester, Salford & Trafford Strategic Flood Risk Assessment, March 2011 (SFRA). The pre-development run-off rates for the 1, 2, 30 and 100 year events are therefore: -

Return Period	Q _{Brownfield} (l/s)	Q _{50% Brownfield} (l/s)
1 in 1 year	10.3	5.15
1 in 2 year	13.2	6.60
1 in 30 year	23.1	11.55
1 in 100 year	29.2	14.6

Table 3.1 – Brownfield Run-off Rates

3.1.2 Existing Greenfield Run-Off Rates

A remaining permeable area of 0.092 Ha (922.5m²) is to be considered as greenfield run-off rates. The greenfield run-off rates for this portion of the development have been calculated using Microdrainage ICP SUDS method. The rates presented below are what would be typical of a site with an equivalent surface area which remains undeveloped / covered in grass or vegetation. A partly urbanised catchment ratio of 0.75, Q_{bar} has a return period of 2.3 years.

The equivalent greenfield run-off rate is tabled below: -

Return Period	Q _{Greenfield} (l/s)
1 in 1 year	1.1
1 in 2 year	1.3
1 in 30 year	1.9
1 in 100 year	2.0

Table 3.2 – Greenfield Run-off Rates

3.2 Proposed Surface Water Discharge Rates & Attenuation Requirements

Peak discharge rates will therefore be restricted to 50% of the pre-development brownfield run-off rate, plus greenfield run-off rates for the remaining area.

Restricting discharge rates to Greenfield run-off rates for the whole site is not considered practicable given the site constraints including; size of site, limitations on infiltration. However, practical measures in addition to the 50% reduction in pre-development discharge are presented below, including allowance for climate change in post-development rates and use of SUDs to reduce runoff.

The total proposed run-off rates for the development site has been presented in the table below.

Return Period	Q _{50% Brownfield} (l/s)	Q _{Greenfield} (l/s)	Q _{total} (l/s)
1 in 1 year	5.15	1.1	6.3
1 in 30 year	11.55	1.9	13.5
1 in 100 year	14.6	2.0	16.6

Table 3.3 – Proposed Surface Water Run-off Rates

The proposed development results in circa 2,260m² of building footprint or external hard landscaping.

The ground conditions are not ideal for the use of permeable systems, (refer to the Phase I Desk Top Assessment Report by renaissance dated August 2020). The site is indicated to be underlain with glacial till. This stratum typically comprises clay to sandy clay, unsorted gravels, cobbles and some boulders. This is overlain with made ground and therefore considered at this stage to be unsuitable for infiltration of surface water. This is to be further explored during future Phase II intrusive SI which will confirm the exact characteristics of the ground profile.

The post development discharge rates will include for an increase in the rainfall intensity of 40% to allow for climate change as is consistence with a design life of the development of 100 years, as outlined in NPPF.

To comply with the Non-Statutory Technical Standards for Sustainable Drainage: Practice Guidance the runoff volume for the post development 1 in 100 year 6 hour rainfall event will not exceed the pre-development runoff volume as the Brownfield runoff rates have been reduced by 50%. Elements of SUDs not considered within the new drainage strategy will aid in the reduction and time of concentration of the post development runoff volume.

The total allowable discharge from the site is 16.6 l/s.

A quick storage estimate for the 1 in 100 year storm event, plus 40% for climate change, using Micro Drainage, indicates that the total of circa 46-84m³ of attenuation across the site is required to limit the peak surface water discharge to 50% of the pre-development brownfield plus greenfield, with the discharge limits as presented in Table 3.3.

Refer to Appendix B, Existing Site Permeable and Impermeable areas and Storage Volume Estimate summary, with micro-drainage outputs provided in Appendix E.

As the full footprint of the site will be occupied by the new development, at this stage, the provision of an attenuation tank has been considered. As the design progresses, it is possible that the podium deck and also the main flat roof can be considered as Blue roofs. The



provision of 50mm depth of surface water storage in both of these areas will provide the necessary volume required.

For the post-development discharge rates and volumes, the benefit of these SUDs techniques will be conservatively ignored at this stage and will be investigated further as the development is brought forward to detailed design and construction.

4.0 SURFACE WATER DISCHARGE & SUDS ASSESSMENT

4.1 Surface Water Discharge Assessment

In accordance with NPPF, the following hierarchy of surface water drainage options has been considered:

- Discharge into the ground (infiltration);
- Discharge to a surface water body;
- Discharge to a surface water sewer, highway drain, or another drainage system;
- Discharge to a combined sewer.

Infiltration direct to the ground has been considered, however, due to anticipated areas of made ground and clay content it may not be feasible to dispose of surface water from the development through infiltration.

Opportunities for discharge to watercourse have been considered. The nearest watercourse to the site is the River Irk, which lies at a distance of 705m north-west of the site and flow direction is indicated to be from north to south. There are no surface water features located within 250m, therefore, it is not viable to discharge to this watercourse due to its distance.

Surface water flows will be collected by a dedicated gravity system designed in accordance with BS EN 752 before discharging to a sewer network and into the public combined sewer within Oldham Road, subject to agreement under S106 of the water industry Act.

The surface water system will accommodate flows on-site up to and including the 1 in 100-year critical duration event, with an allowance for climate change. Surface water discharge rate from the site is to be restricted to 50% betterment of existing Brownfield run-off plus Greenfield run-off. Detailed calculations of onsite storage and discharge rates can be found in Appendix C - Existing Site Permeable Areas & Outline Attenuation Summary, and Appendix E, Micro Drainage Pre-Development Surface Water Run-off.

The surface water system will be collected on site, via various SUDs features and collected by a dedicated gravity system designed in accordance with BS EN 752 before discharging to the sewer network, subject to agreement under S106 of the water industry act.

Foul water flows will be collected by a dedicated gravity network designed in accordance with BS EN 752 before discharging to the existing combined sewer in Oldham Road, subject to agreement under Section 106 of the water industry Act.

4.2 Sustainable Urban Drainage

Table 4.1 below provides a summary of typical SUDs techniques outlined within CIRIA guide 753 SUDs manual. Based on a review of the suitability of the SUDs techniques it is proposed that the Osborne Yard development incorporated the following:

- Blue Roof roofs generally and at first floor level on the accessible deck over the parking area to reduce runoff rates, improve water quality and possibly provide amenity value.
- Provide a flow control and underground storage to limit runoff from the site to acceptable limits with the final arrangement to be developed as each phase of the development comes forward for detailed planning.



SUDs Technique	Description	Suitability for Development Site	
Soft Landscaping	Grassed areas that allow direct infiltration of rainwater	Not suitable due to no provision of grassed area.	✗
Filter Drains	Granular filled Linear drains / soakaway with either granular fill and perforated pipe, or dense vegetation that treat runoff from adjacent impermeable areas	Not suitable due to ground conditions, contamination risk and proximity of buildings.	✗
Swales	Shallow landscape channel that can infiltrate or convey runoff.	Not suitable due to ground conditions, contamination risk and proximity of buildings.	✗
Infiltration Basins	Depressions in the ground designed to store and infiltration runoff to the ground. Can be landscaped to provide amenity value.	Not suitable due to ground conditions, contamination risk and proximity of buildings.	✗
Wet Ponds	Basins with permanent pool of water providing water quality treatment, wildlife and amenity benefit. Designed to provide temporary storage for additional runoff.	Not suitable due to ground conditions, contamination risk and proximity of buildings.	✗
Extended Detention Basins	Dry basins that are designed to temporarily store runoff providing water quality treatment.	Not suitable due to ground conditions, contamination risk and proximity of buildings.	✗
Constructed Wetland	Ponds and shallow wetland areas with vegetation to improve pollution removal and enhance wildlife habitat.	Not suitable due to ground conditions, contamination risk and proximity of buildings.	✗
Porous Paving	Granular build-up beneath permeable paving systems that can be used to either store runoff (lined system) and increase time of concentration or allow percolation into the ground.	Not suitable due to extent and nature of development	✗
Trees Pits	Managed permeable paving systems around tree pits that can be used to either store runoff (lined system) and increase time of concentration or allow percolation into the ground.	Not suitable due to no provision of trees with pits	✗
Soakaways	Infiltration device to temporarily store runoff and allow it to percolate into the ground.	Not suitable due to ground conditions and contamination risk.	✗
Green Roof	Vegetated roof area that reduce runoff and increase time of concentration.	Suitable to the roof area, subject to design development.	✓
Blue Roof	Roof area designed to store and reduce peak runoff rates during intense storms.	Suitable to the roof area.	✓
Underground Storage	Attenuation structures installed below ground to provide runoff storage.	Suitable beneath car park area at ground floor	✓

✗ Not suitable

? Potentially suitable subject to further investigation

✓ Suitable

Table 4.1 – SUDs Techniques & Suitability for Development Site

4.3 Water Quality Assessment

The drainage from the site is from the roof to the buildings and a very small area of public / private space, which is restricted to pedestrian use only. Water quality is generally affected by frequent rainfall events, 1 in 1 year events or less, which is circa 5mm/hr for the proposed development site. To assess the water quality consideration will be given to the guidance with the National Standard for Sustainable Urban Drainage (NSSUD) and CIRIA Guide C753. The pollution hazard levels for difference land uses are presented in table 4.2 and are based on the definitions in the NSSUD and C753.



Pollution Hazard Level	Land Use
Very Low	Residential roofs
Low	Individual property driveways, non-residential roofs, residential car parks, low traffic roads, non-residential car parking with infrequent change (e.g. Schools, offices)
Medium	Commercial yards and delivery areas, non-residential car parking with frequent change (e.g. hospital, retail), minor roads
High	Site with heavy pollution (e.g. Haulage yards, lorry parks, waste sites, sites with chemical and fuels are delivered, handled, stored etc.)

Table 4.2 – Pollution Hazard Levels

As the car park area is to be used for residential parking access the Pollution Hazard Level is considered as very low to low with the primary consideration given to removal of gross solids and sediment.

The following tables indicate the minimum number of treatment stages required before surface runoff should reach the infiltration or receiving water body and are extracted from the NSSUD.

Pollution Hazard Level	Land Use	Low	Med	High
G1	Source Protection Zone 1, within 50m of a well, spring or borehole that supplies potable water.	1	3	Consult the EA
G2	Into or immediately adjacent to a sensitive receptor that could be influenced by infiltrated water. Includes designated nature conservation, heritage and landscape sites – including Biodiversity Action Plan (BAP) habitats and Protected Species.	1	3	
G3	Source Protection Zone II and III or Principal Aquifer	1	3	
G4	Secondary Aquifer	1	2	
G5	Unproductive strata	1	2	

Table 4.3 – Groundwater Minimum Treatment Stages

Pollution Hazard Level	Normal surface water	Sensitive surface water
Low	0	1
Med	2	3
High	Consult the EA	

Table 4.4 – Surface Water Body Minimum Treatment Stages

Surface water discharging by infiltration is considered not to be viable generally at this stage given the ground conditions as previously noted and this will be confirmed during the Phase II site investigations.

Discharge of surface water to the receiving public sewer requires no treatment stages due to the low pollution hazard level. However, the adoption of SUDS and good practice will provide inherent treatment. Areas of blue roofs dependant on detailing, will act to absorb most frequent rainfall events and filter out solids and sediment. Any roof areas not utilised as blue-roofs will pass through silt traps prior to entering the attenuation tank and flow control device. Sumps will also be provided to gullies and channels within the ground floor areas prior to connecting to the silt traps. The silt traps and sumps will allow most of the sediment and solids to settle out under low flows, prior to discharging to the public sewer.

4.4 SUDS Management Plan

The adopted Sustainable Urban Drainage systems are to be maintained by the Building Management Company selected by the client. The building management company will be required to maintain the SUDs features in line with the following recommendations and suppliers' requirements of the various features. The management plan and selection of SUDs for each phase of development will be dealt within in more details as the detailed planning applications are progressed.

The following operation and maintenance requirements for the SUDs features incorporated into the development are to be adopted by the Building Management Company. These requirements are general and have been extracted from the CIRA Guide C753.

Table 12.5 - Operation and maintenance requirement for green roofs

(also applies to blue roofs)

Table 21.3 - Operation and maintenance requirement for attenuation storage tanks

The Main Contractor delivering each phase of development will update the general requirements to reflect the product specific requirements of the as installed proprietary SUDs and incorporate these into the Operation & Maintenance manual for the building.

TABLE 12.5 Operation and maintenance requirements for green roofs

Maintenance schedule	Required action	Typical frequency
Regular inspections	Inspect all components including soil substrate, vegetation, drains, irrigation systems (if applicable), membranes and roof structure for proper operation, integrity of waterproofing and structural stability	Annually and after severe storms
	Inspect soil substrate for evidence of erosion channels and identify any sediment sources	Annually and after severe storms
	Inspect drain inlets to ensure unrestricted runoff from the drainage layer to the conveyance or roof drain system	Annually and after severe storms
	Inspect underside of roof for evidence of leakage	Annually and after severe storms
Regular maintenance	Remove debris and litter to prevent clogging of inlet drains and interference with plant growth	Six monthly and annually or as required
	During establishment (ie year one), replace dead plants as required	Monthly (but usually responsibility of manufacturer)
	Post establishment, replace dead plants as required (where > 5% of coverage)	Annually (in autumn)
	Remove fallen leaves and debris from deciduous plant foliage	Six monthly or as required
	Remove nuisance and invasive vegetation, including weeds	Six monthly or as required
	Mow grasses, prune shrubs and manage other planting (if appropriate) as required – clippings should be removed and not allowed to accumulate	Six monthly or as required
Remedial actions	If erosion channels are evident, these should be stabilised with extra soil substrate similar to the original material, and sources of erosion damage should be identified and controlled	As required
	If drain inlet has settled, cracked or moved, investigate and repair as appropriate	As required

TABLE 21.3 Operation and maintenance requirements for attenuation storage tanks

Maintenance schedule	Required action	Typical frequency
Regular maintenance	Inspect and identify any areas that are not operating correctly. If required, take remedial action	Monthly for 3 months, then annually
	Remove debris from the catchment surface (where it may cause risks to performance)	Monthly
	For systems where rainfall infiltrates into the tank from above, check surface of filter for blockage by sediment, algae or other matter; remove and replace surface infiltration medium as necessary.	Annually
	Remove sediment from pre-treatment structures and/or internal forebays	Annually, or as required
Remedial actions	Repair/rehabilitate inlets, outlet, overflows and vents	As required
Monitoring	Inspect/check all inlets, outlets, vents and overflows to ensure that they are in good condition and operating as designed	Annually
	Survey inside of tank for sediment build-up and remove if necessary	Every 5 years or as required



5.0 OUTLINE DRAINAGE STRATEGY

5.1 Surface Water System

The surface water drainage is to collect the rainwater from the proposed building within a dedicated surface water network. The system is to then discharge under gravity to the combined sewer in Oldham Road subject to agreement under S106 of the water industry act. An outline drainage strategy is presented in Appendix D.

The surface water discharge from the site is to be limited 50% of the existing brownfield plus greenfield run-off rates using a flow control device within the final manhole on site prior to discharge into the public sewer.

Attenuation will be provided using cellular storage beneath the car park area with the potential for a blue roof to be adopted over the car park and at the main roof level.

The surface water discharging from the site will be from the building roofs and a nominal amount of private pedestrian only accessible areas at grade only. To ensure water quality to the public sewer is acceptable all rainwater to the public realm area is to be collected in gullies and channels with sumps. In addition all rainwater from the building and at-grade private areas is to pass through silt trap manholes prior to discharging into the attenuation tank to allow silt to be intercepted and settle out under normal rainfall conditions.

The extent of the existing UU combined sewer drain in Oldham Road is to be surveyed to confirm connection levels for the new drainage from the development site. The new surface water drainage connection will be subject to a section 106 application.

The surface water drainage network is to be designed in accordance with Building Regulation Part H, BS EN 752 and 'Sewers for Adoption' 7th edition. In addition, the following requirements will also be adopted in accordance with the Non-Statutory Technical Standards for Sustainable Drainage: Practice Guidance and Salford City Councils SuDS requirements for new developments:

- No surcharging of drainage network for design storm of 1 in 2 years.
- As the site is relatively flat with limited opportunity for management to store flood at grade the below ground drainage system will be designed to ensure flooding does not occur on site for both the 1 in 30 year and 1 in 100 year rainfall events
- 1:100 year + 40% model reviewed, and flood routing plans prepared as part of details site design
- No flooding inside buildings in a 1 in 100 year plus climate change event.

Refer to Appendix E for Micro Drainage calculations showing pre-development discharge on which the proposed system has been based. surface water system will work for the 1, 2, 30 and 100 year return events with 40% climate change and free flow outfall, together with the 1 in 100 + CC Storm duration up to 6hr and 40% climate change for the surcharge outfall with the 1 in 100 year flood level.

5.2 Foul Water System



The foul water drainage from the apartments, plant areas, and washdown gullies will be collected by a dedicated gravity foul network. The system is to be connected to the existing UU combined sewer in Oldham Road, via a new connection.

The proposal is to connect to existing sewer via a saddle connection. At present, based on the details for the upstream UU MH6500, the invert at the connection point is assumed to be 53.70m AOD, allowing the new system to discharge via gravity.

The new foul water drainage connection will be subject to a section 106 application.

The drainage system is to be designed in accordance with Building Regulations Part H, BS EN 752 and 'sewers for adoption' 7th edition.

5.3 Exceedance Events

The levels to the site are relatively flat and in an exceedance event, safe egress can be provided directly from the building onto Oldham Road via the main entrance to the south west or directly from the townhouses which face onto Oldham Road.

5.4 Phasing & Surface Water Management During Construction

It is assumed that given the scale of the development that it will be delivered in a single phase.

The management of surface water management during construction will be addressed by the Main Contractor as part of their 'Construction Management Plan'.

A brief overview of the key consideration relating to surface water management and flood risk that will need to be incorporated into the Main Contractors construction methodology include:

- The existing buildings on site are to be demolished. Stockpiling of material on site is to be minimised to ensure that the flood storage capacity for the 1 in 1000 year (0.1% AEP) event is not compromised.
- Due to the industrial history of the site it is anticipated that ground remediation may be required. A working platform will also be required during construction to allow for formation of piled foundations etc. The top of the working platform is to be located at or lower than existing site levels to ensure that the flood storage capacity for the 1 in 1000 year (0.1% AEP) event is not compromised.
- Subject to the level of contamination beneath the site, level of site remediation, and quality of working platform compaction to reduce infiltration, consideration should be given to the risk of residual contamination on site affecting groundwaters and the adjacent watercourse.
- The risk of spillage of diesel and other contamination risk during construction activities are to be assessed and measures implemented to ensure they do not cause a risk to groundwaters and the adjacent watercourse.



APPENDIX A

Topographical Survey


LEGEND	
CONTROL STATIONS	△
MANHOLE	□ 48" 31.20
BUSH	
TREE	
DROP KERB	---
	TOP BANK
EMBANKMENT	BOTTOM BANK
OVERHEAD ELECTRICITY LINE	
TELEPHONE LINE	
FOOTPATH	
FENCE	
HEDGE	
FOLIAGE	
DITCH	
VERGE	
EXISTING BUILDING	
MAIN CONTOUR	50.00
CONTOUR	45.00
SW SEWER	---
FW SEWER	---
AV	Air Valve
BH	Borehole
BD	Bollard
BM	Bench Mark
BT	BT Inspection Chamber
BL	Bed Level
CATV	Cable TV Cover
C/L	Chain Link Fence
C/P	Catch Pit
CSP	Concrete Paving Slab
ECB	Electricity Control Box
ER	Erector Level
FL	Flower Bed
FR	Fire Hydrant
FL	Floor Level
GH	Greenhouse
GP	Gate Post
GR	Grate
GV	Gas Valve
Q	Quality
IC	Inspection Chamber
IL	Invert Level
KO	Kerb Outlet
JB	Junction Box
LP	Long Post
MH	Man Hole
MP	Marker Post
MS	Mini Stone Marker
NP	Street Name Plate
O/H	Overhead
PB	Post Box
P	Pipe
PM	Parking Meter
P/W	Post & Rail Fence
P/W	Post & Wire Fence
P/E	Electricity Pole
RE	Rodding Eye
RL	Building Ridge Level
RSJ	Reinforced Steel Joist
R/W	Retaining Rail
RWB	Roadwater Pipe
SPLS	Stone Paving Slabs
SL	Self Lift
SP	Sign Post
ST	Stop Top
SV	Stop Valve
SY	Stay Wire
TC	Traffic Crossing
TOW	Top Of Wall Level
TH	Trail Hole
TL	Traffic Light
TD	Telegraph Pole
UTL	Unable To Lift
WM	Water Meter
WH	Water Level
WB	Building Valley Level

Disclaimer
Man Entry to sewers has not been undertaken. Depths, Pipesizes etc are measured from the ground. All sewers and inverts to be checked prior to any works commencing on site. Geomatic Surveys Limited are not responsible for manholes, services, information not surveyed which may have an impact on site development.
Boundaries shown are physical and may not represent legally conveyed ownership.
Tree species have only been identified using basic identification techniques. For precise tree species identification, it is recommended that a qualified arboriculturist is used prior to tree removal.

--	--	--	--	--

REV	DATE	DESCRIPTION	BY	APP
Sheet Layout				
Sheet 1				

Survey Information The Survey has been orientated to Ordnance Survey National Grid and datum using one central control station. No Scale Factor has been applied to the coordinates meaning that the survey is arbitrary and not true Ordnance Survey Coordinates.
--



Client
MPH ANCOATS LIMITED

Project Title	FORMER GARAGE SITE OLDHAM ROAD MANCHESTER
---------------	---

Drawing Title

TOPOGRAPHICAL SURVEY

Drawn ML	Checked IRH	Surveyed Date 11/03/2020
Date 13/03/2020	Scale 1:200 @ AO	Sheet No. SHEET 1 OF 1

Copyright © Geomatic Surveys Limited 2022




APPENDIX B
United Utilities Water Sewer Records



APPENDIX C

Existing Site Permeable Areas & Outline Attenuation Summary



OYM-REN-XX-XX-SK-C-00051-P01



APPENDIX D

Outline Drainage Strategy

NOTES

- DO NOT SCALE FROM THIS DRAWING. ANY AMBIGUITIES, OMISSIONS AND ERRORS ON DRAWINGS SHALL BE BROUGHT TO THE ENGINEERS ATTENTION IMMEDIATELY. ALL DIMENSIONS TO BE CHECKED/VERIFIED ON SITE.
- FOR SETTING OUT OF RWPS AND SVPS LOCATIONS REFER TO CURRENT ARCHITECT DRAWINGS. FOR SETTING OUT OF EXTERNAL LEVELS AND DRAINAGE REFER TO LANDSCAPE ARCHITECT CURRENT DRAWINGS. FOR ABOVE GROUND DRAINAGE REFER TO M&E CURRENT DRAWINGS.
- ALL ADOPTED DRAINAGE WORKS TO BE IN ACCORDANCE WITH THE LATEST EDITION OF 'SEWERS FOR ADOPTION', AND 'SEWERS FOR ADOPTION - A DESIGN AND CONSTRUCTION GUIDE - SMALL DEVELOPMENTS VERSION - SEPTEMBER 2013' AND UNITED UTILITIES APPROVED DETAILS. IF DISCREPANCIES ARE NOTED BETWEEN THE UU, SIA AND RENAISSANCE DRAWINGS THESE SHOULD BE BROUGHT TO THE ATTENTION OF RENAISSANCE FOR REVIEW.
- ALL NON-ADOPTED (PRIVATE) DRAINAGE WORKS TO BE IN ACCORDANCE WITH THE LATEST EDITION OF THE BUILDING REGULATIONS AND RENAISSANCE DETAILS.
- DRAINAGE SIZES AND FALLS TO BE AS INDICATED, AND NOT LESS THAN THE FOLLOWING MINIMAL FALLS:
FOUL
1/80 FOR SVP WITH WC
1/40 FOR SVP WITH NO WC
SURFACE
1/150 FOR 150 DIA PIPES
1/100 FOR 100 DIA PIPES
- ALL RWP GULLYS, CHANNEL DRAINS, TO BE TRAPPED AND WITH RODDABLE ACCESS.
- ALL RWPs AND SVPS TO BE RODDABLE
- ALLOW FOR 450 DIA PPICs TO PRIVATE AREAS U.N.O.
- ALL PPIC COVERS TO BE GRADE B125 IN FOOTPATHS/SOFT LANDSCAPING OR D400 IN TRAFFICKED AREAS
- SEWERS TO BE LAID IN MAXIMUM 3m LENGTHS UNLESS THERE IS A SPECIFIC OPERATIONAL NEED TO LAY LONGER AND THIS IS AGREED BETWEEN THE CONTRACTOR AND THE PIPE SUPPLIER.
- BEDDING AND BACKFILL MATERIAL TO CONFORM TO THE REQUIREMENTS OF THE WATER INDUSTRY SPECIFICATION 4-08092 (TABLE A2)
- ALL CONCRETE PIPES TO BE TO BS EN 1916 CLASS 120 (54kN/m).
- PLASTIC PIPES SHOULD HAVE THE BSI KITEMARK AND CERTIFIED TO BS EN 13476-1 AND CONFORM WITH WIS 4-35-01 OR BS 13476-2. PIPES LESS THAN OR EQUAL TO 500 DIA SHALL HAVE A SHORT TERM RING STIFFNESS NOT LESS THAN 8kN/m2.
- SULPHATE RESISTANT CEMENT (C20-DC2) AND PRECAST CONCRETE PRODUCTS MUST BE USED OR A LABORATORY REPORT PROVIDED DEMONSTRATING THAT SUCH PRECAUTIONS ARE NOT NECESSARY
- SEWERS TO BE LAID IN CLASS 'S' BEDDING WHERE MINIMUM COVER REQUIREMENTS ARE MET. WHERE MINIMUM COVER DEPTHS CANNOT BE ACHIEVED THEN A 150mm CONCRETE PROTECTION SLAB SHOULD BE PROVIDED.
- UNLESS NOTIFIED OTHERWISE CHANNEL DRAINS TO BE ACO M1500 0.0 OR SIMILAR APPROVED
- THE CONTRACTOR IS TO UNDERTAKE A FULL CCTV SURVEY AT COMPLETION OF THE PROJECT TO DEMONSTRATE THAT THE DRAINAGE IS CLEAN. ANY DEFECTS ARE TO BE CORRECTED BY THE CONTRACTOR PRIOR TO HANDOVER OF THE SYSTEM TO THE CLIENT
- THE DRAINAGE DESIGN, LAYOUT AND DETAILS ARE ALL SUBJECT TO APPROVAL FROM:
MANCHESTER CITY COUNCIL
UNITED UTILITIES S106 APPLICATION

KEY

- SITE BOUNDARY
- EXISTING UNITED UTILITIES COMBINED SEWER
- PROPOSED COMBINED WATER DRAINAGE NETWORK
- PROPOSED SURFACE WATER DRAINAGE NETWORK
- PROPOSED SURFACE WATER DRAINAGE NETWORK
- LINEAR DRAIN
- SURFACE WATER GULLY
- FOUL WATER GULLY
- ⊕ INDICATES RWP
- ⊕ INDICATES SVP

P01	FOR INFORMATION	26.08.20	JB	HG
Rev:	Description:	Date:	By:	Chkd:



OSBORNE YARD,
MANCHESTER

BELOW GROUND DRAINAGE
GENERAL ARRANGEMENT

FOR INFORMATION

Size:	Date:	Drawn by:	Designed by:	Checked by:
A1	AUG 20	JB	HG	HG

Scale:	1:100@A1	Project No:	2005-02				
Project:	Originator:	Volume:	Level:	Type:	Role:	Category/Number:	Rev:


OYM-REN-XX-XX-DR-C-00100-P01

LANDSCAPING AND PLANTING OF TREES/BUSHES/SHRUBS

THE LANDSCAPE ARCHITECT IS TO ENSURE THAT THE PLANTING PROPOSALS DO NOT IMPACT ON THE DRAINS AND SEWERS. REFER TO EXTRACT FROM SEWERS FOR ADOPTION WITH REQUIREMENTS.

A sewer or lateral drain should not be located closer to trees/bushes/shrubs than the canopy width at mature height, except where special protection measures are provided, in accordance with Clause B5.5. A tree should not be planted directly over sewers or where excavation onto the sewer would require removal of the tree. The following shallow rooting shrubs are generally suitable for planting close to sewers and lateral drains:

- Berberis candidula*; (Paleleaf barberry)
- Berberis julianae*; (Wintergreen barberry)
- Ceanothus burkwoodii*; (Californian lilac 'Burkwoodii')
- Cotoneaster dammeri*; (Bearberry cotoneaster)
- Cotoneaster skogholm*; (*Cotoneaster x suecicus*, 'Skogholm')
- Cytisus varieties or Sarothamnus*; ((Common or Scotch) Broom)
- Euonymus japonica*; (Japanese spindle)
- Euonymus radicans*; Variety of *Euonymus* (Fortune's spindle or wintercreeper)
- Mahonia varieties*; can be included in the genus *Berberis*, most common name is *M. aquifolium* (Oregon grape)
- Potentilla varieties*; most varieties are types of cinquefoil. Also includes Common tormentil, silverweed and barren strawberry
- Skimmia japonica*; (Skimmia)
- Spiraea japonica*; (Japanese spirea or Japanese meadowsweet)
- Veronica varieties*; (Speedwell)
- Viburnum davidii*; (David viburnum)
- Viburnum tinus*; (Lauristinus)





APPENDIX E
Micro Drainage Pre-Development Surface Water Run-Off

Renaissance Assoc.		Page 1
Carvers Warehouse 77 Dale Street Manchester M1 2HG	2006-06 Osborne Yard Greenfield Run-Off	
Date 24/08/2020 10:05 File	Designed by JB Checked by HG	
Innovyze	Source Control 2020.1	

ICP SUDS Mean Annual Flood

Input

Return Period (years)	2	SAAR (mm)	860	Urban	0.750
Area (ha)	0.092	Soil	0.450	Region Number	Region 10

Results 1/s

QBAR Rural 0.5
QBAR Urban 1.3

Q2 years 1.3

Q1 year 1.1
Q30 years 1.9
Q100 years 2.0

©1982-2020 Innovyze

Renaissance Assoc.		Page 1
Carvers Warehouse 77 Dale Street Manchester M1 2HG	2006-06 Osborne Yard Existing Run-Off	
Date 24/08/2020 10:08 File 2 Pipe Model (0.132ha).MDX	Designed by JB Checked by HG	
Innovyze	Network 2020.1	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	100	PIMP (%)	100
M5-60 (mm)	18.000	Add Flow / Climate Change (%)	0
Ratio R	0.359	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Time Area Diagram for Storm

Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.099	4-8	0.035

Total Area Contributing (ha) = 0.134

Total Pipe Volume (m³) = 0.353

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	10.000	0.125	80.0	0.134	5.00	0.0	0.600	o	150	Pipe/Conduit	
1.001	10.000	0.125	80.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	5.15	57.100	0.134	0.0	0.0	0.0	1.12	19.9	18.1
1.001	50.00	5.30	56.975	0.134	0.0	0.0	0.0	1.12	19.9	18.1

Renaissance Assoc.		Page 2
Carvers Warehouse 77 Dale Street Manchester M1 2HG	2006-06 Osborne Yard Existing Run-Off	
Date 24/08/2020 10:08 File 2 Pipe Model (0.132ha).MDX	Designed by JB Checked by HG	
Innovyze	Network 2020.1	

Area Summary for Storm

Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)
1.000	-	-	100	0.134	0.134	0.134
1.001	-	-	100	0.000	0.000	0.000
				Total	Total	Total
				0.134	0.134	0.134

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
1.001		58.000	56.850	0.000	0	0

Simulation Criteria for Storm


Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 0 Number of Storage Structures 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model	FSR	Profile Type	Summer
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	18.000	Storm Duration (mins)	30
Ratio R	0.359		

©1982-2020 Innovyze

Renaissance Assoc.		Page 5
Carvers Warehouse 77 Dale Street Manchester M1 2HG	2006-06 Osborne Yard Existing Run-Off	
Date 24/08/2020 10:08 File 2 Pipe Model (0.132ha).MDX	Designed by JB Checked by HG	
Innovyze	Network 2020.1	

30 year Return Period Summary of Critical Results by Maximum Outflow (Rank 1) for Storm

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coeffiecient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Synthetic Rainfall Details

```
Margin for Flood Risk Warning (mm) 300.0      DVD Status OFF
      Analysis Timestep   Fine Inertia Status OFF
      DTS Status          ON
```

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	1	60 Summer	30	+0%	30/60 Summer				57.432
1.001	2	60 Summer	30	+0%	30/60 Summer				57.218

Renaissance Assoc.		Page 6																																																												
Carvers Warehouse 77 Dale Street Manchester M1 2HG	2006-06 Osborne Yard Existing Run-Off																																																													
Date 24/08/2020 10:08 File 2 Pipe Model (0.132ha).MDX	Designed by JB Checked by HG																																																													
Innovyze	Network 2020.1																																																													
<u>100 year Return Period Summary of Critical Results by Maximum Outflow (Rank 1) for Storm</u> <u>Simulation Criteria</u> Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000 Hot Start Level (mm) 0 Inlet Coefficient 0.800 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000 Foul Sewage per hectare (l/s) 0.000 Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0 Number of Online Controls 0 Number of Storage Structures 0 Number of Real Time Controls 0 <u>Synthetic Rainfall Details</u> Rainfall Model FSR Ratio R 0.359 Region England and Wales Cv (Summer) 0.750 M5-60 (mm) 18.000 Cv (Winter) 0.840 Margin for Flood Risk Warning (mm) 300.0 DVD Status OFF Analysis Timestep Fine Inertia Status OFF DTS Status ON Profile(s) Summer and Winter Duration(s) (mins) 60 Return Period(s) (years) 1, 2, 30, 100 Climate Change (%) 0, 0, 0, 0 <table><tr><th>PN</th><th>US/MH Name</th><th>Storm</th><th>Return Period</th><th>Climate Change</th><th>First (X) Surge</th><th>First (Y) Flood</th><th>First (Z) Overflow</th><th>Overflow Act.</th><th>Water Level (m)</th></tr><tr><td>1.000</td><td>1</td><td>60 Summer</td><td>100</td><td>+0%</td><td>30/60 Summer</td><td></td><td></td><td></td><td>57.695</td></tr><tr><td>1.001</td><td>2</td><td>60 Summer</td><td>100</td><td>+0%</td><td>30/60 Summer</td><td></td><td></td><td></td><td>57.339</td></tr></table> <table><tr><th>PN</th><th>US/MH Name</th><th>Surcharged Depth (m)</th><th>Flooded Volume (m³)</th><th>Flow / Cap.</th><th>Overflow (l/s)</th><th>Half Drain Time (mins)</th><th>Pipe Flow (l/s)</th><th>Status</th><th>Level Exceeded</th></tr><tr><td>1.000</td><td>1</td><td>0.445</td><td>0.000</td><td>1.64</td><td></td><td></td><td>29.0</td><td>SURCHARGED</td><td></td></tr><tr><td>1.001</td><td>2</td><td>0.214</td><td>0.000</td><td>1.65</td><td></td><td></td><td>29.2</td><td>SURCHARGED</td><td></td></tr></table>			PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	1.000	1	60 Summer	100	+0%	30/60 Summer				57.695	1.001	2	60 Summer	100	+0%	30/60 Summer				57.339	PN	US/MH Name	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded	1.000	1	0.445	0.000	1.64			29.0	SURCHARGED		1.001	2	0.214	0.000	1.65			29.2	SURCHARGED	
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)																																																					
1.000	1	60 Summer	100	+0%	30/60 Summer				57.695																																																					
1.001	2	60 Summer	100	+0%	30/60 Summer				57.339																																																					
PN	US/MH Name	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded																																																					
1.000	1	0.445	0.000	1.64			29.0	SURCHARGED																																																						
1.001	2	0.214	0.000	1.65			29.2	SURCHARGED																																																						
©1982-2020 Innovyze																																																														