



A handwritten signature in black ink, appearing to read 'A L Jones'.

A L Jones
MDS Drainage Solutions

CCTV DRAINAGE SURVEY

32 Hampton Road Chorlton Manchester M21 9LA

Thursday, 25 November 2021

Prepared For Stephanie Bell

3 DS-327



REMARKS

MH 01 Upstream:

Requires root cutting and cipp patch liners.

MH 01 Downstream:

Requires root cutting at the affected joint and a cipp 150mm patch liner to prevent roots infiltrating the pipe again.

MH 01 Leg1:

Requires root cutting, patch liners and removal of a 32mm intruding waste pipe.

The current system is not currently fit for purpose and requires maintenance and repairs.

Root cutting and jetting required to regain maximum flow with no obstructions.

Cipp patch liners to secure joints and prevent further root ingress.

The root cutting and jetting to maintain the system would cost approximately £350:00/£450:00.

To install 11 X 0.5m/150mm patch liners would cost £3650:00.



LOCATION OF MH 01



CONDITION OF MH 01

Chamber channel was holding foul water when opened.