

Globe and Simpson, St Johns

Drainage and SuDS Strategy




Curtins Ref: 068166-CUR-00-XX-RP-C-92003

Revision: V01

Issue Date: 16 February 2022

Client Name: Allied London

Site Address: Globe & Simpson, St Johns Quarter, Manchester



 **curtins**

Curtins
Merchant Exchange
17-19 Whitworth Street West
Manchester, M1 5WG
Tel: 0161 236 2394
www.curtins.com

CIVILS & STRUCTURES • TRANSPORT PLANNING • ENVIRONMENTAL • INFRASTRUCTURE • GEOTECHNICAL • CONSERVATION & HERITAGE • PRINCIPAL DESIGNER
Birmingham • Bristol • Cambridge • Cardiff • Douglas • Dublin • Edinburgh • Glasgow • Kendal • Leeds • Liverpool • London • Manchester • Nottingham

Control Sheet

Rev	Description	Issued by	Checked	Date
V01	First Issue	CG	CG	16/02/2022

This report has been prepared for the sole benefit, use, and information for the client. The liability of Curtins with respect to the information contained in the report will not extend to any third party.

Author	Signature	Date
Chloé Grimsley BSc (Hons) Principal Engineer		16 February 2022

Reviewed	Signature	Date
Chloé Grimsley BSc (Hons) Principal Engineer		16 February 2022



Table of contents

1.0 Introduction 1

1.1 Project Background 1

1.2 Proposed Development..... 1

2.0 Drainage Strategy..... 3

2.1 Foul Water Drainage Strategy..... 3

2.2 Proposed Surface Water Drainage Strategy..... 3

3.0 SuDS/Drainage Verification..... 4

4.0 Maintenance 5

4.2 Components 6

4.3 Inspection and Manhole Chambers 7

4.4 Pipes 8

4.5 Gullies / Sump, Outlet and Access Units 8

4.6 Linear Slot Drainage 9

Appendix A

Proposed Site Layout

Appendix B

Masterplan Drainage Layout

Proposed Drainage Layout

Proposed Drainage Notes

Proposed Drainage Details Drawings

Appendix C

As Installed Drainage Photographs (Foul and Surface Water)

Appendix E

As Installed Drainage CCTV Survey (Surface Water)

Appendix F

Land Drainage Consent (Manchester City Council)

1.0 Introduction


1.1 Project Background

- 1.1.1 A Flood Risk Assessment (FRA) and Surface Water Drainage Statement referenced AR/NAK/3233/JULY 2015 was prepared by ROC Consulting in August 2016 for the St Johns Masterplan. Subsequently, a Drainage Strategy, referenced SJQ099-CUR-00-XX-RP-C-92001-V02 has been prepared by Curtins Consulting in May 2019, which develops the masterplan drainage strategy.
- 1.1.2 Planning Permission for the development was granted under Application No 121721/FO//2018, subject to conditions.
- 1.1.3 Curtins have been appointed by Allied London to provide a Drainage and SuDS Strategy to accompany the below ground drainage design.
- 1.1.4 This report has currently been prepared based on completion of the building only, therefore the report does not currently validate the drainage collection and conveyance points within the external areas. The system has been designed to provide capacity for the catchments areas associated with the external works, but the external areas are currently not yet installed. This report should be updated following completion of external works associated with this plot.

1.2 Proposed Development

- 1.2.1 The proposed development includes a 9-storey building comprising workspace (use Class B1) and flexible commercial workspace at ground level (Use Class A1, A3 and/or B1). Basement level comprises car parking and cycle parking and new public realm space around the building.
- 1.2.2 The proposed site plan is enclosed in **Appendix A**.
- 1.2.3 The site is located on New Quay Street in the city centre of Manchester, as shown at Figure 1 and forms part of the wider St Johns Masterplan.

Figure 1: Aerial Photograph (© Google 2022)



2.0 Drainage Strategy

2.1 Foul Water Drainage Strategy

- 2.1.1 A foul drainage strategy was prepared for the St Johns masterplan to set the principals of outfalls for each plot. The Masterplan strategy is referenced SJQ-099-CUR-XX-XX-DR-C-92550, can be found in Appendix B. The detailed design was developed based on the principals set out in the masterplan strategy.
- 2.1.2 A separate foul and surface water system is proposed for Globe and Simpson and will be retained as a private network. The foul drainage from the building will be connected to the existing public combined sewer adjacent to Quay Street, south-east of the site.
- 2.1.3 All drainage within basements are suspended below the ground floor slab and discharged to the private drainage network at high level. All drainage at basement level is drained to sumps and pumped into the gravity drainage system and is designed as part of the above ground drainage system by others.

2.2 Proposed Surface Water Drainage Strategy

- 2.2.1 Any new development site drainage should be designed in accordance with current best practice to provide adequate capacity not to flood for the critical 1 in 30-year storm event and flood water generated from up to the critical 1 in 100-year plus climate change storm event shall be constrained within the areas on site so not to cause damage to buildings, essential services or adjoining developments & services.
- 2.2.2 A surface water drainage strategy was prepared for the St Johns masterplan to set the principals of outfalls for each plot. The Masterplan strategy is referenced SJQ-099-CUR-XX-XX-DR-C-92550, can be found in Appendix B. The detailed design was developed based on the principals set out in the masterplan strategy.
- 2.2.3 A separate foul and surface water system is proposed for Globe and Simpson and will be retained as a private network. The surface water drainage from the building will be connected to the existing surface water drainage installed under the Manchester Goods Yard Plot (south of Globe and Simpson), which discharges below Water Street and into the Canal Basin west of Water Street.
- 2.2.4 The Land Drainage Consent for the Outfall Constructed as part of the site surface water discharge is enclosed in Appendix E.
- 2.2.5 Levels should be designed to fall away from buildings. An overland flow plan will be provided following receipt of final design and external levels.

3.0 SuDS/Drainage Verification

- 3.1.1 The Verification section has been developed with reference to the drainage design details and philosophy provided in section 3 of this report. Manchester City Council requirements are to verify the installation of the SuDS/Drainage element of the design to confirm by Photographic record that this has been installed
- 3.1.2 **The report should be updated following completion of the external works areas and drainage associated with this plot.**
- 3.1.3 The proposals do not include any SuDS features within this plot. The drainage system for this plot includes traditional pipework, chambers, gullies and channels. Photographic record of the below ground drainage is enclosed in Appendix C.
- 3.1.4 The CCTV Survey for the surface water drainage for this plot is enclosed in Appendix D.
- 3.1.5 The CCTV Survey for the foul water drainage for this plot should be provided once available to confirm satisfactory condition.

4.0 Maintenance

- 4.1.1 All drainage within the site will be maintained by the land owner as a private network. A suitable maintenance strategy should be adopted to ensure the drainage network is cleaned regularly and the routine maintenance and cleansing regime should be documented.
- 4.1.2 This section is intended to give an overview of the operation and maintenance for the drainage features included with the drainage strategy and in relation to typical details. Where proprietary products are specified, the manufacturer's instructions and recommendations should be followed in priority to this document unless specifically noted otherwise due to project constraints.
- 4.1.3 The recommended operations and frequencies are typical only and should be more frequent initially to ensure that there are no unforeseen issues with the operation and then adjusted to suit the site requirements.
- 4.1.4 It is recommended that the drainage system is inspected as a minimum twice a year, with the system also being inspected after any major storm event. Significant sediment deposition is likely in areas used for storage, so a post clean-up operation may be required including the removal of litter, vegetation, sewerage debris and larger objects.
- 4.1.5 The surface water network has been designed to accommodate the 1 in 100-year storm rainfall event plus an allowance for climate change particular to the requirements of the site. It may be that the exceedance flows above the 1 in 30-year storm rainfall event are stored within the site partially above ground, on non-habitable external landscaping, parking or other space. As the flows are generally being attenuated on site and within SuDs features there will be a period of time after storm events where the network is still partially or fully surcharged and is draining down. Where this surcharging is still present after 48hrs appropriate action should be taken as noted in this section.

4.2 Components

4.2.1 The following components have been included within the drainage design for the proposed development:

- Inspection, Manhole and Catchpit Chambers
- Pipes
- Gullies / Sump, Outlet and Access Units **(to be installed)**
- Linear Slot Drainage **(to be installed)**

4.2.2 The maintenance strategy should be adopted to ensure the drainage network is cleaned regularly and the routine maintenance and cleansing regime should be documented.

4.2.3 Maintenance of the drainage network will be the responsibility of an on-site facilities management team.

4.2.4 The maintenance of the drainage network outside of the Ownership Boundary and any public sewer assets will be the responsibility of Manchester City Council and United Utilities.

4.2.5 The current completion date for the development is unknown. The maintenance scheduling should begin from the completion date.

4.2.6 It is recommended that the drainage system is inspected as a minimum twice a year, with the system also being inspected after any major storm event.

4.2.7 Significant sediment deposition is likely in areas used for storage, so a post clean-up operation may be required including the removal of litter, vegetation, sewerage debris and larger objects.

4.2.8 Long-term management practices include monthly sweeping of external paved areas. The sweeping program will remove sand and contaminants directly from paved surfaces before they become mobilised during storm events and transported to the drainage system.

4.2.9 During the winter months, drainage features such as gullies and channels should be cleared of ice, snow, debris or litter

4.2.10 A copy of the final construction drainage layout should be provided in the final Operations and Maintenance Manual. Reference should be made to the proposed drainage layout: Curtins drawing SJQ-102-CUR-00-XX-DR-C-92500.

4.3 Inspection and Manhole Chambers

- 4.3.1 The locations of the chambers are indicated on Curtins drainage drawing SJQ-102-CUR-00-XX-DR-C-92500.
- 4.3.2 Access points have been located at the head of each run, at a change in direction and at a change of pipe size in accordance with Building Regulations Part H.
- 4.3.3 The appropriate barriers and signage should be installed during any opening of manholes to warn pedestrians.
- 4.3.4 Existing manholes are subject to existing access procedures. Typically chambers with a minimum working space of 900mm can be accessed by personnel; however, a winch must be used. Where 1050mm of working space is provided, manholes should be accessed using steps and where 1200mm working space is provided; manholes should be accessed using ladders, this is in accordance with Building Regulations Part H.
- 4.3.5 When accessing chambers, the latest Health and Safety legislation should be adhered to.
- 4.3.6 The appropriate health and safety equipment must be used when accessing manholes. Confined space certificates must be held by any personnel entering a manhole and the appropriate permits should be obtained from the Facilities Maintenance Manager prior to any access.
- 4.3.7 Sediment/material removal should be undertaken in consultation with the environmental regulator to confirm appropriate protocols; especially where run-off is taken from potentially contaminated areas.

Maintenance Schedule	Required Action	Frequency
Monitoring (to be undertaken more regularly within the first year of operation and adjusted as required)	Initial inspection should be provided as post construction CCTV survey.	N/A
	Inspect for evidence of poor operation via water level in chambers. If required take remedial action.	3-monthly, 48 hours after large storms.
Occasional maintenance	Check and remove large vegetation growth near pipe runs.	6 monthly
Remedial actions	Rod through poorly performing runs as initial remediation.	As required.
	If continued poor performance jet and CCTV survey poorly performing runs.	As required.

	Seek advice as to remediation techniques suitable for the type of performance issue and location.	As required If above does not improve performance.
--	---	--

4.4 Pipes

- 4.4.1 The locations of the pipes are indicated on Curtins drainage drawing SJQ-102-CUR-00-XX-DR-C-92500. Pipes can be cleaned using drain cleaning rods or drain cleaning jets, accessed from inspection chambers and manholes.

Maintenance Schedule	Required Action	Frequency
Monitoring (to be undertaken more regularly within the first year of operation and adjusted as required)	Initial inspection should be provided as post construction CCTV survey.	N/A
	Inspect for evidence of poor operation via water level in chambers. If required take remedial action.	3-monthly, 48 hours after large storms.
Occasional maintenance	Check and remove large vegetation growth near pipe runs.	6 monthly
Remedial actions	Rod through poorly performing runs as initial remediation.	As required.
	If continued poor performance jet and CCTV survey poorly performing runs.	As required.
	Seek advice as to remediation techniques suitable for the type of performance issue and location.	As required If above does not improve performance.

4.5 Gullies / Sump, Outlet and Access Units

- 4.5.1 The locations of the gullies or sump outlet units are indicated on Curtins drainage drawing SJQ-102-CUR-00-XX-DR-C-92500.
- 4.5.2 Gullies and sump outlet units installed have removable covers to allow cleaning and clearing of debris and silt. The appropriate barriers and signage should be installed during any opening of gullies to warn pedestrians.

- 4.5.3 Sediment/material removal should be undertaken in consultation with the environmental regulator to confirm appropriate protocols; especially where run-off is taken from potentially contaminated areas.


4.6 Linear Slot Drainage

- 4.6.1 Linear channel drainage systems should be inspected and cleaned in accordance with the manufacturer's maintenance guide.
- 4.6.2 Outlet units can be cleaned through the use of a high-pressure hose; this can be fed into the channel system through access units strategically placed along the channel run. The throat section of channel units should be kept clear at all times to ensure uninterrupted flow of surface water into the drainage channel and any debris within the throat should be removed.
- 4.6.3 Manufacturers details will be included once product selection confirmed.

Appendix A

Proposed Site Layout

P:\2018\1882 ST JOHN'S\01 CAD\02 SHEET LAYOUT\1959_GLOBE & SIMPSON\STAGE 4\ISJQ-102-EXA-XX-L00-DR-L-000100.DWG



KEY

Existing hard landscape

- Globe & Simpson works boundary
- Existing manholes to be reinstated as required

Proposed hard landscape

- Macadam
Highways' grade to Engineers' specification.
- Natural stone type 1
Crystal black granite, Size: W:250 x random length x D:75mm with 6mm staggered joints.
Finish: Flamed. Supplier: Hardscape or similar approved
- Natural stone type 2
Crystal black/Mist granite, Size: W:450 x L: 900 x D:75mm with 6mm staggered joints.
Finish: Bush hammered. Supplier: Hardscape or similar approved
- Natural stone type 3
Mist granite, Size: W:250 x random length x D:75mm with 6mm staggered joints.
Finish: Flamed. Supplier: Hardscape or similar approved
- Natural stone type Special
Crystal black, Size: W: as shown x random length x D:75mm with 6mm staggered joints.
Finish: Flamed. Supplier: Hardscape or similar approved
- Granite kerb
Mist granite Size: 125W X 915L x 255mmH
Finish: Flamed. Supplier: Hardscape or similar approved
- Granite transitional drop kerb (L+R transitions)
Mist granite Size: 125W X 915L x 255-150mmH
Finish: Flamed. Supplier: Hardscape or similar approved
- Blister granite paving
Crystal black Size: 400 X 400 x 50mm
Finish: Flamed. Supplier: Hardscape or similar approved

- Corduroy granite paving
Crystal black Size: 400 X 400 x 75mm
Finish: Flamed. Supplier: Hardscape or similar approved
- Granite step
Mist granite, Size: W:300 x 1000L x H:150mm Finish: Flamed. Supplier: Hardscape or similar approved
- Road marking paint to loading bays
Paint specification to BS6044:1987
Colour: White. Location indicative.
- Furniture element
Timber top with metal base integrated with vent extract, sizing: As shown. Supplier: Logic or similar approved, refer to drawing SJQ-102-EXA-XX-L00-DR-L-000603 for details
CCTV
Building mounted to M&E specification and location to be verified by M&E consultant
- Extent of basement
For details refer to engineer's drawings
- Concrete upstand/slab penetration
For details refer to engineer's drawings
- Building overhang
To architectural details
- Semi dome top bollard
1000H (above FGL) x 101.60mm
Material: galvanised steel powder coated black
Supplier: Bailey Street Scene or similar approved
- Fold down post
620H (above FGL) x 630mm
Material: galvanised steel powder coated black
Supplier: Bailey Street Scene or similar approved
- Tree surround (grille)
Size: Outer Ø1600mm inner Ø600mm
Colour: powder coated black Supplier: Green Blue Urban or similar approved.
- Street cycle parking
50x50x6mm sbs cycle stand stainless steel with pinto finish, 750mm high x 750mm width
supplier: logic or similar approved
- In ground power supply
Approximate location of inground external power supply & drainage point to M&E specification
- Proposed manholes
Black circular manhole covers. Cast iron access manhole cover & frame 600mmØ - B125 class. As supplied by Drainage Superstore or similar approved.
- Escofet column lighting
Single head ball LED carbon steel tube, hot dip galvanised. Finish: Black forge
Height to be confirmed by M&E Engineer. Supplier: Escofet or similar approved
Product location to be coordinated with slab levels and tree pits
- In-ground up-lighting
To M&E specification

- Digital advertising signage
Outdoor led digital unit forum model or equivalent to M&E specification
- Fairy lights to trees
Specification lbc. Integrated power provision to M&E specification
- Stainless steel studs
Size: 25mm, low dome.
- Cycleway demarcation studs
Stainless steel satin finish, 5mm low dome top, ground fixed with fixing stub, cycleway image etched infill, land-mark landscaping systems or similar approved
- Self-compacting bins
To client specification. R= recycling G=General waste
- Indicative gully locations
To engineer's details, final locations subject to slab survey result
- Maintenance zone

- NOTE:
All surface finished & product details subject to final coordination with Allied London & sign off.
- Soft landscape
- Trees
As specified in drawing SJQ-102-EXA-XX-L00-DR-L-000200.
For advanced urban tree pit system refer to drawing SJQ-102-EXA-XX-L00-DR-L-000701. In-ground lighting to M&E specifications
 - Trees in free standing planters
Multi-stem trees H:900mm x 10000 free standing forfitable planter. Pinto finish as supplied by Logic or similar approved
 - Arborraft cell system
Indicative arborraft cell layout to be validated by supplier. For advanced urban tree pit system refer to drawing SJQ-102-EXA-XX-L00-DR-L-000701

No dimensions are to be scaled from this drawing.
All dimensions are to be checked on site.
Area measurements for indicative purposes only.

This drawing is the property of Exterior Architecture Ltd.
No part of the drawing may be reproduced in any manner without permission from Exterior Architecture Ltd.

Client
ALLIED
LONDON

NOTE:
Structural penetration points and up-stands subject to project engineer sign off and design.
Lighting columns, pop ups, smart bins in abeyance and subject to project team coordination and client sign off.

P10	TREE UPDATED TO WATER ST	15.09.2020
P09	STAGE 4 COORDINATION	11.09.2020
P08	STAGE 4 COORDINATION	10.01.2020
P07	STAGE 4 COORDINATION	17.12.2019
P06	STAGE 4 COORDINATION	09.12.2019
P05	STAGE 4 COORDINATION	25.11.2019
P04	STAGE 4 COORDINATION	07.11.2019
P03	STAGE 4 COORDINATION	01.11.2019
P02	STAGE 4 COORDINATION	31.10.2019
P01	INITIAL ISSUE	24.10.2019
Rev	Description	Date

**EXTERIOR
ARCHITECTURE**
LONDON
Unit 17.1, The Leather Market, 11-13 Weston Street, London, SE1 3ER
MANCHESTER
Studio 537, The Royal Exchange, St Anns Square, Manchester, M2 7DH
E-MAIL office@exteriorarchitecture.com
WEB www.exteriorarchitecture.com

Project title
ST JOHN'S - GLOBE & SIMPSON

Drawing title
ST JOHN'S - GLOBE & SIMPSON
GENERAL ARRANGEMENT

Issued By	Manchester	T: 0161 850 8101
Scale	1:200 @ A1	Drawn ExA
Status	STAGE 4	Checked SPL
Date	24.10.2019	Approved JM
Drawing number	SJQ-102-EXA-XX-L00-DR-L-000100	Revision P10


Appendix B

Masterplan Drainage Layout

Proposed Drainage Layout

Proposed Drainage Notes

Proposed Drainage Details Drawings



KEY:

PLOT BOUNDARIES

EXISTING PUBLIC COMBINED SEWER

EXISTING PUBLIC COMBINED SEWER TO BE ABANDONED

EXISTING PUBLIC SURFACE SEWER

PROPOSED SURFACE WATER DRAINAGE

PROPOSED FOUL WATER DRAINAGE

PROPOSED COMBINED PUBLIC SEWER

GATIC SLOT DRAIN, SIZED AS SHOWN

GATIC SLOT DRAIN ACCESS BOX

GATIC SLOT DRAIN SILT BOX

SMART FILTER CHAMBER

UNDER SLUNG DRAINAGE TO BE DESIGNED AND CONFIRMED BY M&E ENGINEER

BACKDROP REQUIRED TO MANHOLE

EXISTING BRIDGE STRUCTURE, EXACT POSITION AND SETTING OUT TO BE CONFIRMED.

SURFACE WATER PLOT CONNECTION

FOUL WATER PLOT CONNECTION

SURFACE WATER WORKS (PROGRAMME OF WORKS TBC)

SURFACE WATER PPIC

FOUL WATER PPIC

REFERENCE OF CONNECTION THROUGH CAPPING BEAM/WALL

PROPOSED SEWER DIVERSION BY OTHERS

FLAP VALVE TO BE INSTALLED TO INCOMING PIPE AS INDICATED. ALTHON FLAP VALVE OR SIMILAR APPROVED, TYPE TBC.

PROPOSED GULLY WITH 150mm CONNECTION

PLOT BOUNDARIES SHOWN ARE INDICATIVE. TO BE UPDATED FOLLOWING RECEIPT OF FINAL INFORMATION. TO BE CONFIRMED BY LANDSCAPE ARCHITECT/ALLIED LONDON.

FOR PIPES PASSING THROUGH WALL LEVELS REFER TO SCHEDULE.

REFER TO DRAWINGS 92555 AND 92556 FOR SURFACE AND FOUL WATER CATCHMENT LAYOUTS. THESE SHOW THE DIRECTION IN WHICH FOUL FLOWS AND SURFACE WATER HARD STANDING/ROOF AREAS ARE TO BE DIRECTED TO. THE DESIGN WILL REQUIRE UPDATING SHOULD ANY OF THESE CATCHMENTS CHANGE.

FOR SHALLOW DRAINAGE I.E. SLOT DRAINAGE ETC REFER TO PLOT DRAINAGE PACKAGE OF WORKS. THIS DRAWING IS TO BE CO-ORDINATED WITH PLOT DRAINAGE DESIGN.

REFER TO DRAWING 92563 FOR MANHOLE SCHEDULE AND DETAILS, PIPES PASSING THROUGH WALL SCHEDULE AND SMART FILTER CHAMBER DETAILS.

FOR BACKDROP INVERT LEVELS REFER TO MANHOLE SCHEDULE.

GENERAL NOTES:

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND ENGINEERS DRAWINGS AND SPECIFICATIONS.
- DO NOT SCALE THIS DRAWING. ANY AMBIGUITIES, OMISSIONS AND ERRORS ON DRAWINGS SHALL BE BROUGHT TO THE ENGINEERS ATTENTION IMMEDIATELY. ALL DIMENSIONS MUST BE CHECKED / VERIFIED ON SITE.
- ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE.

DRAINAGE NOTES

PROPOSED COMBINED SEWER DIVERSION SUBJECT TO SECTION 185 AGREEMENT WITH UNITED UTILITIES. REFER TO DRAWING 067376-CUR-00-XX-DR-C-92501.

PROPOSED SURFACE WATER CATCHMENT DRAWING 067376-CUR-00-XX-DR-C-92555.

PROPOSED FOUL WATER CATCHMENT DRAWING 067376-CUR-00-XX-DR-C-92556.

PROPOSED FOUL CONNECTIONS TO COMBINED PUBLIC SEWER WILL BE SUBJECT TO A SECTION 106 AGREEMENT.

PROPOSED SURFACE WATER OUTFALL SUBJECT TO AGREEMENTS WITH PEEL HOLDINGS. MAX VELOCITY 3m/s.

LAND DRAINAGE CONSENT REQUIRED FROM MANCHESTER CITY COUNCIL LLFA FOR WORKS TO EXISTING RIVER WALLS TO CONSTRUCT OUTFALLS.

PROPOSED SURFACE WATER SEWERS WITHIN ADOPTED HIGHWAY SUBJECT TO LICENCE FROM MANCHESTER CITY COUNCIL.

SURFACE DRAINAGE, MANHOLE COVER AND INVERT LEVELS SHOWN ARE INDICATIVE ONLY AND ARE SUBJECT TO CHANGE FOLLOWING RECEIPT OF PLOT DESIGNERS INFORMATION.

PUBLIC SEWER REQUIREMENTS WITHIN GRAPE STREET/ZONE 8 TO BE CONFIRMED BY ZONE 8 PLOT DESIGNERS.

PROPOSED DRAINAGE SUBJECT TO CHANGE FOLLOWING CO-ORDINATION WITH EXISTING AND PROPOSED SERVICE ROUTES.

ALL EXTERNAL TRAFFICKED AREAS AND TRAFFICKED AREAS BEING DRAINED VIA SUSPENDED DRAINAGE, NOT PASSING THROUGH SMART FILTER CHAMBER TO RECEIVE A LEVEL OF SURFACE WATER TREATMENT PRIOR TO DISCHARGE. PLOT DESIGNER TO CONFIRM TYPE.

PPICS TO BE SET TO APPROPRIATE LEVEL TO COLLECT PLOT DRAINAGE. REFER TO SCHEDULE.

DRAINAGE PROPOSALS WITHIN GRAPE STREET ARE SUBJECT TO PHASING OF WORKS. CO-ORDINATION REQUIRED WITH SOUTH VILLAGE (ZONE 4).

DRAINAGE RUNS TO HAVE CLASS 'S' BEND AND SURROUND. DRAINAGE RUNS WILL REQUIRE CONCRETE PROTECTION WHERE COVER TO PIPE IS LESS THAN 1.2m. FINISHED LEVELS WILL IMPACT DEPENDING ON DEPTH.

P14	F9 LOCATION AMENDED	10.08.20	ATL	ATL
P13	F111, F111A UPDATED, F9A ADDED	10.07.20	ATL	CD
P12	UPDATED FOR T1 PLOT DRAINAGE	12.12.19	AH	CD
P11	DRAINAGE UPDATE	30.10.19	CD	CG
P10	S123 REMOVED. LEVELS UPDATED.	07.10.19	CD	CG
P09	MANHOLES F7 & F8 RELOCATED	02.08.19	CG	CG
P08	UPDATE FOLLOWING PLOT DEVELOPMENTS	25.07.19	CD	CG
P07	UPDATED TO SUIT PHASED CONSTRUCTION PACKAGE OF WORKS	13.05.19	CD	CG
P06	STAGE 4 UPDATE	04.04.19	CD	CG
P05	STAGE 4 UPDATE	19.02.19	CD	CG
P04	STAGE 4	21.08.18	CD	CG
P03	STAGE 3 - UPDATE	04.05.18	CD	CG
P02	STAGE 3	18.02.18	CD	CG
P01	FIRST ISSUE	22.12.17	CD	CG

Rev:	Description:	Date:	By:	Chkd:

STAGE 4

ST JOHNS

PROPOSED DRAINAGE LAYOUT

Size:	Date:	Drawn By:	Designed By:	Checked By:
A1	22.12.17	CD	CD	CG

Scale: 1:500

Project No:	Originator:	Zone:	Level:	Type:	Discipline:	Category / Number:	Rev:
SJQ-099- CUR - XX - XX - DR - C -	92550	- P14					

curtins

Merchant Exchange, 17-19 Whitworth Street West, Manchester, M1 5WG
0161 235 2384
manchester@curtins.com
www.curtins.com


Civils & Structures • Transport Planning • Environmental • Infrastructure • Geotechnical • Conservation & Heritage • Principal Designer
Birmingham • Bristol • Cambridge • Cardiff • Douglas • Dublin • Edinburgh • Glasgow • Kentville • Leeds • Liverpool • London • Manchester • Nottingham

Status:



Project:

Dwg Title:

U:\m\p\Projects\067001 - 068000\067216 - St Johns Infrastructure OMS 4 Production\MS Notes & Drawings - Civil-CCAD




TYPICAL TYPE 2 CONCRETE MANHOLE (PCC) DETAIL
MAX. DEPTH FROM COVER LEVEL TO SOFFIT OF PIPE 3.0m
(SCALE 1:20)




Sited in soft landscaped areas with standard round cover
Sited in soft landscaped areas with standard round cover

TYPICAL INSPECTION CHAMBER (IC) DETAIL
MAX DEPTH 1.2m




CLASS S - 360° GRANULAR SURROUND
PIPE BEDDING DETAIL
(SCALE 1:20)

CLASS Z - CONCRETE BED AND
SURROUND PIPE BEDDING DETAIL
(COVER < 900mm IN VEHICULAR LOADING AND OPEN FIELD.
(COVER < 600mm ELSEWHERE EXCEPT UNDER BUILDINGS.)
(SCALE 1:20)



INSPECTION CHAMBER BASE DETAILS
(SCALE 1:20)



Telescopic IC sited in soft landscaped areas
TYPE 3 DEEP INSPECTION CHAMBER (IC) DETAIL
DEPTHS BETWEEN 1.2m AND 3.0m
(SCALE 1:20)

10. UNLESS NOTED OTHERWISE, ALL MORTAR TO BE CLASS 1 (1:3 CEMENT:SAND).
11. LIMESTONE PIPE BEDDING WILL NOT BE PERMITTED IN ACIDIC GROUNDWATER CONDITIONS. REFER TO CONTRACT SPECIFICATION FOR SPECIFIC DETAILS.
12. CUT ENDS OF ANY REINFORCED CONCRETE PIPES ARE TO BE TREATED WITH EPOXY RESIN PAINT/MORTAR.
13. CONSTRUCTION JOINTS IN CONCRETE SURROUND MUST NOT BE WITHIN 150MM OF CHAMBER RING JOINTS.
14. FLEXIBLE JOINTS SHALL BE PROVIDED AS CLOSE AS POSSIBLE TO THE OUTSIDE FACE OF ANY STRUCTURE INTO WHICH IT IS BUILT. (SEE TABLE BELOW).
- | PIPE DIAMETER (mm) | MAX DIM "A" (mm) | MAX DIM "B" (mm) |
|--------------------|------------------|------------------|
| 150 | 150 | 500-750 |
| 225-450 | DIA | 500-750 |
| 525-600 | DIA | < 1000 |
15. IN CLAY, SOIL, PIPE TRENCHES ARE TO BE BACKFILLED WITH CLEAN GRANULAR HARDWARE 75MM DOWN.
16. CONNECTIONS INTO MANHOLES SHALL BE CONSTRUCTED AT SOFFIT LEVEL, UNLESS DETAILED DIFFERENTLY ON CONSTRUCTION DRAWINGS.
17. SUITABLE MATERIAL/SELECTED FILL SHOULD BE READILY COMPACTABLE, FREE FROM TIMBER, FROZEN MATERIAL, VEGETATION AND FOREIGN MATTER. IT SHOULD EXCLUDE ANY LUMPS OF CLAY RETAINED ON A 100MM SIEVE AND STONES RETAINED ON A 40MM SIEVE.
18. CONCRETE BENCHING AND PIPE SURROUND SHALL BE PLACED IN A SINGLE CONTINUOUS OPERATION FROM THE TOP OF THE BASE SLAB TO TOP OF BENCHING AND PIPE SURROUND.
19. PCC COVER SLABS AND MANHOLE RINGS TO BE MANUFACTURED TO BS-EN 1917 AND BS 5911:3 AND KITEMARKED.
20. PCC COVER SLABS TO HAVE 600X750MM CLEAR OPENING UNLESS STATED OTHERWISE WITHIN THIS SCHEDULE AND BE MANUFACTURED TO BS-EN 1917 AND BS 5911:3.
21. CORBEL SEATING UNITS TO BE MANUFACTURED TO BS-EN 1917 AND BS 5911:3 TO BE USED ECCENTRIC OVER SLAB OPENING TO REDUCE FRD. 600X600MM OPENING IN IRONWORK TO 600X750MM OPENING IN COVER SLAB WHERE APPLICABLE.
22. ALL CONCRETE PIPEWORK TO BE MANUFACTURED TO BS-EN 1916 AND BS 5911:1 AND STRENGTH CLASS 120 AND KITEMARKED.
23. ALL CLAY PIPEWORK SHALL BE EXTRA STRENGTH CLAYWARE TO BS 295 AND BS 65 (SW PIPES ONLY).
24. THE CONTRACTOR MAY ELECT TO USE REINFORCES UPVC PIPES COVERED BY BS-EN 1401:1 FOR DIAMETERS UP TO AND INCLUDING 300MM.
25. ALL PROPRIETARY PRODUCTS ARE TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS GUIDANCE AND INSTRUCTIONS.

GENERAL NOTES:

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND ENGINEERS DRAWINGS AND SPECIFICATIONS.
- ALL DIMENSIONS ARE IN MILLIMETRES.
- ALL ADAPTABLE DRAINAGE WORKS INCLUDING WORKS TO EXISTING PUBLIC SEWERS TO BE UNDERTAKEN IN ACCORDANCE WITH "SEWERS FOR ADOPTION 7th EDITION" AND "CIVIL ENGINEERING SPECIFICATION FOR THE WATER INDUSTRY 7th EDITION" AND CONSTRUCTED TO THE RELEVANT STATUTORY UNDERTAKERS DETAILS.
- ALL PRIVATE DRAINAGE WORKS TO BE IN ACCORDANCE WITH "CIVIL ENGINEERING SPECIFICATION FOR THE WATER INDUSTRY 7th EDITION", BS EN 752 2008 'DRAIN AND SEWER SYSTEMS OUTSIDE BUILDINGS' AND THE BUILDING REGULATIONS APPROVED 'DOCUMENT H'.
- THE SIZES OF MANHOLES STATED ARE MINIMUM. IF TWO OR MORE PIPES ENTER THE MANHOLE, THE CHAMBER SIZE MUST BE SUFFICIENT TO ACCOMMODATE THE ADEQUATE BENCHING WIDTHS. ALL PIPES BUILT INTO THE MANHOLE INVERT SHOULD BE INSTALLED WITH SOFFITS LEVEL.
- THE CONTRACTOR SHALL GIVE AT LEAST ONE WORKING DAYS NOTICE TO THE ENGINEER TO ALLOW OPPORTUNITY TO EXAMINE ANY FORMATION OR ANY WITNESS TESTING.
- ALL SOFT SPOTS TO BE REMOVED FROM THE BOTTOM OF EXCAVATIONS AND TO BE REFILLED TO FORMATION LEVEL WITH THE SAME MATERIAL AS PERMANENT WORKS WHICH REST IN IT.
- ALL CONCRETE AND CONCRETE PRODUCTS SHALL SATISFY THE SULPHATE CLASSIFICATION ADVISED IN THE SITE INVESTIGATION (BS-EN 206 STATES PORTLAND LIMESTONE CEMENT IS NOT PERMITTED). ALL CONCRETE GRADES STATED ON THIS DRAWING ARE THE MINIMUM STRENGTH REQUIREMENTS. THEY MUST BE CAPABLE OF RESISTING THE REQUIRED SULPHATE CLASSIFICATION.
- MANHOLE COVER CLASSIFICATION TO BE IN ACCORDANCE WITH BS-EN 124 AS SHOWN IN THE TABLE BELOW.

COVER TYPES TO EN124		
CLASS	LOAD (T)	APPLICATIONS
A	1.5	PEDESTRIAN ONLY AREAS
B	12.5	CAR PARKS
C	25	SERVICE ROADS NOT EXTENDING MORE THAN 500mm FROM KERB FACE INTO THE CARRIAGEWAY.
D	40	ROADS, LOADING AREAS AND CONCRETE HARDSTANDINGS.
COVER SIZES		
TYPE	LENGTH AND WIDTH (mm)	CIRCULAR (mm)
SMALL ACCESS FITTING	150 x 100	150
LARGE ACCESS FITTING	225 x 100	-
INSPECTION CHAMBER	450 x 450	450
MANHOLE FOR TYPE B MANHOLE WITH <1.8m INTERNAL HEIGHT	600 x 600 685 x 1220 MULTIPLE	600

CONCRETE TYPES			
LOCATION	TYPE	MAX AGGREGATE	NOMINAL SLUMP
ALL CONCRETE FOR DRAINAGE	GEN 3	20mm	S3

RATE OF SAMPLING FOR COMPRESSIVE STRENGTH TEST ONE SET OF CUBES PER 20cu m OR 10 BATCHES OF CONCRETE WHICHEVER REPRESENTS THE LESSER VOLUME, BUT NOT LESS THAN ONE FOR EACH DAY OR USE.
A SET OF CUBES IS TO COMPRISE THREE CUBES, ONE FOR TESTINE AT 28 DAYS, ONE FOR TESTING AT 7 DAYS AND A SPARE. THE NUMBER OF SPARE CUBES AND CUBES FOR TESTING AT 7 DAYS MAY BE REDUCED AT THE CONTRACTORS RISK.

CONSTRUCTION RECORD - FINAL CONSTRUCTION
THE INFORMATION IS BASED ON CONFIRMATION FROM THE CONTRACTOR OF THE INSTALLED WORKS. THERE MAY BE VARIATIONS ON SITE WHICH ARE NOT REFLECTED ON THIS DRAWING AND HAS NOT BEEN VERIFIED BY CURTINS.

IT IS NOTED THAT THE WORKS ON THIS DRAWING REFLECT THE WORKS COVERED UNDER THE LEND LESE CONTRACT ONLY. EXTERNAL DRAINAGE WORKS ASSOCIATED WITH THE FINAL COMPLETED PLOT WILL BE UPDATED UPON SEPARATE DRAWINGS.

CR	FINAL CONSTRUCTION ISSUE	16.02.22	CG	CG
C01	ISSUED FOR CONSTRUCTION	16.09.20	AH	CD
P03	STAGE 4 ISSUE	06.12.19	AH	CD
P02	STAGE 4 DRAFT UPDATE	08.11.19	AH	CD
P01	STAGE 4 DRAFT	19.07.19	CD	CG
Rev:	Description:	Date:	By:	Chkd:



Merchant Exchange, 17-19 Whitworth Street West, Manchester, M1 5WG
0161 238 2384
manchester@curtins.com
www.curtins.com

Civils & Structures • Transport Planning • Environmental • Infrastructure • Geotechnical • Conservation & Heritage • Principal Designer
Birmingham • Bristol • Cambridge • Cardiff • Dublin • Edinburgh • Glasgow • Kentish • Leeds • Liverpool • London • Manchester • Nottingham

Status:

FINAL CONSTRUCTION ISSUE

Project:

ST JOHNS

Dig Title:


BLOCK C - G&S DRAINAGE DETAILS SHEET 1

Size:	Date:	Drawn By:	Designed By:	Checked By:
A1	19.07.19	CD	CD	CG


Scale: NTS

Project No: Originator: Zone: Level: Type: Discipline: Category / Number: Rev:

SJQ-102 -CUR- 00 -XX -DR - C - 92502 - CR




SHOWN WITH CAST
DOUBLE TRIANGLE
GRATING AND
CAST FRAME.



GATIC SLOTDRAIN
KNOCK OUTS

REFER TO GATIC DETAILS, AVAILABLE
ONLINE, FOR DIMENSIONS AND SIZING.

ACCESS BOX WITH
DOUBLE TRIANGULAR
GRATING 5




PIPE OUTLET
KNOCK-OUTS.

FOLD-OUT
TABS USED
AS COLLAR.

END CAP


END CAPS		
DESCRIPTION	PART NUMBER	PIPE OUTLE SIZES (mm)
100mm END CAP / OUTLET	00162	92
150mm END CAP / OUTLET	00163	115
225mm END CAP / OUTLET	00164	115/165/205
300mm END CAP / OUTLET	00165	115/165/205/255
350mm END CAP / OUTLET	00166	115/165/205/255/320
400mm END CAP / OUTLET	00167	115/165/205/255/320/360
500mm END CAP	00168	N/A
600mm END CAP	00169	N/A



Where X is less than 1
metre concrete fill
trench to this level

TYPICAL DETAILS WHERE DRAINAGE
TRENCH IS DEEPER THAN
FOUNDATIONS

(SCALE 1:20)



Surround of granular bedding
material provided for full length
of pipe under and pipe over.


Collars to be
positioned away
from crossing

Standard
bedding
detail

Standard
bedding
detail

PIPE CROSSINGS DETAIL

(SCALE 1:20)



TYPICAL SADDLE DETAIL

GENERAL NOTES:

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND ENGINEERS DRAWINGS AND SPECIFICATIONS.
- ALL DIMENSIONS ARE IN MILLIMETRES.
- ALL ADOPTABLE DRAINAGE WORKS INCLUDING WORKS TO EXISTING PUBLIC SEWERS TO BE UNDERTAKEN IN ACCORDANCE WITH "SEWERS FOR ADOPTION 7th EDITION" AND "CIVIL ENGINEERING SPECIFICATION FOR THE WATER INDUSTRY 7th EDITION" AND CONSTRUCTED TO THE RELEVANT STATUTORY UNDERTAKERS DETAILS.
- ALL PRIVATE DRAINAGE WORKS TO BE IN ACCORDANCE WITH "CIVIL ENGINEERING SPECIFICATION FOR THE WATER INDUSTRY 7th EDITION", BS EN 752 2008 'DRAIN AND SEWER SYSTEMS OUTSIDE BUILDINGS' AND THE BUILDING REGULATIONS APPROVED 'DOCUMENT H'.
- THE SIZES OF MANHOLES STATED ARE MINIMUM. IF TWO OR MORE PIPES ENTER THE MANHOLE, THE CHAMBER SIZE MUST BE SUFFICIENT TO ACCOMMODATE THE ADEQUATE BENCHING WIDTHS. ALL PIPES BUILT INTO THE MANHOLE INVERT SHOULD BE INSTALLED WITH SOFFITS LEVEL.
- THE CONTRACTOR SHALL GIVE AT LEAST ONE WORKING DAYS NOTICE TO THE ENGINEER TO ALLOW OPPORTUNITY TO EXAMINE ANY FORMATION OR ANY WITNESS TESTING.
- ALL SOFT SPOTS TO BE REMOVED FROM THE BOTTOM OF EXCAVATIONS AND TO BE REFILLED TO FORMATION LEVEL WITH THE SAME MATERIAL AS PERMANENT WORKS WHICH REST IN IT.
- ALL CONCRETE AND CONCRETE PRODUCTS SHALL SATISFY THE SULPHATE CLASSIFICATION ADVISED IN THE SITE INVESTIGATION (BS-EN 206 STATES PORTLAND LIMESTONE CEMENT IS NOT PERMITTED). ALL CONCRETE GRADES STATED ON THIS DRAWING ARE THE MINIMUM STRENGTH REQUIREMENTS. THEY MUST BE CAPABLE OF RESISTING THE REQUIRED SULPHATE CLASSIFICATION.
- MANHOLE COVER CLASSIFICATION TO BE IN ACCORDANCE WITH BS-EN 124 AS SHOWN IN THE TABLE BELOW.

COVER TYPES TO EN124		
CLASS	LOAD (T)	APPLICATIONS
A	1.5	PEDESTRIAN ONLY AREAS
B	12.5	CAR PARKS
C	25	SERVICE ROADS NOT EXTENDING MORE THAN 500mm FROM KERB FACE INTO THE CARRIAGEWAY.
D	40	ROADS, LOADING AREAS AND CONCRETE HARDSTANDINGS.

COVER SIZES		
TYPE	LENGTH AND WIDTH (mm)	CIRCULAR (mm)
SMALL ACCESS FITTING	150 x 100	150
LARGE ACCESS FITTING	225 x 100	-
INSPECTION CHAMBER	450 x 450	450
MANHOLE FOR TYPE B MANHOLE WITH <1.8m INTERNAL HEIGHT	600 x 600 685 x 1220 MULTIPLE	600

CONCRETE TYPES			
LOCATION	TYPE	MAX AGGREGATE	NOMINAL SLUMP
ALL CONCRETE FOR DRAINAGE	GEN 3	20mm	S3

RATE OF SAMPLING FOR COMPRESSIVE STRENGTH TEST ONE SET OF CUBES PER 20cu m OR 10 BATCHES OF CONCRETE WHICHEVER REPRESENTS THE LESSER VOLUME, BUT NOT LESS THAN ONE FOR EACH DAY OR USE.
A SET OF CUBES IS TO COMPRISE THREE CUBES, ONE FOR TESTINE AT 28 DAYS, ONE FOR TESTING AT 7 DAYS AND A SPARE. THE NUMBER OF SPARE CUBES AND CUBES FOR TESTING AT 7 DAYS MAY BE REDUCED AT THE CONTRACTORS RISK.

CONSTRUCTION RECORD - FINAL CONSTRUCTION

THE INFORMATION IS BASED ON CONFIRMATION FROM THE CONTRACTOR OF THE INSTALLED WORKS. THERE MAY BE VARIATIONS ON SITE WHICH ARE NOT REFLECTED ON THIS DRAWING AND HAS NOT BEEN VERIFIED BY CURTINS.

IT IS NOTED THAT THE WORKS ON THIS DRAWING REFLECT THE WORKS COVERED UNDER THE LEND LESE CONTRACT ONLY. EXTERNAL DRAINAGE WORKS ASSOCIATED WITH THE FINAL COMPLETED PLOT WILL BE UPDATED UPON SEPARATE DRAWINGS.

- UNLESS NOTED OTHERWISE, ALL MORTAR TO BE CLASS 1 (1:3 CEMENT:SAND).
 - LIMESTONE PIPE BEDDING WILL NOT BE PERMITTED IN ACIDIC GROUNDWATER CONDITIONS. REFER TO CONTRACT SPECIFICATION FOR SPECIFIC DETAILS.
 - CUT ENDS OF ANY REINFORCED CONCRETE PIPES ARE TO BE TREATED WITH EPOXY RESIN PAINT/MORTAR.
 - CONSTRUCTION JOINTS IN CONCRETE SURROUND MUST NOT BE WITHIN 150MM OF CHAMBER RING JOINTS.
 - FLEXIBLE JOINTS SHALL BE PROVIDED AS CLOSE AS POSSIBLE TO THE OUTSIDE FACE OF ANY STRUCTURE INTO WHICH IT IS BUILT. (SEE TABLE BELOW).
- | PIPE DIAMETER (mm) | MAX DIM "A" (mm) | MAX DIM "B" (mm) |
|--------------------|------------------|------------------|
| 150 | 150 | 500-750 |
| 225-450 | DIA | 500-750 |
| 525-600 | DIA | < 1000 |
- IN CLAY SOIL, PIPE TRENCHES ARE TO BE BACKFILLED WITH CLEAN GRANULAR HARD CORE 75MM DOWN.
 - CONNECTIONS INTO MANHOLES SHALL BE CONSTRUCTED AT SOFFIT LEVEL, UNLESS DETAILED DIFFERENTLY ON CONSTRUCTION DRAWINGS.
 - SUITABLE MATERIAL/SELECTED FILL SHOULD BE READILY COMPACTABLE, FREE FROM TIMBER, FROZEN MATERIAL, VEGETATION AND FOREIGN MATTER. IT SHOULD EXCLUDE ANY LUMPS OF CLAY RETAINED ON A 100MM SIEVE AND STONES RETAINED ON A 40MM SIEVE.
 - CONCRETE BENCHING AND PIPE SURROUND SHALL BE PLACED IN A SINGLE CONTINUOUS OPERATION FROM THE TOP OF THE BASE SLAB TO TOP OF BENCHING AND PIPE SURROUND.
 - PCC COVER SLABS AND MANHOLE RINGS TO BE MANUFACTURED TO BS-EN 1917 AND BS 5911:3 AND KITEMARKED.
 - PCC COVER SLABS TO HAVE 600X750MM CLEAR OPENING UNLESS STATED OTHERWISE WITHIN THIS SCHEDULE AND BE MANUFACTURED TO BS-EN 1917 AND BS 5911:3.
 - CORBEL SEATING UNITS TO BE MANUFACTURED TO BS-EN 1917 AND BS 5911:3 TO BE USED ECCENTRIC OVER SLAB OPENING TO REDUCE FRO. 600X600MM OPENING IN IRONWORK TO 600X750MM OPENING IN COVER SLAB WHERE APPLICABLE.
 - ALL CONCRETE PIPEWORK TO BE MANUFACTURED TO BS-EN 1916 AND BS 5911:1 AND STRENGTH CLASS 120 AND KITEMARKED.
 - ALL CLAY PIPEWORK SHALL BE EXTRA STRENGTH CLAYWARE TO BS 295 AND BS 65 (SW PIPES ONLY).
 - THE CONTRACTOR MAY ELECT TO USE REINFORCES UPVC PIPES COVERED BY BS-EN 1401:1 FOR DIAMETERS UP TO AND INCLUDING 300MM.
 - ALL PROPRIETARY PRODUCTS ARE TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS GUIDANCE AND INSTRUCTIONS.

CR	FINAL CONSTRUCTION ISSUE	16.02.22	CG	CG
C01	ISSUED FOR CONSTRUCTION	16.09.20	AH	CD
P03	STAGE 4 ISSUE	06.12.19	AH	CD
P02	STAGE 4 DRAFT UPDATE	08.11.19	AH	CD
P01	STAGE 4 DRAFT	19.07.19	CD	CG
Rev:	Description:	Date:	By:	Chkd:



Merchant Exchange, 17-19 Whitworth Street West, Manchester, M1 5WG
0161 235 2384
manchester@curtins.com
www.curtins.com

Civils & Structures • Transport Planning • Environmental • Infrastructure • Geotechnical • Conservation & Heritage • Principal Designer
Birmingham • Bristol • Cambridge • Cardiff • Douglas • Dublin • Edinburgh • Glasgow • Kentish • Leeds • Liverpool • London • Manchester • Nottingham

Status: FINAL CONSTRUCTION ISSUE				
Project: ST JOHNS				
Dig Title: BLOCK C - G&S DRAINAGE DETAILS SHEET 2				
Size: A1	Date: 19.07.19	Drawn By: CD	Designed By: CD	Checked By: CG
Scale: NTS				
Project No:	Originator:	Zone:	Level:	Type: Discipline: Category / Number: Rev:
SJQ-102	-CUR-	00	-XX-	DR - C - 92503 - CR

Appendix C

As Installed Drainage Photographs (Foul and Surface Water)



Q05	DRAINAGE INSPECTION - PIPES
------------	------------------------------------

CONTRACT	St Johns	CONTRACT NO	201	DATE	03.11.2020
LOCATION	FW03 – FW04 G&S	ITEM	Foul Water Line		

NO	CHECK LIST ITEM	DATE	ADANA	DATE	PRINCIPAL CONTRACTOR
1	BUILDING CONTROL NOTIFIED OF START	03.11.2020	✓	03-11-20	
2	INVERT LEVEL OF OUTFALL CHECKED	03.11.2020	✓	03-11-20	
3	PIPES TO CORRECT SIZE & SPECIFICATION (225mm)	03.11.2020	✓	03-11-20	
4	SET OUT LINE & LEVEL	03.11.2020	✓	03-11-20	
5	EXCAVATION TO CORRECT DEPTH / WIDTH	03.11.2020	✓	03-11-20	
6	PIPE BEDDING AND SURROUND TO SPECIFICATION	03.11.2020	✓	03-11-20	
7	ALL JUNCTIONS RECORDED ON DRAWINGS	03.11.2020	✓	03-11-20	
8	BUILDING INSPECTOR WITNESSED DRAIN RUN	N/A	✓		
9	BACKFILL TO SPECIFICATION & COMPACTED	03.11.2020	✓	03-11-20	
10	PIPES RODDED, CLEANED & TESTED	To Follow	✓		
11					
12					
13					

COMMENTS:

Pipes to be jetted and cleaned at later date

All pipes line and Junctions plotted on As-Built

NAME	SIGNED	DATE
Lee Smith	LS	03.11.2020
FOR AND ON BEHALF OF ADANA CONSTRUCTION		


NAME	SIGNED	DATE
DAVID FANLOS		03.11.20
FOR AND ON BEHALF OF GENURATE		





09:05

Signal strength, Wi-Fi, and battery icons





Q04	DRAINAGE INSPECTION - MANHOLE
------------	--------------------------------------

CONTRACT	St Johns	CONTRACT NO	201	DATE	02.11.2020
LOCATION	Drainage manhole FW03 G&S	ITEM	FW03		

NO	CHECK LIST ITEM	DATE	ADANA	DATE	PRINCIPAL CONTRACTOR
1	INVERT LEVEL (24.111m)	02.11.2020	LS	02-11-20	
2	TYPE - PPIC, BRICK, CONCRETE	02.11.2020	LS	02-11-20	
3	CHANNEL - 225mm	02.11.2020	LS	02-11-20	
5	CONCRETE SPECIFICATION	02.11.2020	LS	02-11-20	
6	DIAMETER OF RING (600mm PPIC)	02.11.2020	LS	02-11-20	
7	STEP IRONS REQUIRED? YES / NO	02.11.2020	LS	02-11-20	
9	JOINTING MATERIAL BETWEEN CHAMBER RINGS	02.11.2020	LS	02-11-20	
10	SIZE OF ACCESS HOLE IN COVER SLAB	02.11.2020	LS	02-11-20	
11	CHANNELS & BENCHING COMPLETE	To Follow	LS		
12	LIFTING HOLES IN CHAMBER RING FILLED	To Follow	LS		
13	CONCRETE SEGMENTS / BRICKWORK CLASS	To Follow	LS		
14	FRAME & COVER TO CORRECT SPECIFICATION	02.11.2020	LS	02-11-20	
15	WITNESSED BY BUILDING INSPECTOR	N/A	N/A		
16	ALL DRAIN STOPPERS ARE REMOVED	02.11.2020	LS	02-11-20	

COMMENTS: Air Test To Be Carried Out & Completed at a later date

NAME	SIGNED	DATE
Lee Smith	Lee Smith	02.11.2020

FOR AND ON BEHALF OF ADANA CONSTRUCTION


NAME	SIGNED	DATE
DAVID JAMES		02.11.20
FOR AND ON BEHALF OF	WENDY	





09:05

4G LTE



III

O

<



Q04	DRAINAGE INSPECTION - MANHOLE
------------	--------------------------------------

CONTRACT	St Johns	CONTRACT NO	201	DATE	05.11.2020
LOCATION	Drainage manhole FW04 G&S	ITEM	FW04		

NO	CHECK LIST ITEM	DATE	ADANA	DATE	PRINCIPAL CONTRACTOR
1	INVERT LEVEL (23.604m)	05.11.2020	LS	05-11-20	
2	TYPE - PPIC, BRICK, CONCRETE	05.11.2020	LS	05-11-20	
3	CHANNEL - 225mm	05.11.2020	LS	05-11-20	
5	CONCRETE SPECIFICATION	05.11.2020	LS	05-11-20	
6	DIAMETER OF RING (600mm PPIC)	05.11.2020	LS	05-11-20	
7	STEP IRONS REQUIRED? YES / NO	05.11.2020	LS	05-11-20	
9	JOINTING MATERIAL BETWEEN CHAMBER RINGS	05.11.2020	LS	05-11-20	
10	SIZE OF ACCESS HOLE IN COVER SLAB	05.11.2020	LS	05-11-20	
11	CHANNELS & BENCHING COMPLETE	To Follow	LS		
12	LIFTING HOLES IN CHAMBER RING FILLED	To Follow	LS		
13	CONCRETE SEGMENTS / BRICKWORK CLASS	To Follow	LS		
14	FRAME & COVER TO CORRECT SPECIFICATION	05.11.2020	LS	05-11-20	
15	WITNESSED BY BUILDING INSPECTOR	N/A	N/A		
16	ALL DRAIN STOPPERS ARE REMOVED	05.11.2020	LS	05-11-20	

COMMENTS: Air Test To Be Carried Out & Completed at a later date

NAME	SIGNED	DATE
Lee Smith	Lee Smith	05.11.2020
FOR AND ON BEHALF OF ADANA CONSTRUCTION		

NAME	SIGNED	DATE
DAVID JAMES		05.11.20.
FOR AND ON BEHALF OF	LENDLEASE.	







Q04	DRAINAGE INSPECTION - MANHOLE
------------	--------------------------------------

CONTRACT	St Johns	CONTRACT NO	201	DATE	04.08.2020
LOCATION	Drainage manhole SW08	ITEM	SW01		

NO	CHECK LIST ITEM	DATE	ADANA	DATE	PRINCIPAL CONTRACTOR
1	INVERT LEVEL	04.08.2020	LS	11/9/20	SLY
2	TYPE - PPIC, BRICK, CONCRETE	04.08.2020	LS	11/9/20	SLY
3	CHANNEL - CATCH PIT	04.08.2020	LS	11/9/20	SLY
5	CONCRETE SPECIFICATION	04.08.2020	LS	11/9/20	SLY
6	DIAMETER OF RING	04.08.2020 1.5m	LS	11/9/20	SLY
7	STEP IRONS REQUIRED? YES / NO	04.08.2020	LS	11/9/20	SLY
9	JOINTING MATERIAL BETWEEN CHAMBER RINGS (Rubber Seal)	04.08.2020	LS	11/9/20	SLY
10	SIZE OF ACCESS HOLE IN COVER SLAB	04.08.2020 600mm x 600mm	LS	11/9/20	SLY
11	CHANNELS & BENCHING COMPLETE	N/A	N/A	11/9/20	SLY
12	LIFTING HOLES IN CHAMBER RING FILLED	N/A	N/A	11/9/20	SLY
13	CONCRETE SEGMENTS / BRICKWORK CLASS	N/A	N/A	11/9/20	SLY
14	FRAME & COVER TO CORRECT SPECIFICATION	04.08.2020	LS	11/9/20	SLY
15	WITNESSED BY BUILDING INSPECTOR	04.08.2020	LS	11/9/20	SLY
16	ALL DRAIN STOPPERS ARE REMOVED	04.08.2020	LS	11/9/20	SLY

COMMENTS: Air Test To Be Carried Out & Completed at a later date

NAME	SIGNED	DATE
Lee Smith	Lee Smith	04.08.2020

FOR AND ON BEHALF OF ADANA CONSTRUCTION
--

NAME	SIGNED	DATE
SLY	SLY	11/9/20
FOR AND ON BEHALF OF	SLY	

MH SW 01





Q04	DRAINAGE INSPECTION - MANHOLE
------------	--------------------------------------

CONTRACT	St Johns	CONTRACT NO	201	DATE	04.08.2020
LOCATION	Drainage manhole SW02	ITEM	SW02		

NO	CHECK LIST ITEM	DATE	ADANA	DATE	PRINCIPAL CONTRACTOR
1	INVERT LEVEL	04.08.2020	LS	11/9/20	S. L. L.
2	TYPE - PPIC, BRICK, CONCRETE	04.08.2020	LS	11/9/20	S. L. L.
3	CHANNEL - CATCH PIT	04.08.2020	LS	11/9/20	S. L. L.
5	CONCRETE SPECIFICATION	04.08.2020	LS	11/9/20	S. L. L.
6	DIAMETER OF RING	04.08.2020 1.5m	LS	11/9/20	S. L. L.
7	STEP IRONS REQUIRED? ☒ YES / NO	04.08.2020	LS	11/9/20	S. L. L.
9	JOINTING MATERIAL BETWEEN CHAMBER RINGS (Rubber Seal)	04.08.2020	LS	11/9/20	S. L. L.
10	SIZE OF ACCESS HOLE IN COVER SLAB	04.08.2020 600mm x 600mm	LS	11/9/20	S. L. L.
11	CHANNELS & BENCHING COMPLETE	N/A	N/A	11/9/20	S. L. L.
12	LIFTING HOLES IN CHAMBER RING FILLED	N/A	N/A	11/9/20	S. L. L.
13	CONCRETE SEGMENTS / BRICK WORK CLASS	N/A	N/A	11/9/20	S. L. L.
14	FRAME & COVER TO CORRECT SPECIFICATION	04.08.2020	LS	11/9/20	S. L. L.
15	WITNESSED BY BUILDING INSPECTOR	04.08.2020	LS	11/9/20	S. L. L.
16	ALL DRAIN STOPPERS ARE REMOVED	04.08.2020	LS	11/9/20	S. L. L.

COMMENTS: Air Test To Be Carried Out & Completed at a later date

NAME	SIGNED	DATE
Lee Smith	Lee Smith	04.08.2020

FOR AND ON BEHALF OF ADANA CONSTRUCTION

NAME	SIGNED	DATE
S. L. L.	S. L. L.	11/9/20
FOR AND ON BEHALF OF	<i>Lee Smith</i>	

M H 5W02



Appendix E

As Installed Drainage CCTV Survey (Surface Water)

TEAM
DRAINAGE UK

Team Drainage UK Ltd

2nd Floor Peel House Peel Road, Skelmersdale

Tel. 01695 768 714

ben.pearce@teamdrainageuk.com

Section Inspection - 30/07/2021 - LINE AX

Section 58	Inspection 58	Date 30/07/21	Time 11:36	Client's Job Ref ST JOHNS PROJECT	Weather No Rain Or Snow	Pre Cleaned Yes	PLR LINE AX
Operator MIKE		Vehicle Not Specified		Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative ID 1

Town or Village:	Manchester	Inspection Direction:	Upstream	Upstream Node:	LINE A
Road:	Water St	Inspected Length:	39.48 m	Upstream Pipe Depth:	
Location:	Property with buildings	Total Length:	39.48 m	Downstream Node:	MH01
Surface Type:		Joint Length:	0.00 m	Downstream Pipe Depth:	1.930 m
Use:	Surface water	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	300 mm		
Year Constructed:		Pipe Material:	Polyvinyl chloride		
Flow Control:	No flow control	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection of condition	Lining Material:	No Lining		

Comments:

Recommendations:

Scale: 1:344	Position [m]	Code	Observation	MPEG	Photo	Grade
Depth: 1.93 m MH01						
	0.00	MH	Start node type, manhole, reference number: MH01: U.S LINE A	00:00:19	MH01 US LINE A_0-00m_	
	0.00	WL	Water level, 5% of the vertical dimension	00:00:21	MH01 US LINE A_0-00m_	
	39.48	MHF	Finish node type, manhole, reference number: LINE A: MH02	00:04:21	MH01 US LINE A_39-48m	
LINE A Depth: m						

Construction Features

Structural Defects

Miscellaneous Features

Service & Operational Observations

STR No. Def	STR Peak	STR Mean	STR Total	STR Grade	SER No. Def	SER Peak	SER Mean	SER Total	SER Grade
0	0.0	0.0	0.0	1.0	0	0.0	0.0	0.0	1.0

Section Pictures - 30/07/2021 - LINE AX

Section	Inspection Direction	PLR	Client's Job Ref	Contractor's Job Ref
58	Upstream	LINE AX	ST JOHNS PROJECT	LEND LEASE



MH01 US LINE A_0-00m_113825.jpg, 00:00:19, 0.00 m
 Start node type, manhole, reference number: MH01, U.S LINE A



MH01 US LINE A_0-00m_113832.jpg, 00:00:21, 0.00 m
 Water level, 5% of the vertical dimension



MH01 US LINE A_39-48m_114243.jpg, 00:04:21, 39.48 m
 Finish node type, manhole, reference number: LINE A, MH02

TEAM
DRAINAGE UK

Team Drainage UK

2nd Floor Peel House Peel Road, Skelme

Tel. 01695 7

ben.pearce@teamdrainage.uk

Section Inspection - 30/07/2021 - LINE AX

Section 58	Inspection 58	Date 30/07/21	Time 11:36	Client's Job Ref ST JOHNS PROJECT	Weather No Rain Or Snow	Pre Cleaned Yes	PLR LINE AX
Operator MIKE	Vehicle Not Specified	Camera Not Specified	Preset Length Not Specified	Legal Status Not Specified	Alternative 1		

Town or Village:	Manchester	Inspection Direction:	Upstream	Upstream Node:	LINE A
Road:	Water St	Inspected Length:	39.48 m	Upstream Pipe Depth:	
Location:	Property with buildings	Total Length:	39.48 m	Downstream Node:	MH01
Surface Type:		Joint Length:	0.00 m	Downstream Pipe Depth:	1.930 m
Use:	Surface water	Pipe Shape:	Circular		
Type of Pipe:	Gravity drain/sewer	Dia/Height:	300 mm		
Year Constructed:		Pipe Material:	Polyvinyl chloride		
Flow Control:	No flow control	Lining Type:	No Lining		
Inspection Purpose:	Routine inspection of condition	Lining Material:	No Lining		

Comments:

Recommendations:

Scale: 1:344 Position [m] Code Observation MPEG Photo G

Depth: 1.93 m

MH01



0.00

MH

Start node type, manhole, reference number: MH01: U.S
LINE A

00:00:19

MH01 US
LINE
A_0-00m_

0.00

WL

Water level, 5% of the vertical dimension

00:00:21

MH01 US
LINE
A_0-00m_

39.48

MHF

Finish node type, manhole, reference number: LINE A:
MH02

00:04:21

MH01 US
LINE
A_39-48mLINE A
Depth: m

Appendix F

Land Drainage Consent (Manchester City Council)



MANCHESTER
CITY COUNCIL

Manchester Quays
Development Ltd.
c/o Allied London
No. 1 Spinningfields
Level 12
1 Hardman Square
Manchester
M3 3EB

Manchester City Council
Flood Risk Management Team
Capital Programme Division
Corporate Services Department
PO Box 532
Town Hall
Manchester
M60 2LA

FAO: Miss Chloe Grimsley

Contact: Esther Goodship

Tel: 0161 219 6713

Fax: 0161 274 7103

Email: floodriskmanagement@manchester.gov.uk

Our ref: MCC038/05/2019

Date: 10 May 2019

Dear Miss Grimsley,

Application for Ordinary Watercourse Land Drainage Consent Works for 2 No. surface outfall pipe connection into canal basin.

Thank you for your application for Ordinary Watercourse Land Drainage Consent received by Manchester City Council on 21 March 2019.

I confirm that your proposals for the permanent works are acceptable to Manchester City Council. I enclose consent number **MCC038/05/2019** issued under Section 23 of the Land Drainage Act 1991.

Please notify this authority no less than seven days before commencement and upon completion of the works, via the email contact details above, quoting the above consent number for reference.

Yours sincerely

Esther Goodship
Flood Risk Engineer



MANCHESTER
CITY COUNCIL

Ordinary Watercourse Land Drainage Consent

Land Drainage Act 1991

Name: **Manchester Quays Development Ltd.**

Consent applying to: **St Johns**

Consent Number: **MCC038/05/2019**

Effective from: **10 May 2019**

Introduction

Land Drainage Consents are required by virtue of the Land Drainage Act 1991. The following activities on an Ordinary (non-main) Watercourse require Local Authority Consent:

Under Section 23 of the Land Drainage Act 1991

- The erection or alteration of any mill dam, weir or other like obstruction to the flow of any watercourse
- The erection or alteration of any culvert that would be likely to affect the flow of any watercourse

Under Sections 17 and 20(2) of the Land Drainage Act 1991

- Any drainage works carried out by a local authority against flooding in connection with any watercourse

Under Section 61F Land Drainage Act 1991 (Inserted by Schedule 22 Environment Act 1995)

- The operation of any drainage works, under the control of any Internal Drainage Board or local authority, so as to manage the level of water in a watercourse for the purposes of facilitating spray irrigation.

Note

Consent under the above legislation is required irrespective of whether the works are permanent or temporary.

Contraventions

In relation to Ordinary Watercourses, the Council can under Section 24 of the Land Drainage Act 1991 serve a legal notice requiring the person to abate the nuisance within a specified time. Failure to abide by such a notice can result in Manchester City Council carrying out the necessary remedial work and seeking to recover costs.

Land Drainage Act 1991

Land Drainage Consent
Control of works affecting watercourses and/or flood defences
Consent number **MCC038/05/2019**

To: **Manchester Quays Development Ltd.**

Manchester City Council, in exercise of its powers under Section 23 of the Land Drainage Act 1991 and subject to the conditions attached, hereby grants its consent in relation to the works or operations described in this Consent.

Watercourse: **Canal Basin adjacent Grey Irwell**

Location: **Water Street, Manchester**

Map reference: **SJ 83034 98050**

Description of works **2 x 525mm concrete pipes with safety grille and base scour protection within existing tow path wall.**

as detailed on plans and sections

Drg Ref: **SJQ-099-CUR-XX-XX-DR-C-92550 Rev P06 Proposed Drainage Layout
SJQ-099-CUR-XX-XX-DR-C-92572 Rev P06 Proposed Bridge Infill Plan
and Section
Method Statement 008 Rev B (ADANA Construction)
Risk Assessment SW Outfall under Water Street 10a Rev A**

Manchester City Council does not accept any responsibility for the design and construction of the works referred hereto and any liability for any loss or damage which may arise out of their design, construction, maintenance or use.

This Consent shall come into effect on

Date: **10 May 2019**

Signed on behalf of Manchester City Council



**Esther Goodship
Engineer**

Date of signing:

10 May 2019

Conditions

This consent is granted with the following conditions:

General

- Connection to the existing canal basin, scour protection and safety grille shall be strictly in accordance with the approved plans, drawings, calculations, specifications and other documents and proceed entirely in accordance with the approved method statement.
- Works should be arranged to ensure there is no increase in flood risk to third parties.
- Manchester City Council does not accept any responsibility for the design and construction of the works that are the subject of this Consent and any liability for any loss or damage which may arise out of their design, construction, maintenance or use.
- It is the responsibility of the applicant to ensure that the consent / permission of any owners and occupiers affected by the works is duly obtained.
- This Consent does not remove from the applicant the necessity to obtain other licences, consents, approvals or permissions (including planning permission) which may be required in law or in order to comply with any duties or responsibilities for conservation or protection of the environment.
- This Consent does not confer any rights of entry or rights over property

Timing

1. This consent is valid for two years from the date of issue.

Construction/Temporary Works

- Taking all reasonable precautions during the undertaking of the works so as not to obstruct, impede or interfere with the flow of water in, into or out of the watercourse.
- Manchester City Council may choose to permit minimal obstruction to flows during construction but these temporary restrictions must not increase flood risk to others and they must be capable of being overtopped in higher flows.
- Works must be undertaken fully in accordance with PPG5, the pollution prevention guidelines on works or maintenance in or near water. These guidelines are important and comprehensive and should be studied carefully by those contemplating works.
- Should any pollution problems occur on site the Environment Agency must be informed immediately on 0800 807060 and Manchester City Council also informed.
- Wet concrete must not be released into the watercourse because of the adverse impact.
- Material used for backfilling must be inert and not contain any material that could potentially leach out into the watercourse.
- There may be stated restriction(s) on working periods because of bird activity (including nesting)
- There may be stated restriction(s) on working periods because of specific flora.
- Netting and other arrangements must be used to ensure that debris does not fall into the watercourse.
- No excavated material or debris arising from the construction of the works shall be disposed of on the site without the prior approval of Manchester City Council.

Other Information

- Upon completion of the works all debris and surplus materials must be removed from the site of the works and the existing canal basin left in a stable condition.
- Notice in writing must be given immediately by the applicant Manchester City Council upon completion of the works.
- As built drawings of the work must be provided to Manchester City Council as the Lead Local Flood Authority within four weeks of completion.

Our Locations

Birmingham

2 The Wharf
Bridge Street
Birmingham
B1 2JS
T. 0121 643 4694
birmingham@curtins.com

Kendal

28 Lowther Street
Kendal
Cumbria
LA9 4DH
T. 01539 724 823
kendal@curtins.com

Bristol

Quayside
40-58 Hotwell Road
Bristol
BS8 4UQ
T. 0117 302 7560
bristol@curtins.com

Leeds

Rose Wharf
Ground Floor
Leeds
L29 8EE
T. 0113 274 8509
leeds@curtins.com

Cardiff

3 Cwrt-y-Parc
Earlswood Road
Cardiff
CF14 5GH
T. 029 2068 0900
cardiff@curtins.com

Liverpool

Curtin House
Columbus Quay
Riverside Drive
Liverpool
L3 4DB
T. 0151 726 2000
liverpool@curtins.com

Douglas

Varley House
29-31 Duke Street
Douglas
Isle of Man
IM1 2AZ
T. 01624 624 585
douglas@curtins.com

London

40 Compton Street
London
EC1V 0BD
T. 020 7324 2240
london@curtins.com

Dublin

39 Fitzwilliam Square
Dublin 2
Ireland
T. 00353 1 507 9447
dublin@curtins.com

Manchester

Merchant Exchange
17-19 Whitworth Street West
Manchester
M1 5WG
T. 0161 236 2394
manchester@curtins.com

Edinburgh

1a Belford Road
Edinburgh
EH4 3BL
T. 0131 225 2175
edinburgh@curtins.com

Nottingham

56 The Ropewalk
Nottingham
NG1 5DW
T. 0115 941 5551
nottingham@curtins.com

Glasgow

Queens House
29 St Vincent Place
Glasgow
G1 2DT
T. 0141 319 8777
glasgow@curtins.com