



KEY	
	Excavation depth 198mm (Excavation in carriageway construction)
	Excavation depth 260mm (323mm below finish level) (Excavation beneath paved footway construction)
	Excavation depth 323mm (Excavation in flexible footway construction)
	Excavation (planing) depth 100mm (Tie-in to existing carriageway)
	Cold milling (planing) of existing carriageway surface 40mm thick
	Excavation to a depth of 50mm (Excavation in soft material) (Excavation for tree pit surface)

E	AMR	ML	ADF	21.07.21	Physical layby removed
D	AMR	ML	ADF	21.05.21	Client name amended
C	AMR	ML	ADF	14.05.21	Additional excavation for Major St paving
B	AMR	ML	ADF	03.09.20	Carriageway excavation to 40mm removed
A	AMR	ML	ADF	04.04.19	Excavation depths amended to suit MCC's revised paving depths
A	AMR	ML	ADF	04.04.19	Excavation to frontage added
					Excavation depths amended

REV	DRN	CHK	APP	DATE	DESCRIPTION

Brindley Lodge,
Adcroft Street,
Stockport, Cheshire,
SK1 3HS.
www.wildcivil.co.uk
Tel : 0161-474-7477
Fax : 0161-474-7492

Client
PORTLAND STREET PROPERTY LIMITED

Project
55 PORTLAND STREET

Title
S278 AGREEMENT WORKS
EXCAVATION REQUIREMENTS

Scale 1:150	Drawn AMR	Date 14.02.19	Chkd ML	Approved ADF
Drawing No. 766/010/600				Revision E
Status FOR APPROVAL				Sheet Size A1