

General Notes

1. All dimensions are in metres unless stated otherwise.
2. This drawing shall be read in conjunction with all other relevant engineering details, drawings and specifications.
3. Any discrepancies should be reported to the engineer immediately so that clarification can be sought prior to the commencement of work.
4. All work is to be carried out in accordance with the specification for highways works and local authority guidance.
5. Underground services may be present in the area. Contractor is to confirm the precise line and depth of any services prior to the commencement of any excavation works.
6. Subbase depth of 350mm is the minimum required for loading, ground conditions and attenuation. Formation to be laid flat and therefore subbase depth will vary to suit proposed driveway gradients.

Legend

-
- Site Boundary
- Proposed Major Contour
250mm intervals
- Proposed Minor Contours
50mm intervals
- S104 Surface Water Sewer
- S104 Surface Water Manhole
- S104 Foul Water Sewer
- S104 Foul Water Manhole
- Existing Surface Water Sewer
- Existing Foul Water sewer
- Private Surface Water Drain
- Private Foul Water Drain
- 300Ø Mini Access Chamber
- 450Ø Inspection Chamber
- 600Ø RIDGISTORMcheck Office
Control Chamber. 2½s MAX.
- Rodding Eye
- ACØ Rain Drain
Surface Water Drainage Channel
- Polypipe Permavoid Rainwater
Diffuser Unit (1062x708x150mm)
- Permeable Driveway with min
350mm Subbase Storage
- Permeable Driveway
Subbase Formation Level
- S38 Road Gully

P01	17/12/21	First issue	ARJ	BKD	JDY
Rev	Date	Description	Drw	Chk	Rev'd

Status

Preliminary

Cler

Towerhouse Systems

Project

Cringle Road
Manchester

Drawing

Private External Works
Plot Drainage
Sheet 2 of 2

Drawing Number

LM20066-DYSE-XX-ZZ-DR-C-1131 P0

DYSE
STRUCTURAL ENGINEERS

ISO A1 (594x841mm) Do Not Scale © Copyright DYSE Ltd

Private External Works Plot Drainage
Sheet 2 of 2
1:200

www.dyse.com @DYSEstructural