



Proposed Site Layout Plan




Gate Type G1:
1700mm high timber sliding gate comprising of naturally finished external grade timber to match rear fencing with a black powder coated steel surround.

Gate Type G2:
1500mm high single leaf gate fixed between 2000mm high posts. The gate is to comprise the same colour and material as the adjacent fencing.

Boundary Treatment: **C**
1400mm high black painted metal railing panels fixed between 1200mm high posts. The panel and posts are of hollow steel sections constructed in a fully welded, pale through method with no visible joints and to comprise decorative finials. The fence panel to post fixing is by way of concealed, vandal resistant fixings. Where the railings return around the corner, 1940mm high black painted metal railing panels fixed between 2000mm high posts.

NB:
Any works carried out in a 1m vicinity of the existing trees are to be carried out by hand without the aid of heavy machinery in order to protect the roots.

Proposed Boundary Treatments



Boundary Treatment: **A**
500mm high naturally finished featheredge timber horizontal batten fencing, produced from external grade timber. To be fixed above the existing 1900mm high brick boundary wall. Full extent of new fencing to be located on site layout and location plans.

PROJECT:	61 High Lane, Chorton
CLIENT:	Mr J. Kennedy
DRAWING:	Proposed Site Layout Plan & Boundary Treatments
DRAWN BY:	GC
CHECKED BY:	---
DATE:	19/04/2021
SCALE:	1:100 & 1:50 @ A1
STATUS:	Planning
DRAWING NO:	1000-SLP-000
REVISION:	A

REV	DATE	AMENDMENT	BY	CHKD
A	10/08/2021	Gateway position amended in accordance with sketch dated 10/08/2021 - sketch also layout plan as agreed by MCC Highways Engineer. Gate and gate posts moved 2m back from the site boundary in order for vehicles entering and leaving the premises to wait for on coming traffic while remaining within the site ownership and so as not to impede on the foot traffic along the public footpath; boundary treatment reduced to low-level stone wall and metal railings amount of landscaping increased in acc. with NMS statement & TP scheme; and hedgeline and driveway rotation added.	GC	-

DO NOT SCALE.
COPYRIGHT REMAINS WITH STUDIOOO.
E-MAIL: @_studiooo@outlook.com