

SHALLONS

Window Schedule

Windows are of original metal frames with glass panes and cementitious backing boards. As shown below are in need of remedial work. Panes of glass will be replaced and backing board re-inserted.



PRINCESS STREET BASEMENT
UNIT 4 WINDOWS



PRINCESS STREET BASEMENT
UNIT 4 WINDOWS



PRINCESS STREET BASEMENT
UNIT 4 WINDOWS



PRINCESS STREET BASEMENT
UNIT 4 WINDOWS

SHALONS

REMEDIAL WORKS NOTE 1

ALL DEFECTIVE / BROKEN PANES OF GLASS TO BE CAREFULLY REMOVED & REPLACED WITH LIKE FOR LIKE GLAZING

JOHNSON HOUSE GLAZING SPEC.:

FOLLOWING INSTALLATION OF NEW GLAZING WORKS (NOTED BELOW) ALL INTERNAL FRAMES ARE TO BE MADE GOOD WHERE NECESSARY (FOLLOWING FURTHER SITE INSPECTION) AND NEW PAINT FINISH APPLIED (AS PER LRW-7664-S(40)01 FINISHES SCHEDULE.

NO EXTERNAL WORKS PROPOSED TO WINDOW FRAMES/ GLAZING



EXISTING INTERNAL CEMENTITIOUS BACKING BOARD TO CAREFULLY REMOVED FROM EXISTING RETAINED OUTER GLASS PANE.

NEW THIN DGU (TO MATCH EXISTING APPEARANCE OF EXISTING RETAINED PANES) TO BE APPLIED INTERNALLY TO MEET U-VALUE REQUIREMENT 1.6 W/M2K



EXISTING CLEAR PANE OF GLASS WITH INTERNALLY BONDED CEMENTITIOUS BACKING BOARD TO BE RETAINED



ELEVATION 7 PRINCESS STREET SCALE - 1:100