

Integra Consulting (Engineers) Ltd		Page 1
First Floor, Suite 4 14-32 Hewsitt Street Manchester, M15 4GB		
Date 04/08/2021 16:13 File 3255 - MD.MDX	Designed by jansk Checked by	
Innovyze	Network 2019.1	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	2	PIMP (%)	100
M5-60 (mm)	18.150	Add Flow / Climate Change (%)	0
Ratio R	0.385	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	400

Designed with Level Inverts

Time Area Diagram for Storm

Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.132	4-8	0.040

Total Area Contributing (ha) = 0.172

Total Pipe Volume (m³) = 4.970

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.000	5.885	0.080	73.6	0.003	5.00	0.0	0.600	o	100	Pipe/Conduit	
S1.001	11.823	0.150	78.8	0.005	0.00	0.0	0.600	o	100	Pipe/Conduit	
S1.002	10.757	0.140	76.8	0.006	0.00	0.0	0.600	o	100	Pipe/Conduit	
S2.000	10.207	0.130	78.5	0.006	5.00	0.0	0.600	o	100	Pipe/Conduit	
S2.001	13.719	0.240	57.2	0.006	0.00	0.0	0.600	o	100	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.000	50.00	5.11	73.300	0.003	0.0	0.0	0.0	0.90	7.1	0.4
S1.001	50.00	5.34	73.220	0.008	0.0	0.0	0.0	0.87	6.8	1.1
S1.002	50.00	5.54	73.070	0.014	0.0	0.0	0.0	0.88	6.9	1.9
S2.000	50.00	5.20	73.300	0.006	0.0	0.0	0.0	0.87	6.8	0.8
S2.001	50.00	5.42	73.170	0.012	0.0	0.0	0.0	1.02	8.0	1.6

First Floor, Suite 4
14-32 Hewsitt Street
Manchester, M15 4GB



```
Date 04/08/2021 16:13
File 3255 - MD.MDX
```

Designed by jansk
Checked by

Innovyze

Network 2019.1

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S3.000	5.835	0.460	12.7	0.005	5.00	0.0	0.600	o	100	Pipe/Conduit	🛠️
S1.003	4.468	0.470	9.5	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	🛠️
S4.000	11.106	0.620	17.9	0.005	5.00	0.0	0.600	o	100	Pipe/Conduit	🛠️
S4.001	13.292	0.080	166.2	0.013	0.00	0.0	0.600	o	225	Pipe/Conduit	🛠️
S4.002	14.673	0.090	163.0	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	🛠️
S1.004	9.925	0.060	165.4	0.029	0.00	0.0	0.600	o	225	Pipe/Conduit	🛠️
S5.000	10.151	0.610	16.6	0.004	5.00	0.0	0.600	o	100	Pipe/Conduit	🛠️
S5.001	22.157	0.140	158.3	0.029	0.00	0.0	0.600	o	225	Pipe/Conduit	🛠️
S5.002	11.620	0.100	116.2	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	🛠️
S6.000	7.872	0.750	10.5	0.008	5.00	0.0	0.600	o	150	Pipe/Conduit	🛠️
S1.005	20.531	0.170	120.8	0.008	0.00	0.0	0.600	o	225	Pipe/Conduit	🛠️
S7.000	7.053	0.620	11.4	0.045	5.00	0.0	0.600	o	150	Pipe/Conduit	🛠️
S1.006	2.000	0.030	66.7	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	🛠️
S1.007	1.784	0.020	89.2	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	🛠️

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S3.000	50.00	5.04	73.390	0.005	0.0	0.0	0.0	2.18	17.1	0.7
S1.003	50.00	5.56	72.930	0.031	0.0	0.0	0.0	3.29	58.1	4.2
S4.000	50.00	5.10	73.250	0.005	0.0	0.0	0.0	1.83	14.4	0.7
S4.001	50.00	5.32	72.630	0.018	0.0	0.0	0.0	1.01	40.2	2.4
S4.002	50.00	5.56	72.550	0.018	0.0	0.0	0.0	1.02	40.6	2.4
S1.004	50.00	5.73	72.460	0.078	0.0	0.0	0.0	1.01	40.3	10.6
S5.000	50.00	5.09	73.250	0.004	0.0	0.0	0.0	1.90	14.9	0.5
S5.001	50.00	5.45	72.640	0.033	0.0	0.0	0.0	1.04	41.2	4.5
S5.002	50.00	5.60	72.500	0.033	0.0	0.0	0.0	1.21	48.2	4.5
S6.000	50.00	5.04	73.150	0.008	0.0	0.0	0.0	3.13	55.3	1.1
S1.005	50.00	6.01	72.400	0.127	0.0	0.0	0.0	1.19	47.3	17.2
S7.000	50.00	5.04	72.850	0.045	0.0	0.0	0.0	3.00	53.1	6.1
S1.006	50.00	6.03	72.230	0.172	0.0	0.0	0.0	1.60	63.8	23.3
S1.007	50.00	6.06	71.850	0.172	0.0	0.0	0.0	1.39	55.1	23.3

Integra Consulting (Engineers) Ltd		Page 4
First Floor, Suite 4 14-32 Hewsitt Street Manchester, M15 4GB		
Date 04/08/2021 16:13 File 3255 - MD.MDX	Designed by jansk Checked by	
Innovyze	Network 2019.1	

Manhole Schedules for Storm

MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Pipe Out Diameter (mm)	PN	Pipes In Invert Level (m)	Pipes In Diameter (mm)	Backdrop (mm)
S1	73.900	0.600	Open Manhole	225	S1.000	73.300	100				
S2	73.900	0.680	Open Manhole	225	S1.001	73.220	100	S1.000	73.220	100	
S3	73.900	0.830	Open Manhole	225	S1.002	73.070	100	S1.001	73.070	100	
S4	73.900	0.600	Open Manhole	225	S2.000	73.300	100				
S5	73.900	0.730	Open Manhole	225	S2.001	73.170	100	S2.000	73.170	100	
S6	73.900	0.510	Open Manhole	100	S3.000	73.390	100				
S4	73.900	0.970	Open Manhole	600	S1.003	72.930	150	S1.002	72.930	100	
								S2.001	72.930	100	
								S3.000	72.930	100	
S8	73.860	0.610	Open Manhole	100	S4.000	73.250	100				
S9	73.760	1.130	Open Manhole	1350	S4.001	72.630	225	S4.000	72.630	100	
S10	73.890	1.340	Open Manhole	1350	S4.002	72.550	225	S4.001	72.550	225	
S5	73.720	1.260	Open Manhole	1350	S1.004	72.460	225	S1.003	72.460	150	
								S4.002	72.460	225	
S12	73.860	0.610	Open Manhole	100	S5.000	73.250	100				
S13	73.770	1.130	Open Manhole	1350	S5.001	72.640	225	S5.000	72.640	100	
S14	73.800	1.300	Open Manhole	1350	S5.002	72.500	225	S5.001	72.500	225	
S15	73.600	0.450	Open Manhole	450	S6.000	73.150	150				
S6	73.670	1.270	Open Manhole	1350	S1.005	72.400	225	S1.004	72.400	225	
								S5.002	72.400	225	
								S6.000	72.400	150	
S17	73.560	0.710	Open Manhole	150	S7.000	72.850	150				
S7	73.640	1.410	Open Manhole	1350	S1.006	72.230	225	S1.005	72.230	225	
								S7.000	72.230	150	
S8	73.640	1.790	Junction		S1.007	71.850	225	S1.006	72.200	225	350
S9	73.570	1.740	Open Manhole	1200	S1.008	71.830	225	S1.007	71.830	225	
S	73.610	1.830	Open Manhole	0		OUTFALL		S1.008	71.780	225	

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
S1	252755.296	364703.438	252755.296	364703.438	Required	
S2	252749.604	364704.936	252749.604	364704.936	Required	

First Floor, Suite 4
14-32 Hewsitt Street
Manchester, M15 4GB

```
Date 04/08/2021 16:13
File 3255 - MD.MDX
```

Designed by jansk
Checked by



Innovyze

Network 2019.1

Manhole Schedules for Storm

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
S3	252752.613	364716.370	252752.613	364716.370	Required	
S4	252772.823	364700.117	252772.823	364700.117	Required	
S5	252775.420	364709.988	252775.420	364709.988	Required	
S6	252765.301	364711.037	252765.301	364711.037	Required	
S4	252763.368	364716.543	252763.368	364716.543	Required	
S8	252770.080	364693.533	252770.080	364693.533	Required	
S9	252779.026	364700.114	252779.026	364700.114	Required	
S10	252775.915	364713.036	252775.915	364713.036	Required	
S5	252763.595	364721.005	252763.595	364721.005	Required	
S12	252749.396	364699.003	252749.396	364699.003	Required	
S13	252745.397	364708.333	252745.397	364708.333	Required	
S14	252751.065	364729.753	252751.065	364729.753	Required	
S15	252769.217	364735.191	252769.217	364735.191	Required	
S6	252762.629	364730.883	252762.629	364730.883	Required	
S17	252753.630	364752.164	252753.630	364752.164	Required	

```
Date 04/08/2021 16:13
File 3255 - MD.MDX
```

Designed by jansk
Checked by



Network 2019.1

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
------------	---------------------------	----------------------------	--------------------------------	---------------------------------	-------------------	-------------------

Station	Wavelength (nm)	Wavelength (nm)	Wavelength (nm)	Wavelength (nm)	Requirement	Diagram
S7	252760.633	364751.316	252760.633	364751.316	Required	
S8	252760.449	364753.308			No Entry	
S9	252758.672	364753.144	252758.672	364753.144	Required	
S	252754.036	364753.931			No Entry	

Integra Consulting (Engineers) Ltd		Page 7
First Floor, Suite 4 14-32 Hewsitt Street Manchester, M15 4GB		
Date 04/08/2021 16:13 File 3255 - MD.MDX	Designed by jansk Checked by	
Innovyze	Network 2019.1	

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.000	o	100	S1	73.900	73.300	0.500	Open Manhole	225
S1.001	o	100	S2	73.900	73.220	0.580	Open Manhole	225
S1.002	o	100	S3	73.900	73.070	0.730	Open Manhole	225
S2.000	o	100	S4	73.900	73.300	0.500	Open Manhole	225
S2.001	o	100	S5	73.900	73.170	0.630	Open Manhole	225
S3.000	o	100	S6	73.900	73.390	0.410	Open Manhole	100
S1.003	o	150	S4	73.900	72.930	0.820	Open Manhole	600
S4.000	o	100	S8	73.860	73.250	0.510	Open Manhole	100
S4.001	o	225	S9	73.760	72.630	0.905	Open Manhole	1350
S4.002	o	225	S10	73.890	72.550	1.115	Open Manhole	1350
S1.004	o	225	S5	73.720	72.460	1.035	Open Manhole	1350
S5.000	o	100	S12	73.860	73.250	0.510	Open Manhole	100
S5.001	o	225	S13	73.770	72.640	0.905	Open Manhole	1350
S5.002	o	225	S14	73.800	72.500	1.075	Open Manhole	1350

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.000	5.885	73.6	S2	73.900	73.220	0.580	Open Manhole	225
S1.001	11.823	78.8	S3	73.900	73.070	0.730	Open Manhole	225
S1.002	10.757	76.8	S4	73.900	72.930	0.870	Open Manhole	600
S2.000	10.207	78.5	S5	73.900	73.170	0.630	Open Manhole	225
S2.001	13.719	57.2	S4	73.900	72.930	0.870	Open Manhole	600
S3.000	5.835	12.7	S4	73.900	72.930	0.870	Open Manhole	600
S1.003	4.468	9.5	S5	73.720	72.460	1.110	Open Manhole	1350
S4.000	11.106	17.9	S9	73.760	72.630	1.030	Open Manhole	1350
S4.001	13.292	166.2	S10	73.890	72.550	1.115	Open Manhole	1350
S4.002	14.673	163.0	S5	73.720	72.460	1.035	Open Manhole	1350
S1.004	9.925	165.4	S6	73.670	72.400	1.045	Open Manhole	1350
S5.000	10.151	16.6	S13	73.770	72.640	1.030	Open Manhole	1350
S5.001	22.157	158.3	S14	73.800	72.500	1.075	Open Manhole	1350
S5.002	11.620	116.2	S6	73.670	72.400	1.045	Open Manhole	1350

Integra Consulting (Engineers) Ltd		Page 8
First Floor, Suite 4 14-32 Hewsitt Street Manchester, M15 4GB		
Date 04/08/2021 16:13 File 3255 - MD.MDX	Designed by jansk Checked by	
Innovyze	Network 2019.1	

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S6.000	o	150	S15	73.600	73.150	0.300	Open Manhole	450
S1.005	o	225	S6	73.670	72.400	1.045	Open Manhole	1350
S7.000	o	150	S17	73.560	72.850	0.560	Open Manhole	150
S1.006	o	225	S7	73.640	72.230	1.185	Open Manhole	1350
S1.007	o	225	S8	73.640	71.850	1.565	Junction	
S1.008	o	225	S9	73.570	71.830	1.515	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S6.000	7.872	10.5	S6	73.670	72.400	1.120	Open Manhole	1350
S1.005	20.531	120.8	S7	73.640	72.230	1.185	Open Manhole	1350
S7.000	7.053	11.4	S7	73.640	72.230	1.260	Open Manhole	1350
S1.006	2.000	66.7	S8	73.640	72.200	1.215	Junction	
S1.007	1.784	89.2	S9	73.570	71.830	1.515	Open Manhole	1200
S1.008	4.702	94.0	S	73.610	71.780	1.605	Open Manhole	0

Integra Consulting (Engineers) Ltd		Page 9
First Floor, Suite 4 14-32 Hewsitt Street Manchester, M15 4GB		
Date 04/08/2021 16:13 File 3255 - MD.MDX	Designed by jansk Checked by	
Innovyze	Network 2019.1	

Area Summary for Storm

Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)
1.000	-	-	100	0.003	0.003	0.003
1.001	-	-	100	0.005	0.005	0.005
1.002	-	-	100	0.006	0.006	0.006
2.000	-	-	100	0.006	0.006	0.006
2.001	-	-	100	0.006	0.006	0.006
3.000	-	-	100	0.005	0.005	0.005
1.003	-	-	100	0.000	0.000	0.000
4.000	-	-	100	0.005	0.005	0.005
4.001	-	-	100	0.013	0.013	0.013
4.002	-	-	100	0.000	0.000	0.000
1.004	-	-	100	0.029	0.029	0.029
5.000	-	-	100	0.004	0.004	0.004
5.001	-	-	100	0.029	0.029	0.029
5.002	-	-	100	0.000	0.000	0.000
6.000	-	-	100	0.008	0.008	0.008
1.005	-	-	100	0.008	0.008	0.008
7.000	-	-	100	0.045	0.045	0.045
1.006	-	-	100	0.000	0.000	0.000
1.007	-	-	100	0.000	0.000	0.000
1.008	-	-	100	0.000	0.000	0.000
				Total	Total	Total
				0.172	0.172	0.172

Integra Consulting (Engineers) Ltd		Page 10
First Floor, Suite 4 14-32 Hewsitt Street Manchester, M15 4GB		
Date 04/08/2021 16:13 File 3255 - MD.MDX	Designed by jansk Checked by	
Innovyze	Network 2019.1	

Network Classifications for Storm

PN	USMH	Pipe	Min Cover	Max Cover	Pipe Type	MH	MH	MH Ring	MH Type
	Name	Dia	Depth	Depth		Dia	Width	Depth	
		(mm)	(m)	(m)		(mm)	(mm)	(m)	
S1.000	S1	100	0.500	0.580	Unclassified	225	0	0.500	Unclassified
S1.001	S2	100	0.580	0.730	Unclassified	225	0	0.580	Unclassified
S1.002	S3	100	0.730	0.870	Unclassified	225	0	0.730	Unclassified
S2.000	S4	100	0.500	0.630	Unclassified	225	0	0.500	Unclassified
S2.001	S5	100	0.630	0.870	Unclassified	225	0	0.630	Unclassified
S3.000	S6	100	0.410	0.870	Unclassified	100	0	0.410	Unclassified
S1.003	S4	150	0.820	1.110	Unclassified	600	0	0.820	Unclassified
S4.000	S8	100	0.510	1.030	Unclassified	100	0	0.510	Unclassified
S4.001	S9	225	0.905	1.115	Unclassified	1350	0	0.905	Unclassified
S4.002	S10	225	1.035	1.115	Unclassified	1350	0	1.115	Unclassified
S1.004	S5	225	1.035	1.045	Unclassified	1350	0	1.035	Unclassified
S5.000	S12	100	0.510	1.030	Unclassified	100	0	0.510	Unclassified
S5.001	S13	225	0.905	1.075	Unclassified	1350	0	0.905	Unclassified
S5.002	S14	225	1.045	1.075	Unclassified	1350	0	1.075	Unclassified
S6.000	S15	150	0.300	1.120	Unclassified	450	0	0.300	Unclassified
S1.005	S6	225	1.045	1.185	Unclassified	1350	0	1.045	Unclassified
S7.000	S17	150	0.560	1.260	Unclassified	150	0	0.560	Unclassified
S1.006	S7	225	1.185	1.215	Unclassified	1350	0	1.185	Unclassified
S1.007	S8	225	1.515	1.565	Unclassified				Junction
S1.008	S9	225	1.515	1.605	Unclassified	1200	0	1.515	Unclassified

Free Flowing Outfall Details for Storm

Outfall	Outfall	C. Level	I. Level	Min	D,L	W
Pipe Number	Name	(m)	(m)	I. Level	(mm)	(mm)
				(m)		

S1.008	S	73.610	71.780	0.000	0	0
--------	---	--------	--------	-------	---	---

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	0.500
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1

Number of Input Hydrographs	0	Number of Storage Structures	1
Number of Online Controls	1	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	M5-60 (mm)	18.150
Return Period (years)	2	Ratio R	0.385
Region England and Wales Profile Type Summer			

Integra Consulting (Engineers) Ltd		Page 11
First Floor, Suite 4 14-32 Hewsitt Street Manchester, M15 4GB		
Date 04/08/2021 16:13 File 3255 - MD.MDX	Designed by jansk Checked by	
Innovyze Network 2019.1		
Synthetic Rainfall Details Cv (Summer) 0.750 Storm Duration (mins) 30 Cv (Winter) 0.840		
©1982-2019 Innovyze		

Integra Consulting (Engineers) Ltd		Page 12
First Floor, Suite 4 14-32 Hewsitt Street Manchester, M15 4GB		
Date 04/08/2021 16:13 File 3255 - MD.MDX	Designed by jansk Checked by	
Innovyze	Network 2019.1	

Online Controls for Storm

Hydro-Brake® Optimum Manhole: S9, DS/PN: S1.008, Volume (m³): 2.0

Unit Reference	MD-SHE-0122-7000-1100-7000
Design Head (m)	1.100
Design Flow (l/s)	7.0
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	122
Invert Level (m)	71.830
Minimum Outlet Pipe Diameter (mm)	150
Suggested Manhole Diameter (mm)	1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.100	7.0
Flush-Flo™	0.324	7.0
Kick-Flo®	0.704	5.7
Mean Flow over Head Range	-	6.1

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	4.3	1.200	7.3	3.000	11.2	7.000	16.8
0.200	6.7	1.400	7.8	3.500	12.1	7.500	17.4
0.300	7.0	1.600	8.3	4.000	12.9	8.000	17.9
0.400	6.9	1.800	8.8	4.500	13.6	8.500	18.4
0.500	6.8	2.000	9.3	5.000	14.3	9.000	19.0
0.600	6.5	2.200	9.7	5.500	15.0	9.500	19.5
0.800	6.0	2.400	10.1	6.000	15.6		
1.000	6.7	2.600	10.5	6.500	16.2		

Integra Consulting (Engineers) Ltd		Page 13																																																																																	
First Floor, Suite 4 14-32 Hewsitt Street Manchester, M15 4GB																																																																																			
Date 04/08/2021 16:13 File 3255 - MD.MDX	Designed by jansk Checked by																																																																																		
Innovyze Network 2019.1																																																																																			
<u>Storage Structures for Storm</u> <u>Cellular Storage Manhole: S8, DS/PN: S1.007</u> Invert Level (m) 71.850 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>45.0</td><td>0.0</td><td>1.076</td><td>0.0</td><td>0.0</td></tr><tr><td>1.075</td><td>45.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <u>Manhole Headloss for Storm</u> <table><tr><th>PN</th><th>US/MH Name</th><th>US/MH Headloss</th></tr><tr><td>S1.000</td><td>S1</td><td>0.500</td></tr><tr><td>S1.001</td><td>S2</td><td>0.500</td></tr><tr><td>S1.002</td><td>S3</td><td>0.500</td></tr><tr><td>S2.000</td><td>S4</td><td>0.500</td></tr><tr><td>S2.001</td><td>S5</td><td>0.500</td></tr><tr><td>S3.000</td><td>S6</td><td>0.500</td></tr><tr><td>S1.003</td><td>S4</td><td>0.500</td></tr><tr><td>S4.000</td><td>S8</td><td>0.500</td></tr><tr><td>S4.001</td><td>S9</td><td>0.500</td></tr><tr><td>S4.002</td><td>S10</td><td>0.500</td></tr><tr><td>S1.004</td><td>S5</td><td>0.500</td></tr><tr><td>S5.000</td><td>S12</td><td>0.500</td></tr><tr><td>S5.001</td><td>S13</td><td>0.500</td></tr><tr><td>S5.002</td><td>S14</td><td>0.500</td></tr><tr><td>S6.000</td><td>S15</td><td>0.500</td></tr><tr><td>S1.005</td><td>S6</td><td>0.500</td></tr><tr><td>S7.000</td><td>S17</td><td>0.500</td></tr><tr><td>S1.006</td><td>S7</td><td>0.500</td></tr><tr><td>S1.007</td><td>S8</td><td>0.000</td></tr><tr><td>S1.008</td><td>S9</td><td>0.500</td></tr></table>			Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	45.0	0.0	1.076	0.0	0.0	1.075	45.0	0.0				PN	US/MH Name	US/MH Headloss	S1.000	S1	0.500	S1.001	S2	0.500	S1.002	S3	0.500	S2.000	S4	0.500	S2.001	S5	0.500	S3.000	S6	0.500	S1.003	S4	0.500	S4.000	S8	0.500	S4.001	S9	0.500	S4.002	S10	0.500	S1.004	S5	0.500	S5.000	S12	0.500	S5.001	S13	0.500	S5.002	S14	0.500	S6.000	S15	0.500	S1.005	S6	0.500	S7.000	S17	0.500	S1.006	S7	0.500	S1.007	S8	0.000	S1.008	S9	0.500
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																														
0.000	45.0	0.0	1.076	0.0	0.0																																																																														
1.075	45.0	0.0																																																																																	
PN	US/MH Name	US/MH Headloss																																																																																	
S1.000	S1	0.500																																																																																	
S1.001	S2	0.500																																																																																	
S1.002	S3	0.500																																																																																	
S2.000	S4	0.500																																																																																	
S2.001	S5	0.500																																																																																	
S3.000	S6	0.500																																																																																	
S1.003	S4	0.500																																																																																	
S4.000	S8	0.500																																																																																	
S4.001	S9	0.500																																																																																	
S4.002	S10	0.500																																																																																	
S1.004	S5	0.500																																																																																	
S5.000	S12	0.500																																																																																	
S5.001	S13	0.500																																																																																	
S5.002	S14	0.500																																																																																	
S6.000	S15	0.500																																																																																	
S1.005	S6	0.500																																																																																	
S7.000	S17	0.500																																																																																	
S1.006	S7	0.500																																																																																	
S1.007	S8	0.000																																																																																	
S1.008	S9	0.500																																																																																	
©1982-2019 Innovyze																																																																																			

Integra Consulting (Engineers) Ltd

Page 14

First Floor, Suite 4
14-32 Hewsitt Street
Manchester, M15 4GB

Date 04/08/2021 16:13
File 3255 - MD.MDX

Innovyze

Designed by jansk
Checked by

Network 2019.1



Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 0.500
Hot Start Level (mm) 0 Inlet Coeffiecient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1
Number of Online Controls 1 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.385
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 18.150 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status ON
DVD Status ON
Inertia Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
720, 960, 1440, 2160, 2880, 4320, 5760,
7200, 8640, 10080
Return Period(s) (years) 30
Climate Change (%) 0

	US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	Level
									(m)
S1.000	S1	15 Winter	30	+0%					73.325
S1.001	S2	15 Winter	30	+0%					73.264
S1.002	S3	15 Winter	30	+0%					73.132
S2.000	S4	15 Winter	30	+0%					73.337
S2.001	S5	15 Winter	30	+0%					73.220
S3.000	S6	15 Winter	30	+0%					73.411
S1.003	S4	15 Winter	30	+0%					72.978
S4.000	S8	15 Winter	30	+0%					73.272
S4.001	S9	15 Winter	30	+0%					72.697
S4.002	S10	15 Winter	30	+0%					72.673
S1.004	S5	15 Winter	30	+0%					72.666
S5.000	S12	15 Winter	30	+0%					73.270
S5.001	S13	15 Winter	30	+0%					72.721
S5.002	S14	15 Winter	30	+0%					72.645
S6.000	S15	15 Winter	30	+0%					73.172
S1.005	S6	15 Winter	30	+0%	30/15 Winter				72.631
S7.000	S17	15 Winter	30	+0%					72.907
S1.006	S7	15 Winter	30	+0%	30/15 Summer				72.524

©1982-2019 Innovyze

Integra Consulting (Engineers) Ltd		Page 15
First Floor, Suite 4 14-32 Hewsitt Street Manchester, M15 4GB		
Date 04/08/2021 16:13 File 3255 - MD.MDX	Designed by jansk Checked by	
Innovyze	Network 2019.1	

Summary of Critical Results by Maximum Level (Rank 1) for Storm

		Surcharged	Flooded			Pipe		
	US/MH	Depth	Volume	Flow /	Overflow	Flow		Level
PN	Name	(m)	(m³)	Cap.	(l/s)	(l/s)	Status	Exceeded
S1.000	S1	-0.075	0.000	0.15		0.9		OK
S1.001	S2	-0.056	0.000	0.40		2.5		OK
S1.002	S3	-0.038	0.000	0.69		4.5		OK
S2.000	S4	-0.063	0.000	0.29		1.8		OK
S2.001	S5	-0.050	0.000	0.50		3.8		OK
S3.000	S6	-0.079	0.000	0.10		1.5		OK
S1.003	S4	-0.102	0.000	0.23		9.7		OK
S4.000	S8	-0.078	0.000	0.11		1.5		OK
S4.001	S9	-0.158	0.000	0.16		5.7		OK
S4.002	S10	-0.102	0.000	0.15		5.3		OK
S1.004	S5	-0.019	0.000	0.62		20.9		OK
S5.000	S12	-0.080	0.000	0.09		1.2		OK
S5.001	S13	-0.144	0.000	0.28		10.6		OK
S5.002	S14	-0.080	0.000	0.23		9.3		OK
S6.000	S15	-0.128	0.000	0.05		2.4		OK
S1.005	S6	0.006	0.000	0.79		33.8	SURCHARGED	
S7.000	S17	-0.093	0.000	0.30		13.7		OK
S1.006	S7	0.069	0.000	1.54		46.1	SURCHARGED	

