




SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION

IN ADDITION TO THE HAZARDS/RISKS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, NOTE THE FOLLOWING

1. UTILITIES ARE PRESENT IN THIS AREA

2. ADJACENT TO HOSPITAL

3. ADJACENT TO SCHOOL

IT IS ASSUMED THAT ALL WORKS WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROVED METHOD STATEMENT

- NOTES
1. ALL DIMENSIONS ARE IN METRES UNLESS NOTED OTHERWISE.

2. ALL LEVELS ARE IN METRES RELATED TO ORDNANCE DATUM NEWLYN (OD) UNLESS NOTED OTHERWISE.

3. ALL COORDINATES ARE IN METRES RELATED TO ORDNANCE SURVEY NATIONAL GRID.

4. ALL MATERIALS AND WORKMANSHIP WILL BE AS DEFINED IN THE SPECIFICATION UNLESS NOTED OTHERWISE.

5. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL DRAWINGS AND DOCUMENTATION ASSOCIATED WITH THE PROJECT.

6. THIS DRAWING HAS BEEN BASED UPON SURVEY/OS INFORMATION SUPPLIED BY A THIRD PARTY AND SCP SHALL NOT BE LIABLE FOR ANY INACCURACY OR DEFICIENCIES ARISING FROM IT.

7. ALL LEVELS, DIMENSIONS AND LOCATIONS ARE TO BE CHECKED BY THE MAIN CONTRACTOR PRIOR TO COMMENCEMENT OF ANY WORK ON SITE.

8. ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH LOCAL AUTHORITY ADOPTABLE RESIDENTIAL ROAD SPECIFICATION AND STANDARD DETAILS.

KEY

PROPOSED FOOTWAY RESURFACING

PROPOSED KERB

PROPOSED EDGING KERB

PROPOSED BUFF COLOURED TACTILE PAVING

HIGHWAY BOUNDARY

PROPOSED ROAD SIGN

PROPOSED REFLECTIVE KEEP LEFT BOLLARD

DRAFT

REVISIONS			
REV	DESCRIPTION	DATE	BY
-	ISSUED FOR INFORMATION	21.05.21	JC

SCP

Transportation Planning : Infrastructure Design

Colewyn Chambers, 19 York Street, Manchester, M2 3BA, Tel 0161 632 4400.

www.scptransport.co.uk, Email info@scptransport.co.uk

Client Name:

VINCI CONSTRUCTION UK LTD

Project Title:

THE CHRISTIES HOSPITAL S278 WORKS

Drawing Title:

HEYSCROFT ROAD
GENERAL ARRANGEMENT

Date:	02.06.2021	Drawn By:	JL
Scale:	1:100 @ A1	Checked:	JAB
Status:	PLANNING	Approved:	UNAPPROVED

Drawing No.	Rev.
SCP-210142-0000-001	-

The diagram is a detailed site plan for the Heycroft Road project. It shows the layout of Heycroft Road, Cotton Lane, and various proposed road works. Key features include:

- Proposed Footway Resurfacing:** Indicated by thick black lines along the footways.
- Proposed Kerb and Edging Kerb:** Shown as blue lines.
- Proposed Buff Coloured Tactile Paving:** Represented by yellow hatched areas.
- Highway Boundary:** Marked with a red dashed line.
- Proposed Road Sign:** Indicated by a black circle with a white 'A'.
- Proposed Reflective Keep Left Bollard:** Represented by a blue square.
- Existing Features:** Includes existing buildings, houses, driveways, and parking areas.
- Proposed Traffic Island:** A triangular area in the center of the road.
- Proposed Tactile Paving:** A rectangular area near the traffic island.
- Proposed Tactile Crossing:** A rectangular area near the intersection.
- Proposed Road Sign:** A black circle with a white 'A'.
- Proposed Reflective Keep Left Bollard:** A blue square.
- Proposed Road Sign:** A black circle with a white 'A'.
- Proposed Reflective Keep Left Bollard:** A blue square.

© Crown Copyright. All Rights Reserved. 2018 Licence Number 0100031673