



39 Deansgate, Manchester

Flood Risk Assessment & Drainage Strategy Report

For: Kames Property Income Fund

IGE Consulting
Bartle House
Oxford Court
Manchester
M2 3WQ

Tel 0161-914-9170
Email contact@igeconsulting.co.uk

Ref: 3174-03

Rev: D
By: NS

Date: July 2021

REVISIONS

Revision	Date	Prepared By	Authorised By	Remarks
First Issue	11 th September 2019	 Neville Shaw	 Andrew Edwards	-
Revision A	23 rd December 2019	 Neville Shaw	 Andrew Edwards	Updated following receipt of amended proposed development plans
Revision B	30 th January 2020	 Neville Shaw	 Andrew Edwards	Updated site area
Revision C	20 th July 2021	 Neville Shaw	 Andrew Edwards	Updated client and site details
Revision D	30 th July 2021	-	 Andrew Edwards	Updated Site Details



CONTENTS

1.0 INTRODUCTION

2.0 STANDARDS AND LIMITATIONS

3.0 CURRENT SITUATION

- 3.1 Site Location and Description
- 3.2 Hydrology and Flooding
- 3.3 Existing Sewers

4.0 PROPOSED DEVELOPMENT

- 4.1 Development Proposals
- 4.2 Surface Water Drainage
- 4.3 SuDS Feasibility
- 4.4 National Planning Policy Framework and Technical Guidance
- 4.5 EA Mapping Review
- 4.6 Safe Access and Egress
- 4.7 Foul Water Drainage

5.0 CONCLUSIONS

- 5.1 Flooding
- 5.2 Site Surface Water Drainage
- 5.3 Site Foul Water Drainage
- 5.4 Flood Risk Management Measures
- 5.5 Off Site Impacts
- 5.6 Residual Risk

APPENDICES

APPENDIX 1	SITE LOCATION PLAN
APPENDIX 2	ENVIRONMENT AGENCY FLOOD MAPPING
APPENDIX 3	EXISTING TOPOGRAPHICAL SURVEY
APPENDIX 4	UNITED UTILITIES SEWER PLANS
APPENDIX 5	EXISTING DRAINAGE SURVEY DATA

1.0 INTRODUCTION

IGE Consulting has been commissioned by *Kames Property Income Fund* to undertake a Flood Risk Assessment and Drainage Strategy report for a site at 39 Deansgate, Manchester. This document has been prepared to accompany the full planning application for the proposed commercial re-development of the application site.

The objective of this Flood Risk Assessment and Drainage Strategy is to identify potential drainage / flooding issues and any consequent implications on the proposed site development. Both existing and proposed surface water and foul water drainage for the development site are considered.

The Flood Risk Assessment and Drainage Strategy has been undertaken in accordance with the pro-forma guidance contained in:

- Department for Communities and Local Government document 'National Planning Practice Guidance: Flood Risk and Coastal Change'
- Manchester City, Salford City and Trafford Councils Level 1 Strategic Flood Risk Assessment (SFRA) dated May 2010 and Level 2 SFRA dated March 2011
- CIRIA SuDS Manual C753 dated 2015
- DEFRA / Environment Agency publication SC030219 'Rainfall Runoff Management for Developments' dated October 2013.
- National Planning Policy Framework published in March 2012, and revised in July 2018

To date, consultations have been undertaken with the Environment Agency (EA) and United Utilities (UU).

2.0 STANDARDS AND LIMITATIONS

This report has been prepared solely for use by *Kames Property Income Fund*.

It shall not be relied upon or transferred to any other party without the prior written authorisation of IGE Consulting.

The findings and opinions in the report are based on information derived from a variety of different sources. IGE Consulting do not accept any liability for the accuracy or otherwise of any information provided by third parties.

It should be noted that some of the aspects considered in this study may be subject to change with time. Therefore, if the development is delayed or postponed, consideration may need to be given to reviewing such issues to confirm that no changes have taken place, either at the site or within relevant legislation.

Further consultations with statutory bodies are likely as the scheme progresses. It should be noted that even where responses have been received from Regulators, these could be subject to change at a later date.

3.0 CURRENT SITUATION

3.1 Site Location and Description

The Site is irregular in shape and comprises an area of 0.12 ha (1,227m²). It is bound by Deansgate to the West, St Mary's Gate to the North, the Grade II* listed Barton Arcade to the South and by 12-14 St Mary's Gate to the East. It situated within the St Ann's Conservation Area.

The existing building has a net area of 3,754m² (40,408sq. ft) with accommodation arranged over ground, mezzanine, and eight upper floors. The ground floor, circa 1,116m² (12,013sq. ft) is occupied by a variety retail tenants whilst the upper floors are currently used as offices, with an area in excess of 2,638m² (28,395sq. ft).

The Site is currently serviced by an alley leading to a yard accessed via the pedestrianised Exchange Street / St. Ann's Square to the East.

This existing site is wholly developed and is currently positively drained (refer to drainage survey in Appendix 5 and topographical / existing drainage connectivity survey in Appendix 3).

The site is generally level with the existing building ground floor level varying from circa 36.5m AOD to 37.0m AOD (refer to topographical / existing drainage connectivity survey in Appendix 3).

3.2 Hydrology and Flooding

Current Environment Agency flood data indicates the site to lie wholly in Flood Zone 1 - refer to Appendix 2 for details.

EA / DEFRA flood mapping generally indicates a very low probability of surface water flooding across the site with a localised area in the south east corner of the site identified to have a low to medium risk of surface water flooding.

The site is shown to lie outside the maximum extent of flooding area from reservoirs.

The nearest watercourse to the site is the River Irwell which lies circa 175m to the west of the site development boundary.

3.3 Existing Sewers

The adopted sewers present in the vicinity of the proposed development site are noted as follows - refer to Appendix 4 for United Utilities (UU) sewer plans and Appendix 3 for topographical survey including the existing drainage survey:

- 700mm x 1600mm brick combined sewer extending from east to west beneath St Mary's Gate;
- 2300mm diameter combined sewer extending from north to south beneath Deansgate;
- 100mm diameter combined sewer extending from south to north beneath the existing passageway directly to the east of the subject site adjacent to 12-14 St Mary's Gate;
- 150mm diameter combined sewer extending from east to west across the envelope of the development site;
- 150mm diameter combined sewer indicated to extend from north to south beneath the eastern pavement of Deansgate.

An existing drainage survey has been undertaken at the site (refer to Appendix 5 for details) which indicates that existing site surface water discharges into the system of 150mm diameter adopted combined sewers adjacent to / crossing the site envelope.

Existing foul water from the site is also indicated to discharge into the system of 150mm diameter adopted combined sewers adjacent to / crossing the site envelope.

The new building arrangement includes a full basement. This new arrangement, together with the level of the existing adopted sewer system crossing the site, will necessitate the diversion of the existing 100mm / 150mm combined sewer system by

lowering it to sit directly beneath the new basement slab level. The exact future alignment and level of this length of adopted sewer are subject to detailed design of the proposed building and associated liaison / negotiation with United Utilities.

4.0 PROPOSED DEVELOPMENT

4.1 Development Proposals

It is proposed to undertake the erection of a 17 storey building comprising office use (Use Class E(g)(i)) and flexible ground floor commercial units (Use Classes E(a),(b),(c) and sui generis 'drinking establishment'), new electricity sub-station, basement cycle parking and rooftop plant enclosure, together with access, servicing and associated works following demolition of the existing building- refer to proposed site plans submitted as part of the planning application.

4.2 Surface Water Drainage

The issue of surface water drainage to the proposed development has been considered with reference to the hierarchy of surface water disposal as noted in the Building Regulations H3:

- i) Sustainable Urban Drainage Systems (SUDS)
- ii) Discharge of surface water off site direct to watercourse
- iii) Discharge to adopted sewer

SUDS are made up of one or more structures built to manage surface water runoff. They are used in conjunction with good management of the site to prevent flooding and pollution. There are four general methods of control:

- Filter strips and swales
- Filter drains and permeable surfaces
- Infiltration devices
- Basins and Ponds

The nature of this development (full basement) clearly precludes the use of soakaways and permeable surfaces for post-development surface water drainage.

The nearest water course is the River Irwell which lies circa 175m to the west of the site through numerous third part ownerships. It is therefore not considered practical to discharge post-development surface water to the River Irwell.

Given the nature of the site and the proposed build, the only pragmatic method of post-development surface water discharge is to the adopted combined system present adjacent / within the site envelope. The existing drainage survey superimposed onto the site topographical survey (refer to Appendix 3) indicates that the 150mm diameter sewer extending from UU manhole 7515 discharges into the adjacent 2300mm diameter combined sewer beneath Deansgate via UU manhole 7506.

The new building arrangement includes a full basement. This new arrangement, together with the level of the existing adopted sewer system crossing the site, will necessitate the diversion of the existing adopted 100mm / 150mm combined sewer by lowering it to sit directly beneath the new basement slab level. The exact future alignment and level of this length of adopted sewer are naturally subject to detailed design of the proposed building and associated liaison / negotiation with United Utilities. It is therefore proposed that post-development surface water discharges directly to the adopted combined sewer system at location(s) along its diverted line to suit the detailed building design.

Due to the building functional requirements, it is not feasible to accommodate post-development surface water storage within the new building envelope and hence it is considered pragmatic for post-development surface water from the 0.11 hectare development site to discharge unattenuated (as existing) into the adjacent UU adopted combined sewer system.

4.3 SuDS Feasibility

One SuDS measure that is considered feasible in the context of the nature of the proposed development is noted below:

- Blue / Green Roofs: It is proposed to utilise a 'blue' roof system in order to collect rainwater, provide attenuation then release water slowly after rainfall has ceased (refer to proposed development plans submitted for details).

Other SuDS measures are not considered appropriate at this development – refer to the reasoning set out below:

- Underground Storage: Due to the building functional requirements, it is not feasible to accommodate post-development surface water storage within the new building envelope.
- Rainwater Harvesting: In accordance with BS8515: 2009 + A1: 2013, the annual demand of the commercial building will be greater than the annual rainwater yield. Therefore, the use of rainwater harvesting is not a feasible SuDS method. Furthermore, the various functional requirements of the development scheme dictate that there is not available space to accommodate rainwater harvesting.
- Soakaway: The proposed basement covering the full site area precludes the use of this option.
- Filter Strips: The proposed basement area occupies the whole site area hence filter strips are not feasible.
- Permeable Paving: The proposed basement area occupies the whole site area and therefore permeable paving is not feasible.
- Bioretention Area: The proposed basement area occupies the whole site area and therefore a bioretention area is not feasible.
- Swale: The proposed basement area occupies the whole site area and therefore swales are not feasible.
- Hardscape Storage: The proposed basement area occupies the whole site area and therefore hardscape storage is not feasible.
- Pond / Basin: The proposed basement area occupies the whole site area and therefore ponds / basins are not feasible.

4.4 National Planning Policy Framework and Technical Guidance

The commercial site development proposals are classed as 'less vulnerable' in Table 2 of the Flood Risk and Coastal Change guidance.

'Less vulnerable' developments in Flood Zone 1 are classed as appropriate according to Table 3 of the Flood Risk and Coastal Change guidance.

Proposed post development levels will be engineered in order to protect the development and not provide any increased flood risk elsewhere. Types of flooding that could affect the site are:

River	the site is in Flood Zone 1
Sea	there is no risk of flooding from the sea
Land	there are no undrained land slopes towards the site
Groundwater	there are no springs or weep areas on the site
Sewers	there have been no local reports of sewer surcharge

4.5 EA Mapping Review

There are no groundwater protection zones in the vicinity of the site and there is negligible residual fluvial risk. The site is not noted to lie within a flood warning area.

4.6 Safe Access and Egress

Safe access / egress from the site in extreme conditions will be via the entrance on Deansgate.

4.7 Foul Water Drainage

It is proposed to discharge post-development foul water to the existing adopted combined sewer system in Deansgate via connection(s) along the diverted sewer line (refer to clause 4.2 for details).

The foul drainage network (as indicated in Appendix 4) will naturally comply with Building Regulations 2010 – Approved Document H1 and future calculations for post-development foul water discharge will be based on Sewers for Adoption 8th Edition.

5.0 CONCLUSIONS

5.1 Flooding

Following review of the Environment Agency flood maps and data, it has been confirmed that the site lies wholly in Flood Zone 1.

5.2 Site Surface Water Drainage

There will be no change in hard surfaced area at the post-development site in relation to the current situation.

It is proposed to discharge post-development surface water to the adopted combined sewer system at locations along the diverted sewer line (within the new building envelope) to suit the detailed building design (refer to clause 4.2 for details).

All feasible SuDS methods have been assessed given the nature and location of the development site (refer to section 4.3 for details) – none are considered feasible other than the blue roof system (which work by retaining the flow of water into the sewer system).

5.3 Site Foul Water Drainage

It is proposed to discharge post-development foul water to the adopted combined sewer system via connection(s) along the diverted sewer line to suit the detailed building design (refer to clause 4.2 for details).

5.4 Flood Risk Management Measures

There will be a site management Health and Safety document prepared in respect of the site.

5.5 Off Site Impacts

All roofed and paved areas are to be formally drained into the site surface water drainage system.


5.6 Residual Risk

With careful design of the drainage elements as described above, there will be no residual flood related risks remaining after the development has been completed.

A post-development safe emergency access can be maintained at all times during a flood event. Emergency access will be from Deansgate.

APPENDIX 1
SITE LOCATION PLAN

APPENDIX C - TITLE PLAN



Official copy of register of title

- Title number LA14037
- Edition date 11.07.2016
- This official copy shows the entries on the register of title on 21 JUL 2017 at 14:45:54.
 - This date must be quoted as the "search from date" in any official search application based on this copy.
 - The date at the beginning of an entry is the date on which the entry was made in the register.
 - Issued on 21 Jul 2017.
 - Under s.67 of the Land Registration Act 2002, this copy is admissible in evidence to the same extent as the original.
 - This title is dealt with by HM Land Registry, Fylde Office.

A: Property Register

This register describes the land and estate comprised in the title. Except as mentioned below, the title includes any legal easements granted by the registered lease but is subject to any rights that it reserves, so far as those easements and rights exist and benefit or affect the registered land.

- GREATER MANCHESTER : MANCHESTER
- (07.09.1962) The Leasehold land shown edged with red on the plan of the above Title filed at the Registry and being Speakers House, 39 Deansgate, Manchester (M3 2BA).
 - The mines and minerals are excepted.
 - (07.09.1962) Short particulars of the lease(s) (or under-lease(s)) under which the land is held:
Date : 31 July 1962
Term : 99 years from 27 April 1960
Rent : £17250
Parties : (1) The Lord Mayor Aldermen and Citizens of The City of Manchester
(2) Coal Industry (Nominees) Limited
 - There are excepted from the effect of registration all estates, rights, interests, powers and remedies arising upon, or by reason of, any dealing made in breach of the prohibition or restriction against dealings therewith inter vivos contained in the Lease.
 - Unless otherwise mentioned the title includes any legal easements granted by the registered lease(s) but is subject to any rights that it reserves, so far as those easements and rights exist and benefit or affect the registered land.
 - (01.05.2007) A new title plan based on the latest revision of the Ordnance Survey Map has been prepared.

B: Proprietorship Register

This register specifies the class of title and identifies the owner. It contains any entries that affect the right of disposal.

Title absolute

Title number LA14037

B: Proprietorship Register continued

- 1 (20.11.2015) PROPRIETOR: TARGET REAL ESTATE LLP (LLP Regn. No. OC397354) of 111 Edmund Street, Birmingham B3 2HJ.
- 2 (20.11.2015) The price stated to have been paid on 4 November 2015 was £7,645,000 exclusive of VAT.
- 3 (20.11.2015) A Transfer of the land in this title dated 4 November 2015 made between (1) The Royal London Mutual Insurance Society Limited and (2) Target Real Estate Llp contains purchaser's personal covenants.

NOTE:-Copy filed.
- 4 (20.11.2015) RESTRICTION: No disposition of the registered estate by the proprietor of the registered estate is to be registered without a written consent signed by the proprietor for the time being of the Charge dated 4 November 2015 in favour of ICG-Longbow Debt Investments No 4 S.A.R.L. referred to in the Charges Register or its conveyancer.
- 5 (11.07.2016) RESTRICTION: No disposition of the registered estate by the proprietor of the registered estate is to be registered without a written consent signed by the proprietor for the time being of the Charge dated 27 June 2016 in favour of N M Rothschild & Sons Limited referred to in the Charges Register or their conveyancer.

C: Charges Register

This register contains any charges and other matters that affect the land.

- 1 The parts of the land affected thereby are subject to the leases set out in the schedule of leases hereto.
The leases grant and reserve easements as therein mentioned.
- 2 Deed dated 20 December 1963 made between (1) The Lord Mayor Aldermen and Citizens of The City of Manchester, (2) Coal Industry (Nominees) Limited (3) Polewin Properties Investments Limited (4) The Prudential Assurance Company Limited and (5) General Store Holdings Limited relates to rights of light and re-building.
- 3 (20.11.2015) REGISTERED CHARGE contained in a Supplemental Debenture dated 4 November 2015.

NOTE: See the entry below altering the priority of this charge.
- 4 (20.11.2015) Proprietor: ICG-LONGBOW DEBT INVESTMENTS NO.4 S.A.R.L. (incorporated in Luxembourg) of 2 Boulevard Konrad Adenauer, L-1115 Luxembourg, Luxembourg.
- 5 (20.11.2015) The proprietor of the Charge dated 4 November 2015 referred to above is under an obligation to make further advances. These advances will have priority to the extent afforded by section 49(3) Land Registration Act 2002.
- 6 (11.07.2016) REGISTERED CHARGE contained in a Debenture dated 27 June 2016 affecting also other titles.

NOTE 1: Charge reference CYM252650.
NOTE 2: See the entry below altering the priority of this charge.
- 7 (11.07.2016) Proprietor: N M ROTHSCHILD & SONS LIMITED (Co. Regn. No. 00925279) of New Court, 1-10 St. Swithin's Lane, London EC4N 8AL.
- 8 (11.07.2016) The proprietor of the Charge dated 27 June 2016 referred to above is under an obligation to make further advances. These advances will have priority to the extent afforded by section 49(3) Land Registration Act 2002.
- 9 (11.07.2016) The priorities of the charges dated 27 June 2016 and 4 November 2015 referred to above have been altered by a Intercreditor Agreement dated 27 June 2016.

Schedule of notices of leases

Title number LA14037

1	02.02.2010 7 (part of)	43 Deansgate, Manchester (ground floor only)	22.01.2010 15 years from 22.1.2010	MAN155326
2	01.11.2010 7 (part of)	41 Deansgate, Manchester (ground floor)	24.09.2010 10 years from 24.9.2010	MAN167405
3	12.05.2011 4 (part of) and 5 (part of)	10/12 St Mary's Gate (ground floor) and (ground and first floor)	06.04.2011 10 years from 6.4.2011	MAN175709
4	27.09.2011 4 (part of)	8 St Mary's Gate (ground and first/mezzanine floors)	13.09.2011 15 years from 5.9.2011	MAN181718
5	10.05.2013 edged and numbered 8 in blue (part of)	47 Deansgate (ground floor)	18.04.2013 15 years from and including 18.04.2013	MAN208678
6	23.04.2014 edged and numbered 7 in blue (part of)	7th floor, Speakers House, 39 Deansgate	26.03.2014 from 24/3/2014 until 5/4/2021	MAN225620
7	19.09.2014 Edged and numbered 6 in blue (part of)	49 Deansgate (ground and first floors)	04.09.2014 10 years from and including 29.9.2013	MAN233372
8	29.10.2014 Edged and numbered 7 in blue (part of) and 8 in blue (part of)	45 Deansgate (Ground and first floors)	22.10.2014 10 years from 22/10/2014	MAN236289

End of register

APPENDIX 2

ENVIRONMENT AGENCY FLOOD MAPPING

Flood map for planning

Your reference
Deansgate

Location (easting/northing)
383768/398505

Created
6 Sep 2019 19:36

Your selected location is in flood zone 1, an area with a low probability of flooding.

This means:


- you don't need to do a flood risk assessment if your development is smaller than 1 hectare and not affected by other sources of flooding
- you may need to do a flood risk assessment if your development is larger than 1 hectare or affected by other sources of flooding or in an area with critical drainage problems

Notes

The flood map for planning shows river and sea flooding data only. It doesn't include other sources of flooding. It is for use in development planning and flood risk assessments.

This information relates to the selected location and is not specific to any property within it. The map is updated regularly and is correct at the time of printing.

The Open Government Licence sets out the terms and conditions for using government data.
<https://www.nationalarchives.gov.uk/doc/open-government-licence/version/3/>



Flood map for planning

Your reference

Deansgate

Location (easting/northing)

383768/398505

Scale

1:2500

Created

6 Sep 2019 19:36

-  Selected point
-  Flood zone 3
-  Flood zone 3: areas benefiting from flood defences
-  Flood zone 2
-  Flood zone 1
-  Flood defence
-  Main river
-  Flood storage area


 0 20 40 60m

APPENDIX 3
EXISTING TOPOGRAPHICAL SURVEY

APPENDIX 4
UNITED UTILITIES SEWER PLANS

Integra Consulting

**14-32
Hewitt Street,
Manchester,
M15 4GB**

FAO:

How to contact us:

**United Utilities Water Limited
Property Searches
Haweswater House
Lingley Mere Business Park
Great Sankey
Warrington
WA5 3LP**

Telephone: 0370 7510101

E-mail: propertysearches@uuplc.co.uk

**Your Ref: 39 Deansgate
Our Ref: UUPS-ORD-121212
Date: 02/09/2019**

Dear Sirs

Location: Deansgate

I acknowledge with thanks your request dated 31/08/2019 for information on the location of our services.

Please find enclosed plans showing the approximate position of United Utilities' apparatus known to be in the vicinity of this site.

The enclosed plans are being provided to you subject to the United Utilities terms and conditions for both the wastewater and water distribution plans which are shown attached.

If you are planning works anywhere in the North West, please read United Utilities' access statement before you start work to check how it will affect our network. <http://www.unitedutilities.com/work-near-asset.aspx>.

I trust the above meets with your requirements and look forward to hearing from you should you need anything further.

If you have any queries regarding this matter please [contact us](#).

Yours Faithfully,




Karen McCormack
Property Searches Manager

TERMS AND CONDITIONS - WASTEWATER AND WATER DISTRIBUTION PLANS

These provisions apply to the public sewerage, water distribution and telemetry systems (including sewers which are the subject of an agreement under Section 104 of the Water Industry Act 1991 and mains installed in accordance with the agreement for the self construction of water mains) (UUWL apparatus) of United Utilities Water Limited "(UUWL)".

TERMS AND CONDITIONS:

- This Map and any information supplied with it is issued subject to the provisions contained below, to the exclusion of all others and no party relies upon any representation, warranty, collateral contract or other assurance of any person (whether party to this agreement or not) that is not set out in this agreement or the documents referred to in it.
- This Map and any information supplied with it is provided for general guidance only and no representation, undertaking or warranty as to its accuracy, completeness or being up to date is given or implied.
- In particular, the position and depth of any UUWL apparatus shown on the Map are approximate only. UUWL strongly recommends that a comprehensive survey is undertaken in addition to reviewing this Map to determine and ensure the precise location of any UUWL apparatus. The exact location, positions and depths should be obtained by excavation trial holes.
- The location and position of private drains, private sewers and service pipes to properties are not normally shown on this Map but their presence must be anticipated and accounted for and you are strongly advised to carry out your own further enquiries and investigations in order to locate the same.
- The position and depth of UUWL apparatus is subject to change and therefore this Map is issued subject to any removal or change in location of the same. The onus is entirely upon you to confirm whether any changes to the Map have been made subsequent to issue and prior to any works being carried out.
- This Map and any information shown on it or provided with it must not be relied upon in the event of any development, construction or other works (including but not limited to any excavations) in the vicinity of UUWL apparatus or for the purpose of determining the suitability of a point of connection to the sewerage or other distribution systems.
- No person or legal entity, including any company shall be relieved from any liability howsoever and whensoever arising for any damage caused to UUWL apparatus by reason of the actual position and/or depths of UUWL apparatus being different from those shown on the Map and any information supplied with it.
- If any provision contained herein is or becomes legally invalid or unenforceable, it will be taken to be severed from the remaining provisions which shall be unaffected and continue in full force and affect.
- This agreement shall be governed by English law and all parties submit to the exclusive jurisdiction of the English courts, save that nothing will prevent UUWL from bringing proceedings in any other competent jurisdiction, whether concurrently or otherwise.



Refo	Cover	Func	Invert	Size x	Size y	Shape	Mat	Length	Grad
7234	41.57	CO	150	2.02599	100	VC	40.93669	1 in 27	
8203	35.83	CO	110.4	800		VC	16.7505	1 in 186	
9407	40.82	CO	31.03	225		VC	4.121168	1 in 150	
8802	30.95	CO	22.78	700		BR	71.19691	1 in 4	
9219		CO	150			VC	1.277161		
8230		CO	150			VC	12.17195		
9804	34.17	CO	31.1			VC	6.324555		
5703	29.27	CO	31.1			VC	20.1553		
5608		CO	24.17	500		BR	32.3925		
7704	26.7	CO	24.72	150		VC	11.04485		
6312	35.88	CO	30.65	1500		CO	48.70318		
9190	42.4	CO	37.69	1500		CO	24.35339		
7404		CO	150			VC	19.7096		
6203	35.7	CO	23.05	1275		VC	5.385165		
5202	35.26	CO	31.23	150		VC	9.848569		
5709	27.23	CO	24.28	150		VC	7.015773		
8309		CO	150			VC	3.09886		
7515		CO	150			VC	28.14859		
6206	35.66	CO	31.91	600		CO	8.944272	1 in 25	
7203	35.24	CO	33.37	450		VC	18.43905	1 in 164	
7510		CO	150			VC	4.836473		
9401	37.17	CO	28.79	375		VC	42.26768	1 in 204	
5609	26.81	CO	24	450		BR	30.4795	1 in 88	
5402	33.95	CO	28.24	300		VC	77.7811		
7411	36.15	CO	25.52	1500		CO	19.69772	1 in 67	
7302	36.54	CO	0	1500		CO	107.2179		
7424		CO	150			VC	1.83088		
8310		CO	150			VC	4.474855		
7238		CO	150			VC	6.118559		
6705	26.85	CO	22.54	300		VC	2.87207		
5328		CO	150			VC	4.231385		
8203	37.8	CO	32.82	400		VC	11.07758	1 in 58	
7505		CO	150			VC	14.13708	1 in 1	
9601	35.16	CO	27.85	100		VC	12.68111	1 in 107	
8410	38.23	CO	28.36	500		PE	18.14539		
7602		CO	0	2300		VC	4.37267		
5707	29.24	CO	0	375		VC	76.32169		
7305	36.55	CO	30.44	600		BR	5.385165	1 in 61	
9307	38.74	CO	35.62	300		VC	89.73815	1 in 61	
9706	35.3	CO	0	150		VC	3.162278		
5222		CO	27.17	150		VC	26.65333	1 in 167	
4301	33.01	CO	27.17	150		VC	2.498542	1 in 1	
8215	38.29	CO	35.26	400		VC	25.46346	1 in 31	
5508	26.54	SW	24.32	150		VC	2.23068	1 in 1	
0405	42.15	CO	28.53	700		BR	11.70457	1 in 225	
8312	36.86	CO	31.5	600		CO	20.2496	1 in 225	
6703		CO	45.52	450		VC	65.87265	1 in 1279	
8713		CO	375			VC	4.185113		
6207	35.66	CO	31.34	375		CI	50.92151		
8227		CO	31.53	600		VC	27.313	1 in 67	
7410	37.17	CO	31.4	100		VC	3.213574	1 in 47	
8327	28.93	CO	23.64	150		VC	39.29444	1 in 258	
9809		CO	600			VC	3.514048		
7302	36.54	CO	28.47	1500		CO	8.139123	1 in 1	
9612	27.09	CO	27.75	225		BR	41.2106	1 in 885	
9406	39.23	CO	37.53	225		VC	99.47864	1 in 117	
8304	37.03	CO	33.07	500		VC	20.14531	1 in 32	
6712	26.97	SW	25.98	150		VC	48.60443	1 in 117	
5206		CO	225			VC	40.09577	1 in 32	
6215		CO	150			VC	14.76482	1 in 1	
5224		CO	32.75	330		BR	8.82672	1 in 1	
6208	35.97	CO	32.75	300		VC	14.89862	1 in 50	
8313	36.83	CO	31.57	1500		BR	41.62415	1 in 50	
5201	36	CO	27.36	500		VC	20.1553	1 in 73	
6306	35.83	CO	0	375		CO	105.5462		
8890	39.77	CO	0	600		BR	50.96077	1 in 348	
8311	37.12	CO	28.13	1050		VC	9.219544	1 in 625	
7408	36.06	CO	22.1	2300		PE	7.21102	1 in 885	
4700	28.07	CO	17.618	600		BR	187.5527	1 in 9	
7211	37.01	CO	30.72	430		BR	37.57659	1 in 284	
6706	26.64	CO	24.15	150		VC	10.01802	1 in 778	
5701	28.18	CO	23.28	500		BR	14.21267	1 in 1	
7802	28.6	CO	22.21	450		BR	54.34251		
8317	36.69	CO	28.19	300		VC	56.17143		
8406		CO	150			VC	1.642787	1 in 187	
9305	39.21	CO	31.37	600		VC	20.21628		
6204	35.52	CO	28.3	450		VC	8.43391		
0301	44.48	CO	40.58	540		BR	36.65797		
5626		CO	150			VC	7.196777		
5714	27.59	CO	0	150		CI	3.68551	1 in 32	
5505	26.81	CO	23.18	225		VC	7.071068		
5301	33.38	CO	32.3	300		VC	20.2496	1 in 143	
7109		CO	32.3	150		VC	2.20665	1 in 28	
7426		CO	28.36	150		VC	25.91784	1 in 138	
8403	36.74	CO	28.36	450		VC	5.83052		
8209	38.67	CO	33.53	300		VC	17.88864		
9705	35.27	CO	32.7	225		BR	99.43329		
5817	28.96	CO	0	2100		VC	57.17316		
9402	36.66	CO	28.51	400		VC	5.747467	1 in 204	
6410		CO	0	390		VC	12.77792	1 in 166	
5601	35.35	CO	28.37	225		VC	22.8452	1 in 4	
6601		CO	300			VC	2.82947	1 in 67	
5704	27.78	CO	22.15	450		VC	4.101243	1 in 204	
5502	26.94	CO	22.34	300		VC	86.17817	1 in 236	
8201	39	CO	33.06	400		VC	16.40122	1 in 61	
5608		CO	150			VC	9.5852911		
5507	26.56	SW	25.18	150		VC	1.413869		
6504	26.53	SW	25.18	150		VC	30.3116	1 in 25	
7308	36.39	CO	30.39	375		VC	11.50125	1 in 49	
5203	34.88	CO	31.65	150		BR	23.89055		
7308	27.27	CO	22.27	450		VC	8.83052	1 in 11	
0201	44.68	CO	41.15	450		BR	38.18377	1 in 243	
7332		CO	150			VC	12.16553	1 in 35	
8210		CO	100			VC	6.624982	1 in 58	
0209	46.31	CO	40.06	300		PE	27.83223		
7705	26.85	CO	11.50125	450		BR	13.0147	1 in 25	
6205	35.55	CO	22.05	2300		VC	20.5863	1 in 45	
6506	34.84	CO	28.33	300		VC	23.89055		
6506	34.1	CO	24.8	300		VC	16.12452	1 in 44	
9415		SW	35.66	225		VC	12.30985	1 in 56	
9414	38.02	CO	32.15	500		VC	18.10777	1 in 44	
7514		CO	150			VC	7.28011	1 in 79	
8218	38.49	CO	34.43	400		VC	3.789728	1 in 45	
5509	26.85	CO	24.49	150		VC	16.73355	1 in 70	
9703	35.29	CO	30.94	375		VC	2.23068	1 in 691	
8401	37.17	CO	28.79	375		VC	34.52535	1 in 45	
7204	36.37	CO	33.41	450		VC	7.615773	1 in 879	
8604		CO	0	1800		VC	3.609745	1 in 35	
6220		CO	225			BR	52.73185	1 in 8	
5303	33.64	CO	28.4	1500		CO	16.73355		
6307	35.84	CO	30.83	600		VC	21.80329		
7502	36.25	CO	25.01	1200		VC	9.219544	1 in 49	
0303	43.86	CO	35.49	450		VC	7.615773	1 in 46	
5605	27.25	CO	23.5	300		VC	17.35455	1 in 98	
5509		CO	0	930		VC	11.01292		
8333		CO	31.79	900		PSC	2.934509	1 in 18	
8115		CO	31.19	600		BR	11.31291	1 in 17	
9310		CO	225			VC	14.82688		
6708	26.74	CO	25.2	150		VC	5.385165	1 in 206	
0207	45.7	CO	42.38	300		BR	34.79901	1 in 189	
7501	34.54	CO	24.73	450		VC	4.24564		
5510	29.72	CO	25.08	150		VC	12.36932	1 in 206	
7306	36.52	CO	30.52	375		VC	28.3249	1 in 187	
9308	38.22	CO	31.24	600		VC	7.161773		
0793		CO	0	1850		BR	171.3522		
7307	36.46	CO	30.73	375		VC	9.219544	1 in 49	
5706	21.2	CO	22.28	450		VC	7.615773	1 in 46	
9202	39.78	CO	34.41	300		VC	17.35455	1 in 98	
8206	37.53	CO	33.45	225		VC	21.80329		
7212	38.32	CO	36.28	410		BR	33.24154		
7503		CO	1500			VC	24.20744		
6701	34.81	CO	28.63	375		VC	37.92708		
9191	41.7	CO	37.12	450		VC	21.75031	1 in 40	
9408	40.37	CO	37.37	150		VC	7.01138	1 in 187	
8335	36.91	CO	28.82	1500		BR	25.03875		
8116	37.12	CO	33.33	1330		VC	12.52983		
7503		CO	0	700		BR	6.954919		
9403	40.08	CO	28.5	375		VC	7.28011		
5629		CO	150			VC	14.39183		
6217		CO	150			VC	9.85762		
5308		CO	225			VC	7.145642		
9405	40.4	CO	35.88	375		VC	2.23068		
7314	36.91	CO	32.86	225		VC	7.28011	1 in 79	
9803	34.6	CO	31.44	150		VC	6.324555	1 in 45	
9406	40.87	CO	28.12	1600		BR	18.1454		
6308	35.97	CO							

APPENDIX 5

EXISTING DRAINAGE SURVEY DATA

Table of contents

Project Name: St_Marys_Gate_Manchester	Project number: 19457	Date: 06/06/2019	Contact: Simon Scragg	
---	--------------------------	---------------------	--------------------------	--

Profile Report	1
----------------------	---

Inspection: 1

Project Information	2
---------------------------	---

Legend of Classification	3
--------------------------------	---

Section: 1, UC01 --- UC02	4
---------------------------------	---

Section: 2, UC03 --- UC01	5
---------------------------------	---

Section: 3, UC06 --- UC05	6
---------------------------------	---

Section: 4, UC02 --- UC07	7
---------------------------------	---

Section: 5, UC08 --- UC06	8
---------------------------------	---

Section: 6, UC09 --- UC06	9
---------------------------------	---

Section: 7, UC03 --- UC09	10
---------------------------------	----

Section: 8, UC10 --- UC06	11
---------------------------------	----

Section: 9, UC11 --- UC06	12
---------------------------------	----

Section: 10, UC12 --- UC04	13
----------------------------------	----

Section: 11, UC13 --- UC04	14
----------------------------------	----

Section: 12, UC14 --- UC04	15
----------------------------------	----

Section: 13, UC15 --- UC04	16
----------------------------------	----

Section: 14, UC16 --- UC04	17
----------------------------------	----

Section: 15, UC18 --- UC17	18
----------------------------------	----

Section: 16, UC17 --- UC03	19
----------------------------------	----

Section: 17, UC19 --- UC03	20
----------------------------------	----

/ Main sections

Project name : St_Marys_Gate_Manchester_Survey	Project number : 19457	Contact : Simon Scragg	Date : 06/06/2019
--	----------------------------------	----------------------------------	-----------------------------

Nr.	US MH	DS MH	Date	Road	Tape No.	Material	m	(m)
8	UC10	UC06	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	5.69	5.69
9	UC11	UC06	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	1.89	1.89
10	UC12	UC04	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	3.95	3.95
11	UC13	UC04	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	0.02	0.02
12	UC14	UC04	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	7.02	7.02
13	UC15	UC04	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	5.89	5.89
14	UC16	UC04	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	1.56	1.56
15	UC18	UC17	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	3.62	3.62
16	UC17	UC03	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	0.63	0.63
17	UC19	UC03	06/06/2019	R/O 41/43 DEANS GATE		Vitrified clay	3.24	3.24

Pipe size: CIRCULAR 100 = 33.51 m (33.51 m)

Nr.	US MH	DS MH	Date	Road	Tape No.	Material	m	(m)
1	UC01	UC02	06/06/2019	O/S 43/41 DeansGate		Cast iron	22.74	22.74
2	UC03	UC01	06/06/2019	O/S 43/41 DeansGate		Cast iron	5.88	5.88
3	UC06	UC05	06/06/2019	O/S 43/41 DeansGate		Cast iron	10.78	10.78
4	UC02	UC07	06/06/2019	O/S 45/47 DeansGate		Vitrified clay	11.90	11.90
5	UC08	UC06	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	0.93	0.93
6	UC09	UC06	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	13.00	13.00
7	UC03	UC09	06/06/2019	R/O 41/43 DEANS GATE		Cast iron	8.96	8.96

Pipe size: CIRCULAR 150 = 74.19 m (74.19 m)

All sections = 107.7 m (107.7 m)

Project-information

Project name : St_Marys_Gate_Manchester_Survey	Project Number : 19457	Contact : Simon Scragg	Date : 06/06/2019
---	---------------------------	---------------------------	----------------------

Client:
Contact Name:
Department:
Address:
Town:
Telephone:
Mobile:
E-mail:

CBRE Ltd
Edward Warren
Director
10th Floor | One St. Peters
Square | Manchester | M2 3DE
0161 2335446
07795 121228
ed.warren@cbre.com

Site:
Contact Name:
Department:
Address:
Telephone:
Fax:
Mobile:
E-mail:

St Marys Gate, Manchester
Edward Warren
Director
10th Floor | One St. Peters
Square | Manchester | M2 3DE
0161 2335446
07795 121228
ed.warren@cbre.com

Contractor
Contact Name:
Telephone:
E-mail:

SSL / IWJS
Simon Scragg / Jake Boydell
01625 533444
simon.s@survsys.co.uk

Defect Grade Description

Project Name : St_Marys_Gate_Manchester_Survey	Project number : 19457	Contact : Simon Scragg	Date : 06/06/2019
---	---------------------------	---------------------------	----------------------

1:

Brick: No Structural Defects
 Pipe: No Structural Defects

Acceptable Structural Condition

2:

Brick: Minor cracking, Surface mortar loss, Spalling slight, wear slight
 Pipe: Circumfrential crack, Moderate joint defects, Spalling slight, Wear slight

Minor collapse risk in short term but potential for further deterioration

3:

Brick: Total mortarloss without other defects, single brick displaced, Deformation up to 5%, Spalling medium, Wear medium
 Pipe: Fractures with deformation up tp 5%, Longitudinal cracking or mulitlpe cracking, Minor loss of level, More severe joint

! Collapse unlikely in near future but future deterioration likely !

4:

Brick: Total mortarloss with deformation greater than 10%, Deformation up to 10% and fractured, Displaced/hanging brickwork, Small number of missing bricks
 Pipe: Broken, Deformation up to 10% and broken,, Fractured with deformation 5 - 10%, Multipl

!! Collapse likely in foreseeable future !!

5:

Brick: Already Collapsed, Missing invert, Deformation over 10% and fractured, Displaced/hanging brickwork and deformation over 10%, Extensive missing bricks
 Pipe: Already collapsed, Deformation over 10% and broken, Extensive areas of fabric missin

!!! Collapsed or collapse imminent !!!


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 1	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Manchester	Location details:	U/S MH : UC01
Road : O/S 43/41 DeansGate	Catchment:	U/S Depth :
Location A footway beside a road	Pipe Shape : Circular	D/S MH : UC02
Inspection UC01 (D/S) UC02	Pipe Length	D/S Depth :

Use: Combined	Pipe Width :
Year laid :	Pipe Diameter : 150 mm
Purpose : Sample survey to determine asset condition	Pipe material : Cast iron
Total length : 22.74 m	Lining :

Comment :

1:196	Position	Observation	Grade						
									
	0.00	Start node type, manhole, reference number : UC01	0						
	0.00	Water level, 05% of the vertical dimension	0						
	22.74	Finish node type, manhole reference number: UC02 Remarks: drop shaft into UC02	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 2	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Manchester	Location details:	U/S MH : UC03
Road : O/S 43/41 DeansGate	Catchment:	U/S Depth :
Location A footway beside a road	Pipe Shape : Circular	D/S MH : UC01
Inspection UC01 (U/S) UC03	Pipe Length	D/S Depth :

Use: Combined	Pipe Width :
Year laid :	Pipe Diameter : 150 mm
Purpose : Sample survey to determine asset condition	Pipe material : Cast iron
Total length : 5.88 m	Lining :

Comment :

1:56	Position	Observation	Grade						
		Start node type, manhole, reference number : UC01	0						
		Water level, 05% of the vertical dimension	0						
		Finish node type, manhole reference number: UC03 Remarks: UTR UC05 DUE TO BEING ON TILED FLOORING WITHIN BUILDING	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 3	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Road : Location Inspection	Manchester O/S 43/41 DeansGate A footway beside a road UC05 (U/S) UC06	Location details: Catchment: Pipe Shape : Pipe Length	Circular	U/S MH : U/S Depth : D/S MH : D/S Depth :	UC06 UC05
---	---	--	-----------------	--	--------------------------------

Use: Year laid : Purpose : Total length :	Combined Sample survey to determine asset condition 10.78 m	Pipe Width : Pipe Diameter : Pipe material : Lining :	 150 mm Cast iron
--	--	--	---

Comment :

1:98	Position	Observation	Grade						
	0.00	Start node type, manhole, reference number : UC05	0						
	0.00	Water level, 05% of the vertical dimension	0						
	10.78	Finish node type, manhole reference number: UC06	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 4	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Manchester	Location details:	U/S MH : UC02
Road : O/S 45/47 DeansGate	Catchment:	U/S Depth :
Location A footway beside a road	Pipe Shape : Circular	D/S MH : UC07
Inspection UC02 (D/S) UC07	Pipe Length	D/S Depth :

Use: Combined	Pipe Width :
Year laid :	Pipe Diameter : 150 mm
Purpose : Sample survey to determine asset condition	Pipe material : Vitrified clay
Total length : 11.90 m	Lining :

Comment :

1:98	Position	Observation	Grade						
	0.00	Start node type, manhole, reference number : UC02	0						
	0.00	Water level, 05% of the vertical dimension	0						
	5.03	Line deviates down	0						
	11.90	Finish node type, other special chamber reference number: UC07 Remarks: JUNCTION INTO MAIN SEWRE ON DEANS_GATE	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 5	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Manchester	Location details:	U/S MH : UC08
Road : R/O 41/43 DEANSGATE	Catchment:	U/S Depth :
Location Property with buildings	Pipe Shape : Circular	D/S MH : UC06
Inspection UC06 (U/S) UC08	Pipe Length	D/S Depth :

Use: Combined	Pipe Width :
Year laid :	Pipe Diameter : 150 mm
Purpose : Sample survey to determine asset condition	Pipe material : Cast iron
Total length : 0.93 m	Lining :

Comment :

1:50	Position	Observation	Grade						
		Start node type, manhole, reference number : UC06	0						
		Water level, 05% of the vertical dimension	0						
		Finish node type, other special chamber reference number: UC08 Remarks: SVP	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 6	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Manchester	Location details:	U/S MH : UC09
Road : R/O 41/43 DEANS GATE	Catchment:	U/S Depth :
Location Property with buildings	Pipe Shape : Circular	D/S MH : UC06
Inspection UC06 (U/S) UC09	Pipe Length	D/S Depth :

Use: Combined	Pipe Width :
Year laid :	Pipe Diameter : 150 mm
Purpose : Sample survey to determine asset condition	Pipe material : Cast iron
Total length : 13.00 m	Lining :

Comment :

1:112	Position	Observation	Grade						
	0.00	Start node type, manhole, reference number : UC06	0						
	0.00	Water level, 05% of the vertical dimension	0						
	1.70	Junction, at 1 o'clock, diameter 100mm	0						
	1.70	Material changes, vitrified clay	0						
	2.25	Material changes, cast iron	0						
	9.62	Line deviates right	0						
	12.36	Water level, 15% of the vertical dimension	0						
	13.00	Finish node type, manhole reference number: UC09	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 7	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Road : Location Inspection	Manchester R/O 41/43 DEANSGATE Property with buildings UC09 (U/S) UC03	Location details: Catchment: Pipe Shape : Pipe Length	Circular	U/S MH : U/S Depth : D/S MH : D/S Depth :	UC03 UC09
---	---	--	-----------------	--	--------------------------------

Use: Year laid : Purpose : Total length :	Combined Sample survey to determine asset condition 8.96 m	Pipe Width : Pipe Diameter : Pipe material : Lining :	 150 mm Cast iron
--	---	--	---

Comment :

1:84	Position	Observation	Grade						
	UC09	Start node type, manhole, reference number : UC09	0						
	0.00	Water level, 05% of the vertical dimension	0						
	0.00								
	4.82	Water level, 10% of the vertical dimension	0						
	6.46	Dimension changes, 100mm high	0						
	7.28	Water level, 05% of the vertical dimension	0						
8.96	Finish node type, manhole reference number: UC03	0							
	UC03								
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 8	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Manchester	Location details:	U/S MH : UC10
Road : R/O 41/43 DEANSGATE	Catchment:	U/S Depth :
Location Property with buildings	Pipe Shape : Circular	D/S MH : UC06
Inspection UC06 (U/S) UC10	Pipe Length	D/S Depth :

Use: Combined	Pipe Width :
Year laid :	Pipe Diameter : 100 mm
Purpose : Sample survey to determine asset condition	Pipe material : Cast iron
Total length : 5.69 m	Lining :

Comment :

1:56	Position	Observation	Grade
			
		Start node type, manhole, reference number : UC06	0
		Water level, 05% of the vertical dimension	0
		Finish node type, other special chamber reference number: UC10 Remarks: ACO DRAIN	0


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 9	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Road : Location Inspection	Manchester R/O 41/43 DEANS GATE Property with buildings UC06 (U/S) UC11	Location details: Catchment: Pipe Shape : Pipe Length	Circular	U/S MH : U/S Depth : D/S MH : D/S Depth :	UC11 UC06
---	--	--	-----------------	--	--------------------------------

Use: Year laid : Purpose : Total length :	Combined Sample survey to determine asset condition 1.89 m	Pipe Width : Pipe Diameter : Pipe material : Lining :	 100 mm Cast iron
--	---	--	---

Comment :

1:50	Position	Observation	Grade						
	UC06	Start node type, manhole, reference number : UC06	0						
		Water level, 05% of the vertical dimension	0						
	UC11	Finish node type, other special chamber reference number: UC11 Remarks: ACO DRAIN	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 10	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Manchester	Location details:	U/S MH : UC12
Road : R/O 41/43 DEANSGATE	Catchment:	U/S Depth :
Location Property with buildings	Pipe Shape : Circular	D/S MH : UC04
Inspection UC04 (U/S) UC12	Pipe Length	D/S Depth :

Use: Combined	Pipe Width :
Year laid :	Pipe Diameter : 100 mm
Purpose : Sample survey to determine asset condition	Pipe material : Cast iron
Total length : 3.95 m	Lining :

Comment :

1:50	Position	Observation	Grade						
	0.00	Start node type, manhole, reference number : UC04	0						
	0.00	Water level, 05% of the vertical dimension	0						
	0.77	Line deviates right	0						
	2.61	Material changes, vitrified clay	0						
	2.83	Junction, at 3 o'clock, diameter 100mm Remarks: JUNCTION SERVES RAINWATER GULLY	0						
	3.95	Finish node type, other special chamber reference number: UC12 Remarks: HOS	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 12	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Manchester	Location details:	U/S MH : UC14
Road : R/O 41/43 DEANSGATE	Catchment:	U/S Depth :
Location Property with buildings	Pipe Shape : Circular	D/S MH : UC04
Inspection UC04 (U/S) UC14	Pipe Length	D/S Depth :

Use: Combined	Pipe Width :
Year laid :	Pipe Diameter : 100 mm
Purpose : Sample survey to determine asset condition	Pipe material : Cast iron
Total length : 7.02 m	Lining :

Comment :

1:70	Position	Observation	Grade						
	UC04	Start node type, manhole, reference number : UC04	0						
		Water level, 05% of the vertical dimension	0						
	UC14	Finish node type, other special chamber reference number: UC14 Remarks: LINE NOT IN USE	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 13	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Manchester	Location details:	U/S MH : UC15
Road : R/O 41/43 DEANSGATE	Catchment:	U/S Depth :
Location Property with buildings	Pipe Shape : Circular	D/S MH : UC04
Inspection UC04 (U/S) UC15	Pipe Length	D/S Depth :

Use: Combined	Pipe Width :
Year laid :	Pipe Diameter : 100 mm
Purpose : Sample survey to determine asset condition	Pipe material : Cast iron
Total length : 5.89 m	Lining :

Comment :

1:56	Position	Observation	Grade						
	0.00	Start node type, manhole, reference number : UC04	0						
	0.00	Water level, 05% of the vertical dimension	0						
	1.80	Material changes, vitrified clay	0						
	2.12	Junction, at 12 o'clock, diameter 100mm	0						
	2.36	Junction, at 12 o'clock, diameter 100mm	0						
	4.48	Line deviates up	0						
	5.89	Finish node type, inspection chamber reference number: UC15 Remarks: HOS UTL UC15 DUE TO BEING LOACTED WITH BUILDING	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 14	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Manchester	Location details:	U/S MH : UC16
Road : R/O 41/43 DEANSGATE	Catchment:	U/S Depth :
Location Property with buildings	Pipe Shape : Circular	D/S MH : UC04
Inspection UC04 (U/S) UC16	Pipe Length	D/S Depth :

Use: Combined	Pipe Width :
Year laid :	Pipe Diameter : 100 mm
Purpose : Sample survey to determine asset condition	Pipe material : Cast iron
Total length : 1.56 m	Lining :

Comment :

1:50	Position	Observation	Grade						
		Start node type, manhole, reference number : UC04	0						
		Water level, 05% of the vertical dimension	0						
		Line deviates up	0						
		Survey abandoned Remarks: SA DUE TO LINE UP, LINE LOOKS LIKE IT SERVES SW STACK	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 15	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Road : Location Inspection	Manchester R/O 41/43 DEANSGATE Property with buildings UC17 (U/S) UC18	Location details: Catchment: Pipe Shape : Pipe Length	Circular	U/S MH : U/S Depth : D/S MH : D/S Depth :	UC18 UC17
---	---	--	-----------------	--	--------------------------------

Use: Year laid : Purpose : Total length :	Combined Sample survey to determine asset condition 3.62 m	Pipe Width : Pipe Diameter : Pipe material : Lining :	 100 mm Cast iron
--	---	--	---

Comment :

1:50	Position	Observation	Grade						
	UC17	Start node type, manhole, reference number : UC17	0						
		Water level, 05% of the vertical dimension	0						
	UC18	Finish node type, other special chamber reference number: UC18 Remarks: UC17 IS HOS AND TAKES NOTHING FURTHER U/S FR	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 16	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Manchester	Location details:	U/S MH : UC17
Road : R/O 41/43 DEANSGATE	Catchment:	U/S Depth :
Location Property with buildings	Pipe Shape : Circular	D/S MH : UC03
Inspection UC17 (D/S) UC03	Pipe Length	D/S Depth :

Use: Combined	Pipe Width :
Year laid :	Pipe Diameter : 100 mm
Purpose : Sample survey to determine asset condition	Pipe material : Cast iron
Total length : 0.63 m	Lining :

Comment :

1:50	Position	Observation	Grade						
	UC17	Start node type, manhole, reference number : UC17	0						
		Water level, 05% of the vertical dimension	0						
	UC03	Finish node type, manhole reference number: UC03	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1


Inspection report

Date : 06/06/2019	Job number :	Section Type : unknown	Operator : Aden H	Section number : 17	PLR SUFFIX: X
Weather no rain or snow	Vehicle : FL65 WZD	Camera : PUSH ROD	Preset :	Cleaned : no	Type of Drain : Gravity drain/sewer

Place : Road : Location Inspection	Manchester R/O 41/43 DEANSGATE Property with buildings	Location details: Catchment: Pipe Shape : Pipe Length	Circular	U/S MH : U/S Depth : D/S MH : D/S Depth :	UC19 UC03
---	---	--	-----------------	--	--------------------------------

Use: Year laid : Purpose : Total length :	Combined Sample survey to determine asset condition 3.24 m	Pipe Width : Pipe Diameter : Pipe material : Lining :	 100 mm Vitrified clay
--	---	--	--

Comment :

1:50	Position	Observation	Grade						
	UC19	Start node type, manhole, reference number : UC19	0						
		Water level, 05% of the vertical dimension	0						
	UC03	Finish node type, other special chamber reference number: UC03 Remarks: SVP	0						
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1



SURVEY systems

Project No.

19457

Survey Date.

04/06/2019

Surveyor.

A.HALLIWELL

Asset Survey Card

Asset ID: **SJ83987503** Asset Type: **MH** eg: MH, CP, GY Function: **C** Cover Level:

Location: **St.Mary's Gate junction of Deansgate Footpath**

Town: **MANCHESTER**

COVER DETAILS

☐ Square
 ☒ Rectangle
 ☐ Triangle
 ☐ Dbl Triangle
 ☐ Circular
 ☐ Other Other

☐ Hinged
 ☐ Lockable
 ☐ Grating
 ☒ Cover Duty
 700 x **600** Size (mm)

PIPE DETAILS

Incoming Pipes

Pipe	Depth from Cover (m)	Upstream / Downstream Ref	Shape	Size (mm)		Pipe Mat	Lining Mat	Back Drop Dia (mm)	Invert Level (m)
A	3.34		C	100	x	VC			-3.340
B	13.58		A	900	x	B			-13.580
C					x				0.000
D					x				0.000
E					x				0.000
F					x				0.000
G					x				0.000
X	13.94		C	1500	x	CO			-13.940
Z					x				0.000

MANHOLE CONSTRUCTION DETAILS

Shaft

640 x **640** Size (mm)
 0.35 Depth (m)
 2 No. of Reg Courses
 Soffit

Chamber

3200 x **1800** Size (mm)
 YES Side Entry
 N OX / H2S / METH Toxic atmosphere
 N Evidence of Surge

☐ Pre Cast Concrete
 ☐ Insitu Concrete
 ☒ Brick
 ☐ Bolted segments
 ☐ GRP
 ☐ Reducing Slab

1 Step Irons
 ☒ Ladder
 1 No. of Landings
 200 Depth of Flow (mm)
 0 Depth of Silt (mm)

ADDITIONAL CONSTRUCTION DETAILS

☐ Flap Valve
 ☐ Orifice
 ☐ Sluice Gate
 ☐ Weir
 ☐ Screens
 ☐ Penstock
 ☐ Flume
 ☐ H/Wall

CONDITION INFORMATION (Specify in Remark)

	Cover	Shaft	Irons/Ladder	Chamber	Benching	Channel
OK	☒	☒	☒	☒	☒	☒
Needs Attention	☐	☐	☐	☐	☐	☐
Urgent Attention	☐	☐	☐	☐	☐	☐

Remark

See Overleaf for Key

7503

SURVEY TO SUBROUNDERING PARCELS

INDICATES APPROXIMATE LOCATION OF RAP AND SW BASED ON WEST ARROW DRAINAGE. MAY HAVE BEEN CLOSED OVER TIME. SHOWN FOR ASSISTANCE

12-11 ST MARY'S CHURCH

INDICATES APPROXIMATE LOCATION OF WATER UTILITIES (SEWER BRANCH) BUILDING REFER TO LOCAL GRIDS TO IDENTIFY TRACES AND SUBMITTED INCLUDING ALL RECORDING PAPERS TO ALLOW POTENTIAL ABANDONMENT

UTILITY SCAN AND DRAINAGE SURVEY TO REAR OF PROPERTY AND ALLEYWAY

TOPOGRAPIHICAL SURVEY TO BE EXTENDED TO INCLUDE NEAR ACCESS ALLEYWAY

ALL DRAINAGE ACCESS POINTS TO REAR OF BUILDING TO BE SURVEYED TO VERIFY IF DRAINAGE FROM ROAD/CUT PROPERTIES CONNECTS AND THE ALL DRAINAGE SYSTEM FLOWS BENEATH THE SITE

114 ACRES (APPROX)

BARTON BRIDGE

AS MUCH OF THE INTERNAL DRAINAGE IS TO BE TRACED WHERE POSSIBLE FROM ACCESSIBLE INTERNAL MANHOLES AND MANHOLE EXITS EXTENDING 200M

ISSUED: LOCATION OF EXISTING EXCHANGE POINT TO DEEP SEWER IN EXISTING INVERT LEVELS AND PIPES WITHIN MANHOLE TO BE DETERMINED AT ALL OF SURVEY

ISSUED: IN HIGHWAY TO BE SURVEYED TO CONFIRM COVER AND INVERT LEVELS

The diagram shows a cross-section of a ship's hull with two main internal compartments: "LADDERS" at the top and "LANDING" at the bottom. The "LADDERS" compartment contains a large oval structure with an arrow labeled "A" pointing left from its right edge. The "LANDING" compartment is empty. External forces are represented by arrows: "X" is a large arrow pointing left from the left side of the hull, and "B" is a large arrow pointing right from the right side of the hull.

STATUS	PU : Public	PR : Private	WC : Culverted Watercourse	} Applies to main outlet
	24 : Section 24	HD : Highway Drain		
FUNCTION	F : Foul	C : Combined	S : Surface Water	} Applies to main outlet
MANHOLE TYPE	IF : Infall	MH : Manhole	CP : Catchpit	
	LH : Lamphole	RE : Rodding Eye	SO : Storm Overflow	
	GU : Gully	OF : Outfall	SA : Soakaway	
COVER DUTY	L : Light Duty	M : Medium Duty	H : Heavy Duty	
SHAPE	C : Circular	E : Egg	R : Rectangular	
	S : Square	T : Trapezoidal	A : Arched	
	B : Barrel	H : Horseshoe (Inverted U)	U : U-shaped with flat top	
	X : Other (state in words)			
PIPE (OR LINING)	AK : Alkathene	AC : Asbestos Cement	BR : Brick	
MATERIAL	CI : Cast Iron	SI : Spun (Grey) Iron	CO : Concrete	
	CSB : Concrete Segments (Bolted)	CSU : Concrete Segments (Unbolted)	CC : Concrete Box Culvert	
	DI : Ductile Iron	GRC : Glass Reinforced Concrete	GRP : Glass Reinforced Plastic	
	PSC : Plastic/Steel Composite	PVC : Polyvinyl Chloride	PE : Polyethylene	
	RPM : Reinforced Plastic Matrix	ST : Steel	VC : Vitrified Clay	
	PP : Polypropylene	PF : Pitch Fibre	MAC : Masonry, Coursed	
	MAR : Masonry, Random Courses	XXX : Other (State in remarks)		
LINING	BL : Bitumen	RL : Resin	IS : Insituform	
	CL : Cement	PI : Plastic		



SURVEY
systems

Project No.

19457

Survey Date.

04/06/2019

Surveyor.

A.HALLIWELL



Asset Survey Card

Asset ID: Asset Type: eg: MH, CP, GY Function: Cover Level:

Location:

Town:

COVER DETAILS

☐ Square ☒ Rectangle ☐ Triangle ☐ Dbl Triangle ☐ Circular ☐ Other Other

☐ Hinged ☐ Lockable ☐ Grating Cover Duty x Size (mm)

PIPE DETAILS

Incoming Pipes

Pipe	Depth from Cover (m)	Upstream / Downstream Ref	Shape	Size (mm)		Pipe Mat	Lining Mat	Back Drop Dia (mm)	Invert Level (m)
A	2.66		C	150	x	CI			-2.660
B					x				0.000
C					x				0.000
D					x				0.000
E					x				0.000
F					x				0.000
G					x				0.000
X	2.7		C	150	x	CI			-2.700
Z					x				0.000

MANHOLE CONSTRUCTION DETAILS

Shaft

x Size (mm) Depth (m) No. of Reg Courses Soffit

Chamber

x Size (mm) Side Entry OX / H2S / METH Toxic atmosphere Evidence of Surge

☐ Pre Cast Concrete ☐ Insitu Concrete ☒ Brick ☐ Bolted segments ☐ GRP ☐ Reducing Slab

Step Irons ☐ Ladder No. of Landings Depth of Flow (mm) Depth of Silt (mm)

ADDITIONAL CONSTRUCTION DETAILS

☐ Flap Valve ☐ Orifice ☐ Sluice Gate ☐ Weir ☐ Screens ☐ Penstock ☐ Flume ☐ H/Wall

CONDITION INFORMATION (Specify in Remark)

	Cover	Shaft	Irons/Ladder	Chamber	Benching	Channel
OK	☒	☒	☒	☒	☐	☒
Needs Attention	☐	☐	☐	☐	☒	☐
Urgent Attention	☐	☐	☐	☐	☐	☐

Remark

RECOMMEND TO REMOVE DEBRIS FROM BENCHING

See Overleaf for Key

[illegible]

STATUS	PU : Public	PR : Private	WC : Culverted Watercourse	} Applies to main outlet
	24 : Section 24	HD : Highway Drain		
FUNCTION	F : Foul	C : Combined	S : Surface Water	} Applies to main outlet
MANHOLE TYPE	IF : Infall LH : Lamphole GU : Gully	MH : Manhole RE : Rodding Eye OF : Outfall	CP : Catchpit SO : Storm Overflow SA : Soakaway	
COVER DUTY	L : Light Duty	M : Medium Duty	H : Heavy Duty	
SHAPE	C : Circular S : Square B : Barrel X : Other (state in words)	E : Egg T : Trapezoidal H : Horseshoe (Inverted U)	R : Rectangular A : Arched U : U-shaped with flat top	
PIPE (OR LINING) MATERIAL	AK : Alkathene CI : Cast Iron CSB : Concrete Segments (Bolted) DI : Ductile Iron PSC : Plastic/Steel Composite RPM : Reinforced Plastic Matrix PP : Polypropylene MAR : Masonry, Randon Courses	AC : Asbestos Cement SI : Spun (Grey) Iron CSU : Concrete Segments (Unbolted) GRC : Glass Reinforced Concrete PVC : Polyvinyl Chloride ST : Steel PF : Pitch Fibre XXX : Other (State in remarks)	BR : Brick CO : Concrete CC : Concrete Box Culvert GRP : Glass Reinforced Plastic PE : Polyethylene VC : Vitrified Clay MAC : Masonry, Coursed	
LINING	BL : Bitumen CL : Cement	RL : Resin PI : Plastic	IS : Insituform	



SURVEY
systems

Project No.

19457

Survey Date.

04/06/2019

Surveyor.

A.HALLIWELL

Asset Survey Card

Asset ID: Asset Type: eg: MH, CP, GY Function: Cover Level:

Location:

Town:

COVER DETAILS

☐ Square ☒ Rectangle ☐ Triangle ☐ Dbl Triangle ☐ Circular ☐ Other Other

☐ Hinged ☐ Lockable ☐ Grating Cover Duty x Size (mm)

PIPE DETAILS

Incoming Pipes

Pipe	Depth from Cover (m)	Upstream / Downstream Ref	Shape	Size (mm)		Pipe Mat	Lining Mat	Back Drop Dia (mm)	Invert Level (m)
A	3.45		C	150	x	CI			-3.450
B					x				0.000
C					x				0.000
D					x				0.000
E					x				0.000
F					x				0.000
G					x				0.000
X	9.41		C	150	x	VC			-9.410
Z					x				0.000

MANHOLE CONSTRUCTION DETAILS

Shaft

x Size (mm) Depth (m) No. of Reg Courses Soffit

Chamber

x Size (mm) Side Entry OX / H2S / METH Toxic atmosphere Evidence of Surge

☐ Pre Cast Concrete ☐ Insitu Concrete ☐ Brick ☒ Bolted segments ☐ GRP ☐ Reducing Slab

Step Irons ☐ Ladder No. of Landings Depth of Flow (mm) Depth of Silt (mm)

ADDITIONAL CONSTRUCTION DETAILS

☐ Flap Valve ☐ Orifice ☐ Sluice Gate ☐ Weir ☐ Screens ☐ Penstock ☐ Flume ☐ H/Wall

CONDITION INFORMATION (Specify in Remark)


	Cover	Shaft	Irons/Ladder	Chamber	Benching	Channel
OK	☒	☒	☒	☐	☒	☒
Needs Attention	☐	☐	☐	☒	☐	☐
Urgent Attention	☐	☐	☐	☐	☐	☐

Remark


RECOMMEND TO REMOVE LADDERS FROM WITHIN MH CHAMBER

See Overleaf for Key

LOCATION SKETCH



PLAN OF MANHOLE



LOCATION PHOTO



INTERNAL PHOTO



STATUS	PU : Public	PR : Private	WC : Culverted Watercourse	} Applies to main outlet
	24 : Section 24	HD : Highway Drain		
FUNCTION	F : Foul	C : Combined	S : Surface Water	} Applies to main outlet
MANHOLE TYPE	IF : Infall	MH : Manhole	CP : Catchpit	
	LH : Lamphole	RE : Rodding Eye	SO : Storm Overflow	
	GU : Gully	OF : Outfall	SA : Soakaway	
COVER DUTY	L : Light Duty	M : Medium Duty	H : Heavy Duty	
SHAPE	C : Circular	E : Egg	R : Rectangular	
	S : Square	T : Trapezoidal	A : Arched	
	B : Barrel	H : Horseshoe (Inverted U)	U : U-shaped with flat top	
	X : Other (state in words)			
PIPE (OR LINING) MATERIAL	AK : Alkathene	AC : Asbestos Cement	BR : Brick	
	CI : Cast Iron	SI : Spun (Grey) Iron	CO : Concrete	
	CSB : Concrete Segments (Bolted)	CSU : Concrete Segments (Unbolted)	CC : Concrete Box Culvert	
	DI : Ductile Iron	GRC : Glass Reinforced Concrete	GRP : Glass Reinforced Plastic	
	PSC : Plastic/Steel Composite	PVC : Polyvinyl Chloride	PE : Polyethylene	
	RPM : Reinforced Plastic Matrix	ST : Steel	VC : Vitrified Clay	
	PP : Polypropylene	PF : Pitch Fibre	MAC : Masonry, Coursed	
	MAR : Masonry, Random Courses	XXX : Other (State in remarks)		
LINING	BL : Bitumen	RL : Resin	IS : Insituform	
	CL : Cement	PI : Plastic		



SURVEY
systems

Project No.

19457

Survey Date.

04/06/2019

Surveyor.

A.HALLIWELL

Asset Survey Card

Asset ID: Asset Type: eg: MH, CP, GY Function: Cover Level:

Location:

Town:

COVER DETAILS

☒ Square ☐ Rectangle ☐ Triangle ☐ Dbl Triangle ☐ Circular ☐ Other Other

☐ Hinged ☐ Lockable ☐ Grating ☒ H Cover Duty x Size (mm)

PIPE DETAILS

Incoming Pipes

Pipe	Depth from Cover (m)	Upstream / Downstream Ref	Shape	Size (mm)		Pipe Mat	Lining Mat	Back Drop Dia (mm)	Invert Level (m)
A	0.62		C	100	x	CI			-0.620
B	0.55		C	100	x	VC			-0.550
C					x				0.000
D					x				0.000
E					x				0.000
F					x				0.000

Outgoing Pipes

X	0.66		C	100	x	CI			-0.660
Z					x				0.000

MANHOLE CONSTRUCTION DETAILS

Shaft

x Size (mm) Depth (m) No. of Reg Courses Soffit

Chamber

x Size (mm) Side Entry ☒ OX / H2S / METH Toxic atmosphere ☒ Evidence of Surcharge

☐ Pre Cast Concrete ☐ Insitu Concrete ☒ Brick ☐ GRP ☐ Reducing Slab

Step Irons ☐ Ladder No. of Landings Depth of Flow (mm) Depth of Silt (mm)

ADDITIONAL CONSTRUCTION DETAILS

☐ Flap Valve ☐ Orifice ☐ Sluice Gate ☐ Weir ☐ Screens ☐ Penstock ☐ Flume ☐ H/Wall


CONDITION INFORMATION (Specify in Remark)

	Cover	Shaft	Irons/Ladder	Chamber	Benching	Channel
OK	☒	☐	☐	☒	☒	☒
Needs Attention	☐	☐	☐	☐	☐	☐
Urgent Attention	☐	☐	☐	☐	☐	☐


Remark

See Overleaf for Key

LOCATION SKETCH



PLAN OF MANHOLE



LOCATION PHOTO



INTERNAL PHOTO



STATUS	PU : Public	PR : Private	WC : Culverted Watercourse	} Applies to main outlet
	24 : Section 24	HD : Highway Drain		
FUNCTION	F : Foul	C : Combined	S : Surface Water	} Applies to main outlet
MANHOLE TYPE	IF : Infall	MH : Manhole	CP : Catchpit	
	LH : Lamphole	RE : Rodding Eye	SO : Storm Overflow	
	GU : Gully	OF : Outfall	SA : Soakaway	
COVER DUTY	L : Light Duty	M : Medium Duty	H : Heavy Duty	
SHAPE	C : Circular	E : Egg	R : Rectangular	
	S : Square	T : Trapezoidal	A : Arched	
	B : Barrel	H : Horseshoe (Inverted U)	U : U-shaped with flat top	
	X : Other (state in words)			
PIPE (OR LINING) MATERIAL	AK : Alkathene	AC : Asbestos Cement	BR : Brick	
	CI : Cast Iron	SI : Spun (Grey) Iron	CO : Concrete	
	CSB : Concrete Segments (Bolted)	CSU : Concrete Segments (Unbolted)	CC : Concrete Box Culvert	
	DI : Ductile Iron	GRC : Glass Reinforced Concrete	GRP : Glass Reinforced Plastic	
	PSC : Plastic/Steel Composite	PVC : Polyvinyl Chloride	PE : Polyethylene	
	RPM : Reinforced Plastic Matrix	ST : Steel	VC : Vitrified Clay	
	PP : Polypropylene	PF : Pitch Fibre	MAC : Masonry, Coursed	
	MAR : Masonry, Random Courses	XXX : Other (State in remarks)		
LINING	BL : Bitumen	RL : Resin	IS : Insituform	
	CL : Cement	PI : Plastic		



SURVEY
systems

Project No.

19457

Survey Date.

05/06/2019

Surveyor.

A.HALLIWELL

Asset Survey Card

Asset ID: Asset Type: eg: MH, CP, GY Function: Cover Level:

Location:

Town:

COVER DETAILS

☐ Square ☒ Rectangle ☐ Triangle ☐ Dbl Triangle ☐ Circular ☐ Other Other

☐ Hinged ☐ Lockable ☐ Grating ☐ H Cover Duty x Size (mm)

PIPE DETAILS

Incoming Pipes

Pipe	Depth from Cover (m)	Upstream / Downstream Ref	Shape	Size (mm)		Pipe Mat	Lining Mat	Back Drop Dia (mm)	Invert Level (m)
A	0.92		C	100	x	CI			-0.920
B	0.92		C	100	x	CI			-0.920
C	0.92		C	100	x	CI			-0.920
D	0.93		C	100	x	CI			-0.930
E	0.91		C	100	x	CI			-0.910
F	0.91		C	100	x	CI			-0.910
G	0.91		C	100	x	CI			-0.910
X	0.97		C	100	x	CI			-0.970
Z					x				0.000

MANHOLE CONSTRUCTION DETAILS

Shaft

x Size (mm) Depth (m) No. of Reg Courses Soffit

Chamber

x Size (mm) Side Entry OX / H2S / METH Toxic atmosphere Evidence of Surge

☐ Pre Cast Concrete ☐ Insitu Concrete ☐ Brick ☐ GRP ☐ Reducing Slab

Step Irons ☐ Ladder No. of Landings Depth of Flow (mm) Depth of Silt (mm)

ADDITIONAL CONSTRUCTION DETAILS

☐ Flap Valve ☐ Orifice ☐ Sluice Gate ☐ Weir ☐ Screens ☐ Penstock ☐ Flume ☐ H/Wall

CONDITION INFORMATION (Specify in Remark)

	Cover	Shaft	Irons/Ladder	Chamber	Benching	Channel
OK	☒	☒	☐	☒	☒	☒
Needs Attention	☐	☐	☐	☐	☐	☐
Urgent Attention	☐	☐	☐	☐	☐	☐


Remark

See Overleaf for Key

LOCATION SKETCH



PLAN OF MANHOLE



LOCATION PHOTO



INTERNAL PHOTO



STATUS	PU : Public	PR : Private	WC : Culverted Watercourse	} Applies to main outlet
	24 : Section 24	HD : Highway Drain		
FUNCTION	F : Foul	C : Combined	S : Surface Water	} Applies to main outlet
MANHOLE TYPE	IF : Infall	MH : Manhole	CP : Catchpit	
	LH : Lamphole	RE : Rodding Eye	SO : Storm Overflow	
	GU : Gully	OF : Outfall	SA : Soakaway	
COVER DUTY	L : Light Duty	M : Medium Duty	H : Heavy Duty	
SHAPE	C : Circular	E : Egg	R : Rectangular	
	S : Square	T : Trapezoidal	A : Arched	
	B : Barrel	H : Horseshoe (Inverted U)	U : U-shaped with flat top	
	X : Other (state in words)			
PIPE (OR LINING) MATERIAL	AK : Alkathene	AC : Asbestos Cement	BR : Brick	
	CI : Cast Iron	SI : Spun (Grey) Iron	CO : Concrete	
	CSB : Concrete Segments (Bolted)	CSU : Concrete Segments (Unbolted)	CC : Concrete Box Culvert	
	DI : Ductile Iron	GRC : Glass Reinforced Concrete	GRP : Glass Reinforced Plastic	
	PSC : Plastic/Steel Composite	PVC : Polyvinyl Chloride	PE : Polyethylene	
	RPM : Reinforced Plastic Matrix	ST : Steel	VC : Vitrified Clay	
	PP : Polypropylene	PF : Pitch Fibre	MAC : Masonry, Coursed	
	MAR : Masonry, Random Courses	XXX : Other (State in remarks)		
LINING	BL : Bitumen	RL : Resin	IS : Insituform	
	CL : Cement	PI : Plastic		



Project No.

Survey Date.

Surveyor.

Asset Survey Card

Asset ID: Asset Type: eg: MH, CP, GY Function: Cover Level:

Location:

Town:

COVER DETAILS

☐ Square ☒ Rectangle ☐ Triangle ☐ Dbl Triangle ☐ Circular ☐ Other Other

☐ Hinged ☐ Lockable ☐ Grating ☒ Cover Duty x Size (mm)

PIPE DETAILS

Incoming Pipes

Pipe	Depth from Cover (m)	Upstream / Downstream Ref	Shape	Size (mm)		Pipe Mat	Lining Mat	Back Drop Dia (mm)	Invert Level (m)
A	2.23		C	100	x	CI			-2.230
B	2.23		C	100	x	CI			-2.230
C	2.21		C	150	x	CI			-2.210
D	1.19		C	150	x	CI			-1.190
E	0.5		C	100	x	CI			-0.500
F	0.5		C	100	x	CI			-0.500
G					x				0.000
X	2.24		C	150	x	CI			-2.240
Z					x				0.000

MANHOLE CONSTRUCTION DETAILS

Shaft

x Size (mm) Depth (m) No. of Reg Courses Soffit

Chamber

x Size (mm) Side Entry ☒ OX / H2S / METH Toxic atmosphere ☒ Evidence of Surge

☐ Pre Cast Concrete ☐ Insitu Concrete ☒ Brick ☐ GRP ☐ Reducing Slab

Step Irons ☐ Ladder No. of Landings Depth of Flow (mm) Depth of Silt (mm)

ADDITIONAL CONSTRUCTION DETAILS

☐ Flap Valve ☐ Orifice ☐ Sluice Gate ☐ Weir ☐ Screens ☐ Penstock ☐ Flume ☐ H/Wall


CONDITION INFORMATION (Specify in Remark)

	Cover	Shaft	Irons/Ladder	Chamber	Benching	Channel
OK	☒	☐	☒	☒	☒	☒
Needs Attention	☐	☐	☐	☐	☐	☐
Urgent Attention	☐	☐	☐	☐	☐	☐


Remark

See Overleaf for Key

LOCATION SKETCH



PLAN OF MANHOLE



LOCATION PHOTO



INTERNAL PHOTO



STATUS	PU : Public	PR : Private	WC : Culverted Watercourse	} Applies to main outlet
	24 : Section 24	HD : Highway Drain		
FUNCTION	F : Foul	C : Combined	S : Surface Water	} Applies to main outlet
MANHOLE TYPE	IF : Infall	MH : Manhole	CP : Catchpit	
	LH : Lamphole	RE : Rodding Eye	SO : Storm Overflow	
	GU : Gully	OF : Outfall	SA : Soakaway	
COVER DUTY	L : Light Duty	M : Medium Duty	H : Heavy Duty	
SHAPE	C : Circular	E : Egg	R : Rectangular	
	S : Square	T : Trapezoidal	A : Arched	
	B : Barrel	H : Horseshoe (Inverted U)	U : U-shaped with flat top	
	X : Other (state in words)			
PIPE (OR LINING) MATERIAL	AK : Alkathene	AC : Asbestos Cement	BR : Brick	
	CI : Cast Iron	SI : Spun (Grey) Iron	CO : Concrete	
	CSB : Concrete Segments (Bolted)	CSU : Concrete Segments (Unbolted)	CC : Concrete Box Culvert	
	DI : Ductile Iron	GRC : Glass Reinforced Concrete	GRP : Glass Reinforced Plastic	
	PSC : Plastic/Steel Composite	PVC : Polyvinyl Chloride	PE : Polyethylene	
	RPM : Reinforced Plastic Matrix	ST : Steel	VC : Vitrified Clay	
	PP : Polypropylene	PF : Pitch Fibre	MAC : Masonry, Coursed	
	MAR : Masonry, Random Courses	XXX : Other (State in remarks)		
LINING	BL : Bitumen	RL : Resin	IS : Insituform	
	CL : Cement	PI : Plastic		



SURVEY systems



Project No.

19457

Survey Date.

04/06/2019

Surveyor.

A.HALLIWELL

Asset Survey Card

Asset ID: Asset Type: eg: MH, CP, GY Function: Cover Level:

Location:

Town:

COVER DETAILS

☒ Square
 ☐ Rectangle
 ☐ Triangle
 ☐ Dbl Triangle
 ☐ Circular
 ☐ Other Other

☐ Hinged
 ☐ Lockable
 ☐ Grating
 ☒ H Cover Duty
 x Size (mm)

PIPE DETAILS

Incoming Pipes

Pipe	Depth from Cover (m)	Upstream / Downstream Ref	Shape	Size (mm)		Pipe Mat	Lining Mat	Back Drop Dia (mm)	Invert Level (m)
				Height	Width				
A	0.61		C	100	x	CI			-0.610
B	0.61		C	100	x	CI			-0.610
C					x				0.000
D					x				0.000
E					x				0.000
F					x				0.000

Outgoing Pipes

X	0.64		C	100	x	CI			-0.640
Z					x				0.000

MANHOLE CONSTRUCTION DETAILS

Shaft

x Size (mm) Depth (m) No. of Reg Courses Soffit

Chamber

x Size (mm) Side Entry ☒ OX / H2S / METH Toxic atmosphere ☒ Evidence of Surcharge

☐ Pre Cast Concrete
 ☐ Insitu Concrete
 ☒ Brick
 ☐ GRP
 ☐ Reducing Slab

Step Irons
 Ladder
 No. of Landings
 Depth of Flow (mm)
 Depth of Silt (mm)

ADDITIONAL CONSTRUCTION DETAILS

☐ Flap Valve
 ☐ Orifice
 ☐ Sluice Gate
 ☐ Weir
 ☐ Screens
 ☐ Penstock
 ☐ Flume
 ☐ H/Wall

CONDITION INFORMATION (Specify in Remark)

	Cover	Shaft	Irons/Ladder	Chamber	Benching	Channel
OK	☒	☐	☐	☒	☒	☒
Needs Attention	☐	☐	☐	☐	☐	☐
Urgent Attention	☐	☐	☐	☐	☐	☐


Remark

See Overleaf for Key

LOCATION SKETCH



PLAN OF MANHOLE



LOCATION PHOTO



INTERNAL PHOTO



STATUS	PU : Public	PR : Private	WC : Culverted Watercourse	} Applies to main outlet
	24 : Section 24	HD : Highway Drain		
FUNCTION	F : Foul	C : Combined	S : Surface Water	} Applies to main outlet
MANHOLE TYPE	IF : Infall	MH : Manhole	CP : Catchpit	
	LH : Lamphole	RE : Rodding Eye	SO : Storm Overflow	
	GU : Gully	OF : Outfall	SA : Soakaway	
COVER DUTY	L : Light Duty	M : Medium Duty	H : Heavy Duty	
SHAPE	C : Circular	E : Egg	R : Rectangular	
	S : Square	T : Trapezoidal	A : Arched	
	B : Barrel	H : Horseshoe (Inverted U)	U : U-shaped with flat top	
	X : Other (state in words)			
PIPE (OR LINING) MATERIAL	AK : Alkathene	AC : Asbestos Cement	BR : Brick	
	CI : Cast Iron	SI : Spun (Grey) Iron	CO : Concrete	
	CSB : Concrete Segments (Bolted)	CSU : Concrete Segments (Unbolted)	CC : Concrete Box Culvert	
	DI : Ductile Iron	GRC : Glass Reinforced Concrete	GRP : Glass Reinforced Plastic	
	PSC : Plastic/Steel Composite	PVC : Polyvinyl Chloride	PE : Polyethylene	
	RPM : Reinforced Plastic Matrix	ST : Steel	VC : Vitrified Clay	
	PP : Polypropylene	PF : Pitch Fibre	MAC : Masonry, Coursed	
	MAR : Masonry, Random Courses	XXX : Other (State in remarks)		
LINING	BL : Bitumen	RL : Resin	IS : Insituform	
	CL : Cement	PI : Plastic		