

CONSTRUCTION

PRETTYLITTLETHING

Note:-

SpeedDeck Metal Standing Seam Roof Sheet. Finish to be colour Dusty Grey [RAL 7037]

Breather Membrane
1no layer Celotex XB4000 150mm thick to give Uvalue 0.15w/km2

VCL
35mm Profiled steel structural decking to S Eng's design

18mm ply packers under rooflight

27mm Ply substrate

Galvanised steel Purlins size and setting out to S Eng's design [TBC]

Plasterboard lining.

Portal rafter to S Eng's design

Blocking pieces.

18mm ply jamb lining.

30mm ply packerprovides a support for the shaped flashing piece.

Standing seam junction flashing to contractors specification.

Shaped flashing piece to contractor's specification.

Neo®-s rooflight. This is the only item supplied by the rooflight manufacturer. The rooflight is to include the Thermoliner, fixing coach-screws & rooflight internal linings.

Neo-s rooflight frame finish to be Umbra Grey [RAL 7022].

Silicone beading.

12mm ply packer

Shaped jamb flashing piece caps the 30mm ply packers fitted along the jambs of the rooflight.

18mm ply jamb lining.


Quilted Insulation

Blocking pieces.

27mm Ply substrate

Typical Roof Light Detail

Scale 1:5



Scale Bar 1:10 @ A1

C	Finish annotation added in conjunction with pre-start planning conditions.	CM	TR	07.07.21
B	Purlin setting out dimension added.	CM	TR	25.06.21
A	Fixing rail setting out dimension amended.	CM	TR	25.06.21
Rev	Description	by	Chk	Date

Project: **PLT Wellington Mill** Pollard Street East, Ancoats, Manchester, M40 7FS

Title: **Typical Roof Light detail**

Client: **Pretty Little Thing**

Drawn By: **CM** Checked By: **TR** on **18/05/2020**

Original Size: **A1** Project Number: **22009**

Drawing Number: **B1-ZZ-DR-A-6006** REV **C**

