

Replacement Curtain Wall Schedule	
Curtain Wall Count	Area
1525	4255.57 m²

Total elevational area of existing curtain walling removed and replaced with like-for-like curtain walling system

Demolished Curtain Wall Schedule	
Curtain Wall Count	Area
85	311.69 m²

Total elevational area of existing curtain walling removed. Not replaced with like-for-like system.

Total Demolished Doors Schedule	
Level	Count
Level 0 - Basement (FL39.28)	16
Level 1 - Lower Ground Floor (FL42.07)	51
Level 2 - Ground Floor (FL45.08)	53
Level 3 - First Floor (FL48.97)	52
Level 4 - Second Floor (FL52.16)	57
Level 5 - Third Floor (FL55.36)	23
Level 6 - Fourth Floor (FL58.55)	24
Level 7 - Fifth Floor (FL61.76)	26
Level 8 - Sixth Floor (FL64.95)	10
Level 9 - Seventh Floor (FL68.16)	11
Level 10 - Eighth Floor (FL71.34)	13
Level 11 - Ninth Floor (FL74.54)	28
Level 12 - Tenth Floor (FL77.72)	10
Level 13 - Eleventh Floor (FL80.94)	3
Grand total	377

Total number of existing doors to be removed

Total Demolished Walls Schedule		
Count	Volume	Area

Envelope		
9	17.59 m³	55.98 m²
Interior		
993	365.21 m³	3103.76 m²
Grand total: 1002	382.80 m³	3159.74 m²

Total elevational area / volume of existing envelope walls and Interior partitions removed.

Slab Demolition Areas

Area Location	Area (m)	Area (ft)
Basement	3.5 m²	37.67 ft²
Lower Ground Floor	26.32 m²	283.31 ft²
Ground Floor	68.79 m²	740.45 ft²
First Floor	5.29 m²	56.94 ft²
Second Floor	8.89 m²	95.69 ft²
Third Floor	8.89 m²	95.69 ft²
Fourth Floor	9.00 m²	96.88 ft²
Fifth Floor	14.89 m²	160.27 ft²
Sixth Floor	3.10 m²	33.37 ft²
Seventh Floor	3.44 m²	37.03 ft²
Eighth Floor	3.44 m²	37.03 ft²
Ninth Floor	3.44 m²	37.03 ft²
Tenth Floor	3.44 m²	37.03 ft²
Total Demolished Slab Area	162.43 m²	1748.39 ft²

Total area of existing slab to be demolished to allow for new / extended risers, stairs, platform lifts and voids to be created.

NOTES

- Please note that there are areas with limited access. Some areas may differ from the survey information. Structural Slab not surveyed, dimensions to be checked on site prior to construction. Proposals subject to detailed site investigation and opening up works.
- All dimensions to be checked on site and any discrepancies to be highlighted prior to construction.
- Pall Mall Court is Grade II Listed. If in doubt about any element of the works, please consult the Architect before proceeding. Any proposed works that deviate from this drawing are to be reviewed by the Architect prior to carrying out these works.
- Special care to be taken when working adjacent to heritage features such as mosaic tiles or brick floors to stair cores, so as not to disturb or damage these features. Ensure adjacent elements are not damaged.

REV.	DATE	AMENDMENT
P01	06/05/22	Issue for Planning and Listed Building Consent

KEYPLAN

CLIENT
Bruntwood
Works

bruntwood
Works

ID:SR
SHEPPARD ROBSON

27th Floor City Tower Piccadilly Plaza Manchester M1 4BT
T: +44 (0)161 233 8900 E: enquiries@sheppardrobson.com

PROJECT
Pall Mall Court

SCALE@A3	DATE 06/05/22	ORIGINATOR SD	CHECKED ASM	AUTHORISED TOB
----------	------------------	------------------	----------------	-------------------

Planning
Demolition Schedules

STATUS S2	PURPOSE FOR ISSUE Planning	SR NO. 6911
DRAWING NO. 6911 - SRA - ZZ - XX- SH - A - 00003	REV. P01	