

Drainage for customer sink to be connected into existing foul sewer by appointed contractor using a pumped system. All associated ground works and reinstatement of existing floor slabs to be confirmed on site by main contractor. Any penetrations, scabbling or demolition of foundation/slabs to be confirmed with contractor's structural engineer prior to works commencing. All existing membranes must be repaired and replaced if damaged.

DRAWN USING 2.3.2 April 2022 ARCHITECTURAL LIDL DRS
SPECIFICATION AND JAN 2022 SPECIFICATION

