


DO NOT SCALE FROM THIS DRAWING
The contractor shall check and verify all dimensions on site and report any discrepancies in writing to Sheppard Robson before proceeding work.

FOR ELECTRONIC DATA ISSUE
Electronic Data / drawings are issued as "read only" and should not be interrogated for measurement. All dimensions and levels should read, only from those values stated in text on the drawing.



NOTES:

- Refer to 222XX series for Internal Wall Scoping
- Ceiling heights subject to further co-ordination with services engineer.
- Allow for patrestressing above curtains & blinds where required.
- All dimensions to be checked on site and any discrepancies to be highlighted prior to construction
- Acoustic requirements subject to further co-ordination with acoustic consultant.

CEILING CODES:

- CL01-20 Plasterboard
- CL21-30 Suspended/Tile
- CL41-50 Acoustic
- CL51-60 Joinery/Specialist
- CL61-70 Other
- CL71-80 Not Ceilings
- CL81-90 Basebuild/Existing

EV.	DATE	AMENDMENT
01	18.02.2022	Stage 2 - First Issue for stage approval
02	05.04.2022	Draft issue for planning and listed building consent
03	12.04.2022	Draft issue for planning and listed building consent
04	26.04.2022	Stage 3 issue
05	29.04.2022	Issue for Planning and Listed Building Consent


NOTES

- Please note that there are areas with limited access. Some areas may differ from the survey information.
- All dimensions to be checked on site and any discrepancies to be highlighted prior to construction.

- If in doubt about any element of the works, please consult the Architect before proceeding. Any proposed works that deviate from this drawing are to be reviewed by the Architect prior to carrying out these works.

- Special care to be taken when working adjacent to heritage features such as mosaic tiles or brick floors to stair cores, so as not to disturb or damage these features. Ensure adjacent elements are not damaged.

KEYPLAN



CLIENT

Bruntwood Works

bruntwood
Works

ID:SR
SHEPPARD ROBSON

27th Floor City Tower Piccadilly Plaza Manchester M1 4BT
T: +44 (0)161 233 8900 E: enquiries@sheppardrobson.com

PROJECT
Pall Mall Court

SCALE@A0	DATE	ORIGINATOR	CHECKED	AUTHORISE
1 : 100	29.04.2022	ZJW	EG	ML


Ceilings

- Level 00 Plan
- Scoping

RIBA Stage 3

STATUS	PURPOSE FOR ISSUE	SR NO.
S2	Planning	6911

DRAWING NO. 6911 - IDSR-XX-00-DR-I-35200 REV. P05



35 Series Ceilings

Plasterboard system(s)

CL01 K40/XXX
Plasterboard

CL02 K40/XXX
Moisture Resistant Plasterboard

Acoustic system(s)

The diagram shows three acoustic system options connected to a central 'Acoustic system(s)' label. Each option includes a color swatch, a model name, a K40/XXX label, and a description.

- CL42A** (K40/XXX)
Acoustic System Panel Colour 1
- CL42B** (K40/XXX)
Acoustic System Panel Colour 2
- CL42C** (K40/XXX)
Acoustic System Panel Colour 3

Acoustic requirements tbc subject to further coordination with acoustic consultant

Specialist system(s)

The diagram shows three specialist systems, each with a unique icon and a label in a box:

- CL51A** Linear Slats (Icon: Red horizontal slats) [K40/XXX]
- CL52A** Raft System (Icon: Red raft structure) [K40/XXX]
- CL54A** Timber Panel System (Icon: Red timber panel) [N10/XXX]

Bespoke system(s)

CL61A K40/XXX
Timber framed Coffee Ceiling

Other

CTXX
Curtain Tracks

Bulkhead (High Level)
Denotes extent of high level bulkheads
(Refer to 226XX series for details)
All bulkhead to be painted with WF62A -
Taupe. Paint colour TBC at Stage 4.

CTXX
Curtain Tracks

Bulkhead (High Level)
Denotes extent of high level bulkhead
(Refer to 226XX series for details)
All bulkhead to be painted with White
Taupe. Paint colour TBC at Stage 2

Refer to 428XX series drawings for high level painting & decorating finishes

Basebuild/Existing

Where no ceiling indicated:
concrete slab to be exposed and
existing coffer ceilings to be retained

Exposed slab to be cleaned and made
good. All existing services to be
removed.

Where no ceiling indicated:
concrete slab to be exposed and
existing coffer ceilings to be retained

Exposed slab to be cleaned and made
good. All existing services to be
removed.