



all existing windows to be carefully removed

all existing lightweight internal partitions / doors and suspended ceilings to be removed

all existing loose fittings and fixtures, sanitary-ware etc to be removed from internal spaces

all existing pipework / services internally to be removed. all connecting services to be safely terminated in advance

all existing lightweight staircases to be removed

all walls to lift/hoist shafts interfering with proposed accommodation arrangement to be demolished

carry out brickwork repairs locally where necessary. areas of repointing not deemed to be lime mortar type to be raked and reinstated as such

cleaning method to existing brickwork / masonry (cills / lintels e
internally to be agreed with LA


key:

--- to be removed/demolished

void to be in-filled/repaired

1 original escape stairs to be cleaned and retained subject to condition

2 lift shaft walls to be demolished. 300mm approx. to be left in place to support beam.



demolition plans • minto + turner third floor

d • planning issue	20.01.17 • ch •
c • status updated, notes updated + draft planning issue	10.11.16 • hlm •
b • work stage 2	28.07.16 • hlm •
a • draft work stage 2	14.07.16 • ejd •
• first issue	27.05.16 • hlm •
rev • description	issued • drawn • checked

shedkm

```
+44 (0)151 709 8211
+44 (0)207 253 8881
```

project	kampus • listed building
client	AA
drawing number	AW(00)11
scale	100 @
status	work stage

minto • third floor demolitions

do not scale from this drawing • all dimensions are to be set out and checked on site prior to construction • any discrepancy found between information given on this drawing and that elsewhere or recorded on site shall be brought to the attention of the project architect immediately