







GENERAL NOTES

1. Do not scale from this print or use as a template.
2. All dimensions must be verified on site before any work is put in hand and any discrepancies must be reported to the Architect. Where any variations occur between small scale and detailed drawings, detail drawings should be worked from.
3. Copyright of this drawing is reserved by Osbornes and is issued on condition that it is not copied or disclosed to any third party either wholly or in part without the consent of Osbornes in writing.

-  Existing render - Render to be carefully removed and area re-rendered using Sto or Keim render or similar. Note: Existing background to be checked and if required mesh reinforcement to be incorporated as manufacturers recommendations. Finished render to receive paint finish as specified. Note: Paint finish to be fully compatible with render finish.
-  Stone - All paintwork to be removed as specified. It is likely that the stone has been substantially repaired over the years. All previous repairs are to be carefully cleaned off and the stonework is to be repaired and profiles returned using specialist mortars, ie, Keim Restauro or similar approved. Completed stonework/ repairs to receive paint finish as specified. Note: paint finish to be fully compatible with repair materials and stone.
-  Existing render - Render to be repaired and repainted. Finished render to receive paint finish as specified. Note: Paint finish to be fully compatible with render finish. All repairs to BS EN 13914-1:2016.

EXISTING QUAY STREET ELEVATION
1:100



EXISTING BYROM STREET ELEVATION
1:100