



revision: date: note:
P01 2020.07.31 preliminary first issue
P02 2021.01.05 updated

red fill illustrates demolitions

Demolition schedule

- 01 remove tiles to pike of warehouse facade and replace with stone coping
- 02 remove temporary hoarding
- 03 remove scaffold, advertisement and associated lighting
- 04 remove non-original fittings including alarms, pipes, uplighters, etc
- 05 remove non-original shop front and replace with PPC windows and doors
- 06 remove roller shutter and door and replace with PPC door
- 07 remove non-original facias and repair brick facade
- 08 remove non-original grilles and ventilation fans to existing windows (red hatch)

green fill illustrates retained features

Retention schedule

- A1 retain existing warehouse masonry facade, copings and repair as necessary
- A2 retain and repair existing warehouse windows and doors

project
43-47 piccadilly, manchester

job no.

7422

title
existing Back Piccadilly elevation (demolitions)

scale

1:100 @ A3

drawing no.

7546-al(03)0032

stephenson hamilton risley
STUDIO

3 riverside mews
4 commercial street
manchester, M15 4RQ
www.shr.studio
mail@shr.studio
0161 832 0244