



AC (1 : 6)



Stainless Steel Brush Finish
Hand Held Post Socket with Cover plate,
by Sesame

Lift in Down Position (1 : 20)
Home Position



Removable Footlights, by Others

Plum flush surface on Riser Wall


Plum flush Surface on part of side wall
for Stabilisation Wheel to run on

L (1 : 1)

Stainless Steel Platform Tray Visible edges


18 mm Touch Sensitive Tape Switch on Both Sides of Platform

Stainless Steel Pit Trim Visible edges




Stainless steel brush finish
Lower Landing Main Button Station,
by Sesame
location behind side wall
Wall mounted

Y (1 : 6)



Lift in Up Position (1 : 20)



Machine Room Cabinet ,by Sesame

Stainless Steel brush finish
removable Hand Held Post,
By Sesame

Stainless Steel brush finish
Wheelstop, by Sesame

Black Bellows under the Platform, by Sesame

Changes since rev_P00:
- Sheet numbering system updated;

Changes since rev_P01:
- Site layout updated;
- Lift style changed;
- Page with pit trim and
loading points added;

Changes since rev_P02:
- Main Button Station update (wooden enclosure)
- Safety Working Load Plate added
- Hand Held Post location update
- Touch sensitive Tape Switch on
sides of platform added
- Site Layout update

Changes since rev_P03:
- Platform size and pit size update

Changes since rev_P04:
- Location of button station has been changed
- Floor buildup has been changed
- Stabilisation channel has been added

Changes since rev_P05:
- Machine room Cabinet under stage
Visual representation added;
- MRC Conduit route changed;
- Button Station location changed;
- Pit trim changed;

Changes since rev_P06:
- Site Layout update;
- Visible Finish Changed to Stainless Steel;
- HHP Location Change;
- Riser Wall Stabilisation Channel Removed;
- Side Wall Stabilisation Wheel Added;
- Power Requirements updated;


Changes since rev_P07:
- UPS battery backup removed;

Changes since rev_P08:
- UPS battery backup added;

PLEASE NOTE THAT THE SESAME LIFT (RISERS AND TREADS) NEEDS TO BE CLAD FIRST,
BEFORE THE SITE CLADDING IS PUT AROUND THE SESAME SYSTEM.
IF THE AREA AROUND THE SESAME SYSTEM IS CLAD PRIOR TO THE SESAME LIFT,
SESAME SYSTEM LTD. WILL TAKE NO RESPONSIBILITY FOR MISALIGNMENTS OF ALL CLADDING.

Client/Architect/Stonemason to specify the Treads Nosing's or Anti Slip Strips
on the Treads to match the surrounding steps cladding details.

BS:6440:2011, 8.3 - Adjacent surfaces
For adjacent surfaces 10mm or less from any part of the carrier, any projections on the surface shall be as follows:-
a) If they include projections up to 1.5mm, they may have square corners
b) If they include projections from 1.5mm up to 5mm they shall have a minimum of 15 degrees vertical chamfers on all edges
Adjacent surfaces greater than 10mm and less than 100mm from the carrier shall have a sensitive edge, photo cell or light curtain located along any affected sides.
Note there is a risk of crushing if the part of the structure is less than 100mm to an adjacent surface.
To remove any crush zone risk there should be a distance of 300mm or more between the carrier and the crush zone.

This drawing and the information it contains is the property of Sesame Access Systems LTD. and must not be copied or issued to any third party	Designed by K. Porwol	Checked by S.J.Lyons	Date 25/04/2022	Project Name: OTH-SAS-TH-01-DWG-X-0001	Revision P09
				3D Layout	Sheet 1 / 5
	Sesame ACCESS FOR ALL Unit 1, Cumberland Works Winterset Business Park Surrey, KT14 7LF Tel: +44 (0)1784 440088 Fax: +44 (0)1784 705252 Email: foral@sesameaccess.com Web: www.sesameaccess.com				