




Home position
OnLift gate closed
Upper Landing Barrier Rised




BE (1 : 8)




Lift up position,
OnLift gate closed,
Upper Landing Rising Barrier Lowered



Lift down position,
OnLift gate open



BH (1 : 3)



Changes made since rev_P01:
- numbering system updated;

Changes made since rev_P03:
- Beam construction by Others colored in red
- Pit size and Glass installation updates
- Side walls design update
- Lower Landing Automatic Gate removed

Changes made since rev_P04:
- Blockwork infill surrounding Sesame lift added
- Beam construction by Others placement
- Rising glass Barrier added
- Pit Size and Pit Trim
- Loading points location
- Upper Landing Button Post position

Changes made since rev_P05:
- Lower Landing and Upper Landing design update
- Site layout and beam design update

Changes made since rev_P06:
- Button posts have been updated
- Site Layout has been updated
- Sesame System has been adjusted to the new layout
- Steel frame has been updated

Changes made since rev_P07:
- Upper Landing Cover plate added

Changes made since rev_P08:
- On Lift Handrail added;
- On Lift Button Post Incorporated into Handrail;
- Lift Frame modified to fit the ledge;
- Sesame System enclosure updated;
- Glass overhang has been updated

Changes made since rev_P09:
- Acces gantry representation added as per OTH-PUR-TH-LG-SKE-A-3093;
- Pit walls representation updated;
- Button post has been updated;
- Speaker has been added;
- Electroplating finish has been updated.

PLEASE NOTE THAT THE SESAME LIFT (RISERS AND TREADS) NEEDS TO BE CLAD FIRST, BEFORE THE SITE CLADDING IS PUT AROUND THE SESAME SYSTEM.
IF THE AREA AROUND THE SESAME SYSTEM IS CLAD PRIOR TO THE SESAME LIFT, SESAME SYSTEM LTD. WILL TAKE NO RESPONSIBILITY FOR MISALIGNMENTS OF ALL CLADDING.

Client/Architect/Stonemason to specify the Treads Nosing's or Anti Slip Strips on the Treads to match the surrounding steps cladding details.

OTH-SAS-TH-GF-DWG-X-0001 Status S3 Revision P10

This drawing and the information it contains is the property of Sesame Access Systems LTD. and must not be copied or issued to any third party	Designed by K. Porwol	Checked by S.J.Lyons	Date 28.01.2022	Project Name: OTH-SAS-TH-GF-DWG-X-0001	Revision P10
				3D Layout	Sheet 1 / 6

BS:6440:2011, 8.3 - Adjacent surfaces
For adjacent surfaces 10mm or less from any part of the carrier, any projections on the surface shall be as follows:-
a) If they include projections up to 1.5mm, they may have square corners
b) If they include projections from 1.5mm up to 5mm they shall have a minimum of 15 degrees vertical chamfers on all edges
Adjacent surfaces greater than 10mm and less than 100mm from the carrier shall have a sensitive edge, photo cell or light curtain located along any affected sides.
Note there is a risk of crushing if the part of the structure is less than 100mm to an adjacent surface.
To remove any crush zone risk there should be a distance of 300mm or more between the carrier and the crush zone.