



PROPOSED NOTES:	GENERAL NOTES:
GFA GENERAL STRIP-OUT OF NON-ORIGINAL FIXED & LOOSE FURNITURE. WALLS & FLOORS TO BE MADE GOOD WHERE REQUIRED & PREPARED FOR DECORATION. GFA1 EXISTING NON-ORIGINAL WALL LININGS TO BE REMOVED. ORIGINAL MASONRY WALL TO BE EXPOSED, SEALED / WHITE WASHED TO ID SPECIFICATION. GFB EXISTING NON-ORIGINAL ACOUSTIC FLOOR TO FORMER ENSUITES IN TYPE A ROOMS TO BE REMOVED & REPLACED. REPLACED WITH NEW PLYWOOD FLOOR DECK ON BATTENS. GFC NEW FRAMING AROUND NON-ORIGINAL SECONDARY GLAZING TO PROVIDE ACOUSTIC DETAIL TO ORIGINAL FABRIC. GFD NEW SANITARYWARE & ENSUITE FINISHES GFE NEW CASE GOODS & FINISHES GFF EXISTING NON-ORIGINAL STAIR TO RECEIVE NEW WALL, FLOOR & CEILING FINISHES. GFG EXISTING NON-ORIGINAL STORE ROOM STRIPPED OUT & FITTED OUT AS PANTRY.	ALL DIMENSIONS ARE TO BE CHECKED ON SITE WITH ANY DISCREPANCIES REPORTED TO THE ARCHITECT PRIOR TO THE WORKS BEING CARRIED OUT. ALL WORKS ARE TO BE IN ACCORDANCE WITH THE PLANNING APPROVAL AND ANY SUBSEQUENT APPROVED LOCAL AUTHORITY PLANNING CORRESPONDENCE INCLUDING DRAWINGS, DOCUMENTS AND REPORTS. ALL WORKS ARE TO COMPLY WITH THE BUILDING REGULATIONS, BRITISH STANDARDS, CODE OF PRACTICE, AND ANY LOCAL STATUTORY REQUIREMENTS. ALL WORKS ARE TO COMPLY WITH CURRENT HEALTH AND SAFETY LEGISLATION, H.S.E. RECOMMENDATIONS/GUIDANCE AND THE CURRENT C.D.M. REGULATIONS. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH LEACH RHODES WALKER ARCHITECTS GENERAL ARRANGEMENT (L CODE) DRAWINGS, TOGETHER WITH RELEVANT DETAILED (A CODE) DRAWINGS AND SPECIFICATIONS. FOR ALL STRUCTURAL WORKS REFER TO THE STRUCTURAL ENGINEERS INFORMATION. FOR ALL MECHANICAL AND ELECTRICAL WORKS REFER TO THE MECHANICAL AND ELECTRICAL ENGINEERS INFORMATION. FOR ALL ABOVE GROUND DRAINAGE WORKS REFER TO THE PUBLIC HEALTH ENGINEERS INFORMATION. ALL PRODUCTS SPECIFIED ARE TO BE INSTALLED STRICTLY IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS, SPECIFICATION AND DETAILS.

G.A. KEY:

EXISTING SURVEYED FLOOR LEVEL	PROPOSED FLOOR LEVEL
F.F.L.	FINISHED FLOOR LEVEL
F.S.L.	FINISHED SCAFFOLD LEVEL
S.S.L.	STRUCTURAL SLAB LEVEL
C.O.S.	TO BE CHECKED ON SITE
I.C.	INSPECTION COVER
F.P.S.	FIRE PREVENTION SYSTEM TO BE INSTALLED WITHIN KITCHEN UNIT
RAINWATER OUTLET	RAINWATER PIPE
SOILWASTE VENT PIPE	FOUL WATER HIGH LEVEL FALLS
SURFACE WATER HIGH LEVEL FALLS	PIPE PENETRATION IN SLAB ABOVE
ORIGINAL FABRIC (e.g. WINDOWS / DOORS) TO BE RETAINED	NON-ORIGINAL FABRIC TO BE RETAINED
AREA TO REMAIN AS EXISTING (NO PROPOSED WORK)	CONCRETE BLOCK WORK WALLS AS NOTED ON LRW L142 CODE DRAWINGS
PLASTERBOARD & STUD PARTITION WALLS AS NOTED ON LRW L142 CODE DRAWINGS	NEW DOOR & FRAME - REFER TO LRW DRAWING 7611-A32 CODE
FD 60S - FIRE RESISTANCE OF DOOR (MINUTES) & SMOKE SEALS	SC - SELF CLOSING DEVICE
PL - PROXIMITY CARD READER LOCK	NEW TIMBER JOISTED STRUCTURAL FLOOR TO MATCH EXISTING ORIGINAL STRUCTURAL FLOOR BUILD-UP, TO S.E. DETAILS TO ALIGN WITH UPPER GROUND FLOOR MOVEMENT JOINT TRK WITH S.E.
NEW ACOUSTIC FLOOR ON EXISTING NON-ORIGINAL STRUCTURAL FLOOR	MOVEMENT JOINT BETWEEN ORIGINAL TIMBER FLOOR AND CONCRETE SLAB, TIC WITH S.E.

A - FURTHER DETAILED NOTES ADDED IN RESPONSE TO PLANNERS LETTER DATED 14/04/21.		DATE	26.04.21
REV	DESCRIPTION	DATE	BY
01	ISSUED FOR PERMIT	26.04.21	SJM

DO NOT SCALE OFF THIS DRAWING

LeachRhodesWalker Architects

Info@lrw.co.uk | www.lrw.co.uk
50 Deansgate Place Manchester M3 5LH

Manchester London Bournemouth
+44 (0)161 833 0211 +44 (0)207 993 1363 +40 (21)850 4026

client	
ASPEN HOTELS LTD	
project	
STOREYS MANCHESTER	
project no.	drawing no.
8180	L(00)204
rev	A
description	
PROPOSED SECOND FLOOR PLAN	
scale	date issued
1:50@ A0	09/03/21
drawn by	checked by
SJM	SJM
approved by	
SJM	
date of issue	
09/03/21	
drawing no.	
L(00)204	