


1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE SPECIFICATION FOR MECHANICAL SERVICES INSTALLATION AND ALL ASSOCIATED MECHANICAL SERVICES DRAWINGS LISTED THEREIN.
2. ALL MECHANICAL SERVICES DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ASSOCIATED ARCHITECTURAL, STRUCTURAL, PUBLIC HEALTH & ELECTRICAL SERVICES DRAWINGS.
3. SPRINKLER PIPEWORK SERVICES ARE INDICATIVE ONLY. TOBE CONFIRMED WITH SPECIALIST SUBCONTRACTOR.
4. BCWS & HWSF TO BATHROOMS TO BE 220 mm.
5. ALL THW PIPEWORK TO BE FROM RADIATORS TO BE 100 mm.
6. EXPOSED DUCTWORK 1250 mm SPIRAL GALV AND DUCTWORK 204 x 60 mm PLASTIC RECTANGULAR.
7. ALL ATMOSPHERIC DUCTWORK TO BE INSULATED.
8. REFER TO UTILITY DRAWING 4009-BAF-MH-ZZ-DR-51-011.

_____ HIGH LEVEL SERVICES
 _____ LOW LEVEL SERVICES
 _____ SERVICES WITHIN FLOOR VOID

- T** PROGRAMMABLE ROOM THERMOSTAT
- MVHR - RETURN DUCT
- MVHR - EXHAUST DUCT (INSULATED)
- MVHR - SUPPLY DUCT
- MVHR - FRESH AIR DUCT (INSULATED)

- EXPOSED DUCTWORK
- BULKHEAD (CONCEALED SERVICES)

MH 102
MH 103
MH 109
MH 110
MH 202
MH 213
MH 214
MH 302 - VENTILATION TERMINATES THROUGH ROOF
MH 313 - VENTILATION TERMINATES THROUGH ROOF
MH 314 - VENTILATION TERMINATES THROUGH ROOF



Briggs & Forrester Living Ltd
 Sembridge House
 Sembridge Drive
 Kingshorpe
 Northampton
 NN2 6LZ
www.briggsandforrester.co.uk Tel: (01604) 720072


 The logo consists of a green square with a white border. Inside the square, there are three stylized, overlapping white arrows pointing upwards and to the right. The arrows are composed of horizontal and vertical segments, creating a geometric, blocky appearance.

Mount Anvil

Scale:	1:50 @ A0	Checked:	BC
--------	-----------	----------	----

Suitability: 0.4	Drawing Status: CONSTRUCTION
---------------------	---------------------------------



bsi.
BIM Verified
Design & Construction
Capital/Delivery
PAS 1192-2

VC 658367