

Site Location:
Start Date:
Expected Job Duration:
Method Statement Completed by:

Wall knock throughs

Prior to work commencing ensure no electrical or mechanical cables/pipes will interfere with the projective aperture knock through. Ensure areas of work are clear and where necessary fully protected by hoarding/sheeting to prevent the spread of dust. Fully mark out on wall aperture to be cut out, use necessary tools/plant to cut into wall prior to any hydraulic or other plant being used to remove the brick blockwork. If walls are load bearing, pilot holes and acrojacks or pinning maybe required. Fit concrete or timber lintols to support the walls above aperture. Make good aperture to receive door frames/plastered masons opening.
--