

Site Location:
Start Date:
Expected Job Duration:
Method Statement Completed by:

Lighting Installation
Check with principal contractor/site foreman and liaise with other contractors before switching off lighting. Lock off lighting circuit, key to be kept with the electrical foreman. Fit warning signs to isolating switches. Prove the circuit is dead via test meter. Reposition lights according to new arrangement and alter existing switching arrangement where necessary. Check all connections and fittings for security and integrity. Re-energize lighting supply.