

FIRE NOTES

	Fire rated 30 minutes (R,E,I)
	Fire rated 60 minutes (R,E,I)
	Break Glass Unit
	Fire Extinguisher
	Exit
	Disabled Alarm Pull Cord Switch

DOORS & WINDOWS

FD30	Fire door 30 mins
FD30S	Fire door 30 mins with seals
FD60	Fire door 60 mins
FD60S	Fire door 60 mins with seals
FR30/30I	30 mins integrity and 30 mins insulation glass screen
FR60/60I	60 mins integrity and 60 mins insulation glass screen

NOTES

Allsteels fire protected 60mins with intumescent paint, generally site applied. Colour to be confirmed.

Fire extinguishers should be located such that one may be reached within 30m and a minimum of 2 no. 12A extinguishers at Ground Floor and 2 no. 13A extinguishers at 1st Floor

RF Suspended ceilings to be 60min fire rated on ground floor. 30min fire rated on 1st floor (44 not rated only)

ALARM SYSTEMS

	Smoke Detector
	Combined smoke detector, sounder and beacon
	Heat Detector - fixed temperature
	Combined heat detector, sounder and beacon
	Flush mount sampling point for ADS
	Wall mounted fire alarm beacon
	Wall mounted fire alarm sounder & beacon
	Induction loop panel
	PIR Detector

ALARM SYSTEMS	
A	Aspirator Sampling Detection System
INT	Interface Module
DAP	Disabled Alarm Control/Indicator Panel
DAR	Disabled Alarm Repeat Panel
DRI	Disabled Refuge Intercom
EDR	Electro Magnetic Door Release
FAP	Fire Alarm Panel
DH	Door Hold Open
VSP	Aspirator Power Supply Unit
INT	Fire Alarm linked to aspirating Fire Alarm Systems

DO NOT SCALE FROM THIS DRAWING

THE CONTRACTOR IS TO CHECK AND VERIFY ALL BUILDING AND SITE DIMENSIONS, LEVELS AND SEWER INVERT LEVELS AT CONNECTION POINTS BEFORE WORK STARTS


THIS DRAWING IS TO BE READ AND CHECKED
IN CONJUNCTION WITH ENGINEERS AND OTHER
SPECIALIST DRAWINGS

THE DRAWING AND THE WORKS DEPICTED ARE
THE COPYRIGHT OF THIS PRACTICE AND MAY NOT
BE REPRODUCED EXCEPT BY WRITTEN PERMISSION

DRAWINGS TO BE USED FOR COSTING PURPOSES
ONLY

DESIGNS SUBJECT TO DISCHARGE OF PLANNING
CONDITIONS AND BUILDING CONTROL APPROVAL

CONTRACTOR TO ALLOW ADEQUATE TIME FOR
STATUTORY SIGN-OFF PROCESS FOR ALL SAMPLES
REQUESTED



C	26.05.20	AI 29 Bulk head
B	21.05.20	Stage 5 Issue
A	06.12.19	Stage 5 Issue
Rev:	Date:	Description

Job: 1603 Jewish Museum
Client: Manchester Jewish Museum

Drawing: Proposed G+1 Fire Strategy

Drawing no:	Rev:	Status:
1603-5-151	C	Stage 5
Scale:		Date:
1:100 @A3 1:50 @A3		12.11.2019

citizensdesign**bureau**
Studio 118, Hackney Downs Studios, 17 Amhurst Terrace,
London, E8 2BT
t : 02030959732
e : everyone@citizensdesignbureau.net