

Our Ref: 949-02-CIV-Planning Condition 15 response

**Medieval Quarter Glade of Light
23 March 2021**

Response to planning condition 15 - Drainage and flood risk

See below response to planning condition 15 relating to surface water drainage and flood risk for the Medieval Quarter Glade of Light development.

The below table highlights the planning condition comments with Civic Engineers' response alongside.

Planning Condition Comments	Designer's Response
No development shall take place until surface water drainage works have been implemented in accordance with Non-Statutory Technical Standards for Sustainable Drainage Systems (March 2015) or any subsequent replacements national standards and details that have been submitted to and approved in writing by the Local Planning Authority.	
In order to avoid/discharge the above drainage condition the following additional information has to be provided: *Details of surface water attenuation that offers a reduction in surface water runoff rate in line with the Manchester Trafford and Salford Strategic Flood Risk Assessment, i.e. at least a 50% reduction in runoff rate compared to the existing rates, as the site is located within Conurbation Core Critical Drainage Area; *Runoff volume in the 1 in 100 year, 6 hours rainfall shall be constrained to a value as close as is reasonable practicable to the greenfield runoff volume for the same event, but never to exceed the runoff volume from the development site prior to redevelopment; *Evidence that the drainage system has been designed (unless an area is designated to hold and/or convey water as part of the design) so that flooding does not occur during a 1 in 100 year rainfall event with allowance for 40% climate change in any part of a building;	See attached calculations for surface water discharge rates and attenuation volumes, these include: 949-02-CIVIC-C-XX-EX-001_P01- Existing SW Drainage - Existing catchment plan and brownfield run-off calculation Proposed drainage network model, with hydrobrake details and restriction to 50% of the existing 1:1 year flow rate See microdrainage snapshot below and description of calculation method for the run-off volume for the 1:100 year 6 hour duration storm event for the proposed development is 3 Greenfield 1:100 year 6 hour duration event Pre-development 1:100 year 6 hour duration event The microdrainage network calculations show the 1:100 year + 40% climate change storm event contained within the drainage network and SuDS features. 949-02-CIV-Micro drainage network output file rev C01

*Where surface water is connected to the Highway gullies to outfall into River Irwell, agreement in principle from Manchester City Council Highways Department is required. An email of acceptance of proposed flows and/or new connection will suffice.	See attached correspondence from MCC highways and LLFA to date relation to the existing highways drainage. It is understood that as the highways gully is under MCC highway's ownership that the outfall is also under the ownership / management of MCC highways. We await confirmation from the LLFA relating to this.
*Hydraulic calculation of the proposed drainage system;	See attached file 949-02-CIV-Micro drainage network output file rev C01
*Construction details of flow control and SuDS elements. Reason: To promote sustainable development, secure proper drainage and to manage the risk of flooding and pollution. This condition is imposed in light of national policies within the NPPF and NPPG and local policies EN08 and EN14. If there is no clear adoption policy in place to take over the proposed drainage system after construction, we suggest the following construction and maintenance condition to be considered by the LPA:	See attached specification for the Hydrobrake flow control. Also included are the details for the SuDS elements (drawing 949-02-CIVIC-C-XX-DE-004_P03- Drainage Details Sheet 4). MCC will take on maintenance responsibilities for the public realm including SuDS features.

Output from discharge volume wizard tool in Microdrainage below (6 hour 1:100 year storm event)

Discharge Wizard Results

PN	Volume Calculation Method	Pre-development Volume (m³)	Post-development Volume (m³)	Pass/Fail
1.004	Greenfield	183.729	311.795	✗
1.004	Brownfield	312.347	311.795	✗

Warning - The network was still discharging at the end of the discharge volume test and so it is unlikely the system has fully drained down. It is advisable you rerun the simulation using a longer analysis time to allow the system to fully drain down. [See How Do I 39 - Procedure 2.](#)

Summary
Discharge Rates
Discharge Volumes
Minimal Discharge

Micro Drainage
OK
Help

This shows the predevelopment (brownfield) run-off volume (312.347m^3), greenfield run-off volume (183.729m^3) versus the post development run-off volume (311.795m^3). The overall catchment area for all 3 analysis' was taken as 6250m^2 which represents catchment 1A and 1C.

It should be noted that both Phase 1A and 1C have a significant reduction in hardstanding area with Phase 1A impermeable area equating to 2258m^2 . And the Phase 1C impermeable area of circa 2500m^2 (which may be subject to further development). Due to the nature of the surface water drainage system utilising SuDS within the soft landscaping areas, the full catchment has been included within the calculations (6250m^2) which represents a conservative approach to the surface water run-off and discharge volume calculations.

If we re-run the calculations for the actual impermeable catchment through the discharge volume wizard for the same 6 hour 1:100 year storm event but for the 2258m^2 catchment we get a discharge volume of 239m^3 which is a lot closer to the greenfield run-off volume.

The attached documents are provided to support the above responses:

Micro Drainage network calculations

- 949-02-CIV-Micro drainage network output file rev C01

Drainage and Levels Design Drawings

- 949-02-CIVIC-C-XX-EX-001_P01- Existing SW Drainage
- 949-02-CIVIC-C-XX-DE-004_P03- Drainage Details Sheet 4
- 949-02-CIVIC-C-XX-GA-009_P02 Proposed Levels
- SHE-0275-4230-0960-4230_Design_Drawing(OD)
- 949-02-CIVIC-C-XX-DR-002_P06 - Proposed SW Drainage Strategy Phase 1A

Correspondence with MCC, EA and LLFA

Chris Kendrick
For Civic Engineers

Civic Engineers		Page 1
Carvers Warehouse 77 Dale Street Manchester, M1 2HG		
Date 24/03/2021 00:02 File 949-02_SW Drainage Strat...		
Designed by chrisk Checked by		
Innovyze		Network 2020.1

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	2	PIMP (%)	100
M5-60 (mm)	18.000	Add Flow / Climate Change (%)	0
Ratio R	0.357	Minimum Backdrop Height (m)	0.000
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	20.000
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Network Design Table for Storm

« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.000	9.695	0.200	48.5	0.304	4.00	0.0	0.600	o	300	Pipe/Conduit	
S1.001	38.394	0.375	102.4	0.015	0.00	0.0	0.600	o	300	Pipe/Conduit	
S2.000	10.800	0.140	77.1	0.020	6.00	0.0	0.600	o	100	Pipe/Conduit	
S2.001	12.689	0.285	44.5	0.011	0.00	0.0	0.600	o	100	Pipe/Conduit	
S3.000	7.382	0.330	22.4	0.015	6.00	0.0	0.600	o	100	Pipe/Conduit	
S4.000	14.083	0.100	140.8	0.015	6.00	0.0	0.600	o	100	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.000	50.00	4.07	31.500	0.304	0.0	0.0	0.0	2.26	160.0	41.2
S1.001	50.00	4.48	31.274	0.319	0.0	0.0	0.0	1.55	109.8	43.2
S2.000	50.00	6.21	30.840	0.020	0.0	0.0	0.0	0.88	6.9	2.7
S2.001	50.00	6.39	30.700	0.031	0.0	0.0	0.0	1.16	9.1	4.2
S3.000	50.00	6.08	30.895	0.015	0.0	0.0	0.0	1.64	12.9	2.0
S4.000	50.00	6.36	30.925	0.015	0.0	0.0	0.0	0.65	5.1	2.0

©1982-2020 Innovyze

Civic Engineers		Page 4
Carvers Warehouse 77 Dale Street Manchester, M1 2HG		
Date 24/03/2021 00:02 File 949-02_SW Drainage Strat...		
Designed by chrisk Checked by		
Innovyze		Network 2020.1

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.004	8.925	0.052	171.6	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.004	49.85	7.50	28.575	0.625	0.0	0.0	0.0	1.20	84.6	84.4

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
S1.004	S	30.230	28.523	28.500	0	0

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m³/ha Storage	0.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1
Number of Input Hydrographs	0	Number of Storage Structures	10
Number of Online Controls	9	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Profile Type	Summer
Return Period (years)	2	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	18.000	Storm Duration (mins)	30
Ratio R	0.357		

©1982-2020 Innovyze

Civic Engineers		Page 5
Carvers Warehouse 77 Dale Street Manchester, M1 2HG		
Date 24/03/2021 00:02 File 949-02_SW Drainage Strat...	Designed by chrisk Checked by	
Innovyze	Network 2020.1	
Online Controls for Storm Orifice Manhole: S1, DS/PN: S1.001, Volume (m³): 0.8 Diameter (m) 0.130 Discharge Coefficient 0.600 Invert Level (m) 31.300 Orifice Manhole: SIC3, DS/PN: S2.002, Volume (m³): 0.3 Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 30.280 Orifice Manhole: SIC13, DS/PN: S5.001, Volume (m³): 0.4 Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 30.550 Orifice Manhole: SIC15, DS/PN: S7.001, Volume (m³): 0.4 Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 30.170 Orifice Manhole: SIC8, DS/PN: S5.003, Volume (m³): 0.4 Diameter (m) 0.060 Discharge Coefficient 0.600 Invert Level (m) 29.526 Orifice Manhole: SIC18, DS/PN: S10.001, Volume (m³): 0.2 Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 28.820 Orifice Manhole: SIC17, DS/PN: S11.001, Volume (m³): 0.3 Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 28.875 Orifice Manhole: SIC16, DS/PN: S12.001, Volume (m³): 0.4 Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 29.310 Hydro-Brake® Optimum Manhole: S4, DS/PN: S1.004, Volume (m³): 6.3 Unit Reference MD-SHE-0271-4230-1250-4230 Design Head (m) 1.250 Design Flow (l/s) 42.3 Flush-Flo™ Calculated Objective Minimise upstream storage Application Surface Sump Available Yes Diameter (mm) 271 Invert Level (m) 28.575		
©1982-2020 Innovyze		

Civic Engineers

Carvers Warehouse

77 Dale Street

Manchester, M1 2HG

Date 24/03/2021 00:02

File 949-02_SW Drainage Strat...

Designed by chrisk

Checked by

Innovyze

Network 2020.1

Page 6



Hydro-Brake® Optimum Manhole: S4, DS/PN: S1.004, Volume (m³): 6.3

Minimum Outlet Pipe Diameter (mm) 300

Suggested Manhole Diameter (mm) 1800

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.250	42.3	Kick-Flo®	0.918	36.5
Flush-Flo™	0.452	42.3	Mean Flow over Head Range	-	35.3

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	8.6	1.200	41.5	3.000	64.5	7.000	97.4
0.200	27.9	1.400	44.6	3.500	69.5	7.500	100.7
0.300	41.1	1.600	47.6	4.000	74.2	8.000	104.0
0.400	42.2	1.800	50.4	4.500	78.5	8.500	107.1
0.500	42.2	2.000	53.0	5.000	82.7	9.000	110.1
0.600	41.7	2.200	55.5	5.500	86.6	9.500	113.1
0.800	39.7	2.400	57.9	6.000	90.4		
1.000	38.0	2.600	60.2	6.500	93.9		

©1982-2020 Innovyze

Civic Engineers		Page 8																																																												
Carvers Warehouse 77 Dale Street Manchester, M1 2HG																																																														
Date 24/03/2021 00:02 File 949-02_SW Drainage Strat...	Designed by chrisk Checked by																																																													
Innovyze Network 2020.1																																																														
<u>Tank or Pond Manhole: SIC15, DS/PN: S7.001</u> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th></tr><tr><td>0.000</td><td>10.0</td><td>0.500</td><td>10.0</td><td>0.501</td><td>0.0</td></tr></table> <u>Tank or Pond Manhole: SIC8, DS/PN: S5.003</u> Invert Level (m) 29.526 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th></tr><tr><td>0.000</td><td>20.0</td><td>0.500</td><td>20.0</td><td>0.501</td><td>0.0</td></tr></table> <u>Tank or Pond Manhole: SIC18, DS/PN: S10.001</u> Invert Level (m) 28.820 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th></tr><tr><td>0.000</td><td>5.0</td><td>1.000</td><td>5.0</td><td>1.001</td><td>0.0</td></tr></table> <u>Tank or Pond Manhole: SIC17, DS/PN: S11.001</u> Invert Level (m) 28.960 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th></tr><tr><td>0.000</td><td>5.0</td><td>1.000</td><td>5.0</td><td>1.001</td><td>0.0</td></tr></table> <u>Tank or Pond Manhole: SIC16, DS/PN: S12.001</u> Invert Level (m) 29.310 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th></tr><tr><td>0.000</td><td>30.0</td><td>0.500</td><td>30.0</td><td>0.501</td><td>0.0</td></tr></table>			Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)	0.000	10.0	0.500	10.0	0.501	0.0	Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)	0.000	20.0	0.500	20.0	0.501	0.0	Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)	0.000	5.0	1.000	5.0	1.001	0.0	Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)	0.000	5.0	1.000	5.0	1.001	0.0	Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)	0.000	30.0	0.500	30.0	0.501	0.0
Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)																																																									
0.000	10.0	0.500	10.0	0.501	0.0																																																									
Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)																																																									
0.000	20.0	0.500	20.0	0.501	0.0																																																									
Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)																																																									
0.000	5.0	1.000	5.0	1.001	0.0																																																									
Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)																																																									
0.000	5.0	1.000	5.0	1.001	0.0																																																									
Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)																																																									
0.000	30.0	0.500	30.0	0.501	0.0																																																									
©1982-2020 Innovyze																																																														

Civic Engineers

Carvers Warehouse
77 Dale Street
Manchester, M1 2HG

Date 24/03/2021 00:02
File 949-02_SW Drainage Strat...

Innovyze

Designed by chrisk
Checked by

Network 2020.1

Page 9



Summary of Critical Results by Maximum Outflow (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000

Additional Flow - % of Total Flow 0.000

Hot Start (mins) 0

MADD Factor * 10m³/ha Storage 0.000

Hot Start Level (mm) 0

Inlet Coeffiecient 0.800

Manhole Headloss Coeff (Global) 0.500

Flow per Person per Day (l/per/day) 0.000

Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0

Number of Storage Structures 10

Number of Online Controls 9

Number of Time/Area Diagrams 0

Number of Offline Controls 0

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model

FSR

Ratio R 0.360

Region England and Wales Cv (Summer) 0.750

M5-60 (mm)

18.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0

DVD Status OFF

Analysis Timestep

Fine Inertia Status OFF

DTS Status

ON

Profile(s)

Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440

Return Period(s) (years) 1, 30, 100

Climate Change (%) 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S1.000	SPhs1C	15 Summer	100	+40%	100/15 Summer				32.068
S1.001	S1	60 Winter	100	+40%	100/15 Summer				32.232
S2.000	SIC1	15 Winter	100	+40%	100/15 Summer				31.241
S2.001	SIC2	15 Summer	100	+40%	30/15 Winter				31.060
S3.000	SIC1b	15 Winter	100	+40%					30.995
S4.000	SIC19	15 Winter	100	+40%	30/15 Summer				31.508
S4.001	SIC20	15 Winter	100	+40%	30/15 Summer				31.417
S3.001	SIC5	15 Winter	100	+40%	1/15 Winter				31.367
S2.002	SIC3	60 Winter	100	+40%	1/15 Summer	100/30 Summer			31.514
S1.002	S2	60 Winter	100	+40%					30.059
S5.000	SIC11	15 Winter	100	+40%	100/15 Summer				31.952
S6.000	SIC12	15 Winter	100	+40%	100/15 Summer				31.922
S5.001	SIC13	15 Winter	100	+40%	1/15 Summer	100/15 Summer			31.764
S7.000	SIC14	15 Winter	100	+40%	100/15 Summer				31.450
S8.000	SIC13b	15 Winter	100	+40%					31.200
S7.001	SIC15	15 Winter	100	+40%	1/15 Summer	100/15 Winter			31.376

©1982-2020 Innovyze

Civic Engineers

Carvers Warehouse

77 Dale Street

Manchester, M1 2HG

Date 24/03/2021 00:02

File 949-02_SW Drainage Strat...

Designed by chrisk

Checked by

Innovyze

Network 2020.1

Page 11



Summary of Critical Results by Maximum Outflow (Rank 1) for Storm



PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S5.002	SIC7	30 Winter	100	+40%	30/15 Summer	100/30 Summer		
S9.000	SIC3b	15 Winter	100	+40%				
S5.003	SIC8	60 Winter	100	+40%	1/15 Summer	100/120 Winter		
S1.003	S3	60 Winter	100	+40%	100/30 Summer			
S10.000	SRE	15 Winter	100	+40%	30/15 Summer			
S10.001	SIC18	15 Winter	100	+40%	30/15 Summer			
S11.000	SRE	15 Winter	100	+40%	30/15 Summer			
S11.001	SIC17	15 Winter	100	+40%	1/15 Summer			
S12.000	SIC9	15 Winter	100	+40%				
S13.000	SIC8b	15 Winter	100	+40%				
S12.001	SIC16	60 Winter	100	+40%	30/30 Summer			
S1.004	S4	30 Summer	100	+40%	100/15 Winter			



PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
S5.002	SIC7	31.002	1.252	1.605	1.80			13.4	FLOOD
S9.000	SIC3b	30.580	0.000	0.000	1.38			6.7	SURCHARGED*
S5.003	SIC8	30.994	1.418	0.000	1.67			8.6	FLOOD RISK
S1.003	S3	29.783	0.761	0.000	0.62			43.9	SURCHARGED
S10.000	SRE	29.340	0.370	0.000	1.31			6.9	SURCHARGED
S10.001	SIC18	29.322	0.402	0.000	0.61			3.4	SURCHARGED
S11.000	SRE	29.760	0.700	0.000	1.66			11.4	SURCHARGED
S11.001	SIC17	29.696	0.721	0.000	0.54			4.6	SURCHARGED
S12.000	SIC9	29.719	-0.026	0.000	0.90			7.9	OK
S13.000	SIC8b	29.576	0.000	0.000	1.04			4.7	SURCHARGED*
S12.001	SIC16	29.638	0.228	0.000	0.46			2.6	SURCHARGED
S1.004	S4	29.175	0.300	0.000	0.69			42.2	SURCHARGED

PN	US/MH Name	Level Exceeded
S5.002	SIC7	8
S9.000	SIC3b	
S5.003	SIC8	
S1.003	S3	
S10.000	SRE	
S10.001	SIC18	
S11.000	SRE	
S11.001	SIC17	

©1982-2020 Innovyze

Civic Engineers		Page 12																		
Carvers Warehouse 77 Dale Street Manchester, M1 2HG																				
Date 24/03/2021 00:02 File 949-02_SW Drainage Strat...	Designed by chrisk Checked by																			
Innovyze	Network 2020.1																			
<u>Summary of Critical Results by Maximum Outflow (Rank 1) for Storm</u>																				
	<table><tr><td></td><td>US/MH</td><td>Level</td></tr><tr><td>PN</td><td>Name</td><td>Exceeded</td></tr><tr><td>S12.000</td><td>SIC9</td><td></td></tr><tr><td>S13.000</td><td>SIC8b</td><td></td></tr><tr><td>S12.001</td><td>SIC16</td><td></td></tr><tr><td>S1.004</td><td>S4</td><td></td></tr></table>		US/MH	Level	PN	Name	Exceeded	S12.000	SIC9		S13.000	SIC8b		S12.001	SIC16		S1.004	S4		
	US/MH	Level																		
PN	Name	Exceeded																		
S12.000	SIC9																			
S13.000	SIC8b																			
S12.001	SIC16																			
S1.004	S4																			
©1982-2020 Innovyze																				

[illegible]



Standard Notes

1. This drawing is to be read in conjunction with all relevant Architect's and Engineer's drawings and the specification.
2. This drawing should not be scaled.
3. All dimensions are to be verified by the contractor on site.
4. All discrepancies should be reported to the C.A. prior to the commencement of the works.

© CIVIC ENGINEERS

Notes and Keys

1. Topographical survey carried out by Survey Operations in June 2018, received from Galliford Try Infrastructure Limited on 25.06.2018.
2. Existing drainage investigations carried out by General Utilities Northwest Limited in June 2018.
3. Existing drainage features shown in the drawing are based on the topographical survey (by Survey Operations) and the CCTV survey (by General Utilities Northwest Limited).

Notes and Keys

Notes and Keys

21/03/21	P01	ISSUED FOR INFORMATION	CK	CK
Date	Rev	Description	Drawn	Chk

Project	Medieval Quarter Manchester
Title	Existing Drainage Phase 1A
Scale @ A1	1:250
Date Created	18/03/21
Drawn	CK
Checked	CK



Civic Engineers

MANCHESTER
LONDON
LEEDS
GLASGOW



Carver's Warehouse, 77 Dale Street, Manchester, M3 2HG. Tel: 0161 228 6751
Riverside Wharf, 24 Mill Street, London SE1 2SL. Tel: 020 7252 2977
Tower Works, Unit G2-01, Globe Road, Leeds, LS11 5DP. Tel: 0113 2025 130
Graham Chambers, 45 West Nile St, Glasgow, G1 2PT. Tel: 0141 370 1829

www.civicingineers.com

Status

INFORMATION

Project Number	Originator	Discipline	Drawing Number	Revision
949-02	CIVIC	C	----	P01



Standard Notes

1. This drawing is to be read in conjunction with all relevant Architect's and Engineer's drawings and the specification.
2. This drawing should not be scaled.
3. All dimensions are to be verified by the contractor on site.
4. All discrepancies should be reported to the C.A. prior to the commencement of the works.

© CIVIC ENGINEERS

Notes and Keys

1. PROPOSED GENERAL ARRANGEMENT, SITE BOUNDARY ARE AS PER PLANIT-IE DRAWING 'PL1784-VW-001-23-PLANIT IE WORKING FILE', RECEIVED ON 19/11/2020.

Notes and Keys

Notes and Keys

11/12/20	P02	STAGE 4 ISSUE	LGS	CK
27/11/20	P01	STAGE 4 ISSUE	CK	CK
Date	Rev	Description	Drawn	Chk

Project MEDIEVAL QUARTER & GLADE OF LIGHT MANCHESTER				
Title PROPOSED FINISHED LEVELS AND CONTOURS				
Scale @ A1	Date Created	Drawn	Checked	Project Number
1:150	27/11/20	CFK	CFK	949-02



Civic Engineers

MANCHESTER
LONDON
LEEDS

Carver's Warehouse, 77 Dale Street, Manchester, M1 2HG. Tel: 0161 228 6757
Lloyds Wharf, 3 Mill Street, London SE1 2BD. Tel: 020 7253 2977
Tower Works, Unit G2-01, Globe Road, Leeds, LS11 5GB. Tel: 0113 2025 130

www.civicingengineers.com

INFORMATION				
Status	Project Number	Originator	Discipline	Drawing Number
	949-02	CIVIC	C	GA-009
				Revision
				P02

Chris Kendrick

From: GMMC Info Requests <InfoRequests.GMMC@environment-agency.gov.uk>
Sent: 10 November 2020 09:50
To: Chris Kendrick
Subject: GE12845CC Response from the Environment Agency

Dear Chris,

Please see our officer's comments below:

At a planning level matters relation to surface-water drainage are handled primarily by the Lead Local Flood Authority (LLFA). I would advise that the enquirer contacts the LLFA in the first instance as we do not tend to formally comment on surface water drainage proposals unless the development is proposing to utilise infiltration into potentially contaminated ground.

From an environmental permitting aspect, any works within the vicinity of a 'main river' (River Irwell may require a Flood Risk Activity Permit (FRAP) and any existing permit for the outfall noted may need to be varied or a new permit obtained. I'd recommend referring the enquirer to the following pages:

- <https://www.gov.uk/guidance/check-if-you-need-an-environmental-permit>
- <https://www.gov.uk/guidance/flood-risk-activities-environmental-permits>

Kind Regards

Claire

Claire Cooke
Customer and Engagement Officer
Greater Manchester, Merseyside and Cheshire
External: 020 302 50048
Email: inforequests.gmmc@environment-agency.gov.uk



From: Chris Kendrick [<mailto:chris.kendrick@civicengineers.com>]
Sent: 06 November 2020 07:30
To: GMMC Info Requests <InfoRequests.GMMC@environment-agency.gov.uk>
Subject: Medieval Quarter Glade of Light Public Realm, Manchester

Dear Sir / Madam,

We would like to discuss proposals for the surface water discharge for a public realm development close to Manchester Cathedral. Please see attached site location plan and proposed drainage strategy for the development.

The existing development area comprises existing highway and pedestrianised areas with the majority of the site being impermeable hardstanding with some existing raised lawns containing several trees. The existing highway is known as Victoria Street which has been under a prohibition of traffic order for a number of years and has been used as a pedestrian route from Victoria Train Station into the city centre. The new public realm development will introduce more soft landscaping, which will be utilised for SuDS features located to capture surface water run-off in key areas.

The SuDS features will be in the form of raingardens to provide treatment for surface water run-off, reduction in peak flows through lower time of concentration and storage within the sub-base below. The raingardens also encourage a nominal amount of infiltration into soils which can be taken up by plants which add to the biodiversity of the area. Beneath raingardens will sit a granular sub-base and network of perforated pipes in order to provide positive drainage (due to impracticality of relying on infiltration) towards a main piped system and eventual outfall to the River Irwell.

The proposed surface water discharge will utilise an existing 300dia. surface water outfall into the River Irwell. This provides a number of benefits such as:

- It is an existing outfall so minimal work is required near to the River Irwell retaining wall
- It is conveniently located at the lowest part of the site
- Existing highway gullies connect to this chamber
- It means surface water can be taken out of the public sewer for this area

I would welcome the opportunity to discuss these proposals with you but please get in touch if you need anything further in the meantime.


Kind regards,

Chris Kendrick

Senior Civil Engineer

Tel: 0161 228 6757

Mobile: 07921 299371



Manchester / London / Leeds / Glasgow



Please do not print this email unless it is necessary. Every unprinted email helps the environment.

Civic Engineers is a trading name of Civic Engineers Limited (registered number 06824088) which is a limited company registered in England and Wales. Registered address Carver's Warehouse, 77 Dale Street, Manchester, M1 2HG. For email disclaimer, please click [here](#)

Information in this message may be confidential and may be legally privileged. If you have received this message by mistake, please notify the sender immediately, delete it and do not copy it to anyone else. We have checked this email and its attachments for viruses. But you should still check any attachment before opening it. We may have to make this message and any reply to it public if asked to under the Freedom of Information Act, Data Protection Act or for litigation. Email messages and attachments sent to or from any Environment Agency address may also be accessed by someone other than the sender or recipient, for business purposes.

Chris Kendrick

From: Chris Kendrick
Sent: 25 February 2021 10:06
To: Rob Byrne
Cc: Adam Liu (Galliford Try)
Subject: RE: Medieval Quarter - Existing Outfall to R.Irwell

Hi Rob,

Sorry to chase again but we're starting on site towards the end of March and we need to confirm use of the existing highway outfall. The confirmation would also form part of planning conditions we need to close out pre-commencement.

If you could get back to me as soon as possible that would be much appreciated.

Kind regards,

From: Chris Kendrick
Sent: 10 February 2021 14:28
To: Rob Byrne <r.byrne2@manchester.gov.uk>
Subject: RE: Medieval Quarter - Existing Outfall to R.Irwell

Hi Rob,

Further to our conversation and the email chain below could you confirm that MCC highways own the existing 300dia. outfall into the River Irwell. I attach a previous email sent to Nick with details of the existing outfall.

As well as confirming ownership could you please confirm agreement, or how to obtain agreement, for re-using this outfall for the proposed surface water drainage. I also attach the current drainage strategy for the development showing re-use of the existing outfall.

Kind regards,

Chris

From: Rob Byrne <r.byrne2@manchester.gov.uk>
Sent: 16 October 2020 07:23
To: Nick O'Keefe <nick.okeefe@manchester.gov.uk>
Cc: Chris Kendrick <chris.kendrick@civicingineers.com>; Paul Gee <p.gee@manchester.gov.uk>; Victor Nwegbu <v.nwegbu@manchester.gov.uk>; Robert Ashcroft <r.ashcroft@manchester.gov.uk>
Subject: Re: Medieval Quarter - Existing Outfall to R.Irwell

Hi Nick,

Can you please contact Chris to discuss his proposal.

Regards,

Rob Byrne

Contract Manager
Highway Services
Neighbourhoods Directorate
Block C
Hooper Street
Manchester
M12 6LA

Mob: 07789 984162

Email: r.byrne2@manchester.gov.uk

Environment on call email: contact@manchester.gov.uk

Web: www.manchester.gov.uk

POSTAL ADDRESS: Highways Service, Growth and Neighbourhoods Directorate, Manchester City Council, PO Box 532, Town Hall, Manchester, M60 2LA

On Thu, 15 Oct 2020 at 15:30, Victor Nwegbu <v.nwegbu@manchester.gov.uk> wrote:

Hello Rob,

Can you help with this enquiry from Chris Kendrick?

Regards (& keep safe, well and fit!)

Victor

Victor K. NWEGBU (Ph.D.)

Assistant Engineer (Bridges)

Postal Address:

HIGHWAYS, TRANSPORT & ENGINEERING
Growth & Neighbourhoods
Manchester City Council
PO Box 532 Town Hall
Manchester
M60 2LA

Office Location:

*5th Floor *(5-038)* Bridgewater House
58-60 Whitworth Street
Manchester
M1 6LT

Telephone: 0161 219 6668
Internal: 801 36668
Mobile : 07742 227 406
E-mail: v.nwegbu@manchester.gov.uk
Website: www.manchester.gov.uk

*In light of the **COVID-19 situation** I am currently working from home - please bear with me in responding to your email*

----- Forwarded message -----

From: **Victor Nwegbu** <v.nwegbu@manchester.gov.uk>
Date: Thu, 15 Oct 2020 at 09:25
Subject: Re: Medieval Quarter - Existing Outfall to R.Irwell
To: Chris Kendrick <chris.kendrick@civicengineers.com>
Cc: p.gee@manchester.gov.uk <p.gee@manchester.gov.uk>, Adam Liu (Galliford Try) <Adam.Liu@gallifordtry.co.uk>

Hello Chris,

I can confirm that MCC Highways owns the retaining wall structure (Victoria Street Retaining Wall) - see attached. However, with respect to the drainage outfall and any permissions to utilise it is outside my scope.

Hi Paul, are you able to direct the inquirer to the right person?

Regards (& keep safe, well and fit!)

Victor

Victor K. NWEGBU (Ph.D.)
Assistant Engineer (Bridges)

Postal Address:

HIGHWAYS, TRANSPORT & ENGINEERING
Growth & Neighbourhoods
Manchester City Council
PO Box 532 Town Hall
Manchester
M60 2LA

Office Location:

*5th Floor *(5-038)* Bridgewater House
58-60 Whitworth Street
Manchester
M1 6LT

Telephone: 0161 219 6668
Internal: 801 36668

Mobile : 07742 227 406

E-mail: v.nwegbu@manchester.gov.uk

Website: www.manchester.gov.uk

*In light of the **COVID-19 situation** I am currently working from home - please bear with me in responding to your email*

On Wed, 14 Oct 2020 at 17:11, Chris Kendrick <chris.kendrick@civicengineers.com> wrote:

Hi Victor,

Thank you for taking my call earlier.

Further to my call see attached mark up of where we identified a 300mm diameter surface water outfall from Victoria Street, through the retaining wall to the east bank of the River Irwell. The outfall is located under the Chapel Street bridge (also see attached photo).

The drainage survey proved that the existing highway gully, noted on the mark up, connects directly into the 300dia. pipe. No other gullies or drains could be proven to this outfall at the time of the survey.

Therefore, we would like to know if you have any records to suggest that this comes under MCC highways ownership? We would ultimately like to determine who we need to obtain permission from in order to utilise this as an outfall for the Medieval Quarter development.

Any assistance you could offer would be greatly appreciated.

Kind regards,

Chris Kendrick

07921 299 371

Chris Kendrick

Senior Civil Engineer

Tel: 0161 228 6757



Manchester / London / Leeds / Glasgow



Please do not print this email unless it is necessary. Every unprinted email helps the environment.

Civic Engineers is a trading name of Civic Engineers Limited (registered number 06824088) which is a limited company registered in England and Wales. Registered address Carver's Warehouse, 77 Dale Street, Manchester, M1 2HG. For email disclaimer, please click [here](#)

This email and any files transmitted with it are confidential and intended solely for the use of the individual or entity to whom they are addressed. If you have received this email in error please notify the system manager. The full text of the Council's email disclaimer is available at www.manchester.gov.uk/emaildisclaimer.

Your personal data is very important to us. Please refer to our privacy notice at www.manchester.gov.uk/privacy for further information.

This footnote also confirms that this email message has been swept for the presence of computer viruses.

Chris Kendrick

From: Chris Kendrick
Sent: 18 March 2021 22:34
To: Flood Risk Management
Cc: Adam Liu (Galliford Try)
Subject: RE: Medieval Quarter - Surface Water Discharge to Existing Highways Outfall
Attachments: GE12845CC Response from the Environment Agency; 949-02-CIVIC-C-XX-EX-001_P01- Existing SW Drainage.pdf

Hi Laura,

Thanks for the follow up. As requested, I also attach the Environment Agency's response referring us to the LLFA.

In addition, the existing highway is drained by traditional highway gullies. The attached plan shows the existing drainage including the existing 300dia. outfall into the Irwell. Currently there are several gullies which connect to the public sewer and the gullies at the lower end of the catchment discharge to the existing outfall. The proposal involves disconnecting the gullies from the public sewer and instead utilising the existing 300dia. outfall as the means of surface water disposal for the full catchment. I also include a link to the CCTV drainage survey of the existing outfall here showing the survey of the nearest gully outlet opening up into the 300 outfall pipe:

<https://we.tl/t-p2w6FmRUNG>

By removing surface water from the combined sewer we are complying with step 2 of the hierarchy of surface water disposal. Due to the sensitive nature of the site with existing utilities and underground catacombs associated with the Cathedral, surface water disposal by infiltration is not feasible.

The existing area within the Phase 1A site is 3213m²
The existing area within the Phase 1B site is 3043m²

Due to the gradient of Victoria Street, Phase 1B will eventually drain into the new surface water system provided by Phase 1A, therefore the total brownfield run-off from Phase 1A and 1B has been calculated. The existing 1:1 year run-off is 86.5 l/s which when offering a 50% betterment in accordance with Manchester SFRA, gives a discharge rate of 43.25l/s.

We have made several enquiries to various members of the MCC highways team to determine ownership of the existing outfall. Unfortunately, we have not received a formal response confirming MCC ownership / responsibility for this outfall and acceptance of the discharge rate which we require to close out a planning condition. Therefore, is this something you are able to confirm?

I am happy to discuss further should you wish, I am available most of tomorrow for a telephone call or teams meeting should you wish.

Kind regards,

From: Flood Risk Management <floodriskmanagement@manchester.gov.uk>
Sent: 15 March 2021 16:45
To: Chris Kendrick <chris.kendrick@civicingineers.com>
Subject: RE: Medieval Quarter - Surface Water Discharge to Existing Highways Outfall

Good Afternoon Chris,

I hope you are well,

I have been advised that some discussions were recently held with Highways colleagues regarding the drainage strategy. We remain available to hold additional discussions with you, with regards to our below 2 queries on confirming what the existing network is and the EA consultation for main river outfall.

Kind Regards,
Laura

From: Flood Risk Management <floodriskmanagement@manchester.gov.uk>
Sent: 09 March 2021 11:53
To: Chris Kendrick <chris.kendrick@civicengineers.com>
Subject: RE: Medieval Quarter - Surface Water Discharge to Existing Highways Outfall

Good Morning Chris,

Many thanks for your email regarding planning ref: 128045/VO/2020.

To begin our discussion on proposed rates, could you please discuss how existing rates have been calculated, what existing network the site was determined to drain to, & confirm that this existing network has been modelled in your attached calcs. At the point of formal FRA submission for this App, the existing drainage regime was unclear. We subsequently received the below text from the applicant via email 12 Nov 2020.

"The original CCTV survey was inconclusive and could not determine connections to either the public sewer or directly into the River Irwell. Therefore a further investigation was undertaken on 12th October which proved a highway gully connection to an existing 300 diameter piped outfall to the Irwell. This outfall is at a convenient location for the Phase 1A (and 1C) development as it is at a low point of the site. The only challenge with this outfall is that the invert level is approximately 1m below the nearest ground level (estimated based on observation). If the drainage strategy were of a traditional nature, i.e.: gullies, channels and pipes then connection to this would be a lot simpler to achieve. The difficulty arises with the depth of raingarden sub-bases which are used for storage. A strategy has been developed which introduces a shallower detail to raingarden nearest the outfall in order to utilise the existing Irwell outfall."

As per our comments, as the EA is risk management authority for main rivers, any works within or adjacent to the river that would affect it would require consent from Environment Agency. You have stated that you have approached the EA; and they have no objection or stipulations, and have directed you back to the LLFA. An email of acceptance of proposed flows and/or new connection will suffice to discharge this part of our comments.

We look forward to hearing further from you,

Kind Regards,
Laura

From: Chris Kendrick <chris.kendrick@civicengineers.com>
Sent: 25 February 2021 09:59
To: Flood Risk Management <floodriskmanagement@manchester.gov.uk>
Subject: Medieval Quarter - Surface Water Discharge to Existing Highways Outfall

Dear Sir / Madam,

We have contacted the Environment Agency in relation to discharge of surface water to the River Irwell from a new public realm development. They have advised that Manchester as Lead Local Flood Authority would be responsible for approving surface water in this instance.

Therefore, we would like to obtain the necessary approval for the discharge of surface water for the Phase 1A of the Medieval Quarter public realm development (planning ref: 128045/VO/2020) close to Manchester Cathedral. Please see attached site location plan and proposed drainage strategy for the development.

The existing development area comprises existing highway and pedestrianised areas with the majority of the site being impermeable hardstanding with some existing raised lawns containing several trees. The existing highway is known as Victoria Street which has been under a prohibition of traffic order for a number of years and has been used as a pedestrian route from Victoria Train Station into the city centre. The new public realm development will introduce more soft landscaping, which will be utilised for SuDS features located to capture surface water run-off in key areas.

The SuDS features will be in the form of raingardens to provide treatment for surface water run-off, reduction in peak flows through lower time of concentration and storage within the sub-base below. The raingardens also encourage a nominal amount of infiltration into soils and planting beds. Beneath raingardens will sit a granular sub-base and network of perforated pipes in order to provide positive drainage (due to impracticality of relying on infiltration) towards a main piped system and eventual outfall to the River Irwell.

The proposed surface water discharge will utilise an existing 300dia. surface water outfall into the River Irwell. This provides a number of benefits such as:

- It is an existing outfall so minimal work is required near to the River Irwell retaining wall
- It is conveniently located at the lowest part of the site
- Existing highway gullies connect to this chamber
- It means surface water can be taken out of the public sewer for this area

Phase 1A will be the first section to be installed, with Phase 1C and 1B coming forward at a later date. We have calculated the existing run-off from the phase 1A and 1C areas as 84.5 l/s (based on a 1:1 year 50mm/hr rainfall intensity), which when applying a 50% betterment gives a maximum discharge into the existing outfall of 42.25l/s.

I would welcome the opportunity to discuss these proposals with you but please get in touch if you need anything further in the meantime.

Kind regards,

Chris Kendrick

Senior Civil Engineer

Tel: 0161 228 6757

Mobile: 07921 299371



Manchester / London / Leeds / Glasgow



Please do not print this email unless it is necessary. Every unprinted email helps the environment.

Civic Engineers is a trading name of Civic Engineers Limited (registered number 06824088) which is a limited company registered in England and Wales. Registered address Carver's Warehouse, 77 Dale Street, Manchester, M1 2HG. For email disclaimer, please click [here](#)

This email and any files transmitted with it are confidential and intended solely for the use of the individual or entity to whom they are addressed.

If you have received this email in error, please notify the system manager.

The full text of the Council's email disclaimer is available at www.manchester.gov.uk/emaildisclaimer.

Your personal data is very important to us. Please refer to our privacy notice at www.manchester.gov.uk/privacy for further information.

This footnote also confirms that this email message has been swept for the presence of computer viruses.

Technical Specification


Control Point	Head (m)	Flow (l/s)
Primary Design	0.960	42.300
Flush-Flo™	0.421	42.299
Kick-Flo®	0.750	37.562
Mean Flow		34.111

Hydro-Brake® Optimum Flow Control including:

- 3 mm grade 304L stainless steel
- Integral stainless steel pivoting by-pass door allowing clear line of sight through to outlet, c/w stainless steel operating rope
- Beed blasted finish to maximise corrosion resistance
- Stainless steel fixings
- Rubber gasket to seal outlet



hydro-int.com/patents



IMPORTANT:

○ LIMIT OF HYDRO INTERNATIONAL SUPPLY
 THE DEVICE WILL BE HANDED TO SUIT SITE CONDITIONS
 FOR SITE SPECIFIC DETAILS AND MINIMUM CHAMBER SIZE REFER TO HYDRO INTERNATIONAL
 ALL CIVIL AND INSTALLATION WORK BY OTHERS
 * WHERE SUPPLIED
 HYDRO-BRAKE® FLOW CONTROL & HYDRO-BRAKE® OPTIMUM FLOW CONTROL ARE REGISTERED TRADEMARKS FOR FLOW
 CONTROLS DESIGNED AND MANUFACTURED EXCLUSIVELY BY HYDRO INTERNATIONAL

THIS DESIGN LAYOUT IS FOR ILLUSTRATIVE PURPOSES ONLY. NOT TO SCALE.

**DESIGN
ADVICE**



The head/flow characteristics of this SHE-0275-4230-0960-4230 Hydro-Brake® Optimum Flow Control are unique. Dynamic hydraulic modelling evaluates the full head/flow characteristic curve.
The use of any other flow control will invalidate any design based on this data and could constitute a flood risk.

**Hydro
International**

DATE 3/16/2021 7:03 AM

SITE

DESIGNER Sharon King

REF

SHE-0275-4230-0960-4230

Hydro-Brake® Optimum