

Site Location:
Start Date:
Expected Job Duration:
Method Statement Completed by:

Lighting Fixtures (Installation)

All electrical works to be carried out by qualified electricians. The electrical supply to all cables, terminal boxes etc will be isolated. The foreperson will either; remove the fuse from the board or operate the trip switch to isolate the relevant supply. The circuit will then be tested to ensure that electricity supply has been isolated. Fuse to be kept by the foreperson until it is required and a notice will be fitted, stating danger men at work do not install new fuse. The distribution board supplying the area of work will then be locked off to ensure no inadvertent re-energizing of the supply. Mount terminal boxes to rafters/trusses etc and fix to terminal boxes. Run supply cables through conduit and terminate to terminal boxes. Fix a length of flexible conduit to the terminal connector on the light fitting and run cables through Lift the light fitting and twist through the appropriate ceiling space. Remove an adjacent panel to allow access to the terminal boxes and connect cable and flexible conduit to the light fitting. Test all fittings as per local requirements.
