

Site Location:
Start Date:
Expected Job Duration:
Method Statement Completed by:

Drylining Partition Fixing and Erection

Put on PPE.

Ensure the area to be worked and exit points are clear of obstruction and that safe access and egress is maintained.

Mark out partition locations and setting of walls as per construction drawing on the floor area to ensure correct dimensions and room sizes work out and match as required and shown on drawings.

Mark out door aperture locations when setting out.

Cut timber/metal sole/head-plates to size and install to substrate using proprietary fixings, double check plates are plumb to accept stud work using a laser level, spirit level or plumb bob line.

Size and cut timber/metal studwork between the sole and head-plates using proprietary fixings allowing for door aperture and noggins to accept framework and plasterboard with 600 mm maximum center 's.

Double check walls and ensure stud frame work is true and plumb, plasterboard one side only.

Allow for and ensure other trades i.e. electricians, plumbers have completed any 1st fix work which may be inside the partition work while open access to the studs is available.

When sawing or sanding plasterboards, use local exhaust system to control dust or wear a half face mask to EN149 class FFP 2s if dust cannot be controlled.

Install mineral fibre insulation prior to fitting plasterboard to other side.

Remove all debris to designated waste disposal area.

Do not leave tools and equipment unattended at any time.

Ensure area is left safe at end of each working shift leaving no trip or fall hazards.