

Site Location:
Start Date:
Expected Job Duration:
Method Statement Completed by:

Concreting

The concrete will be delivered premixed from Tarmac or Lafarge via cement mixer or boom truck, and poured against the face of the excavation.
--

The concrete must be a minimum strength of 30 N/m², once poured the concrete will be leveled with the use of a vibrating poker; the site foreman is responsible for ensuring the correct distribution of the concrete into the shuttering and that the 20mm reinforcing rod is kept in position.
--