

Site Location:
Start Date:
Expected Job Duration:
Method Statement Completed by:

Dismantling of stud partitions

Put on your PPE.
Ensure the area to be worked and exit points are clear of obstruction and that safe access and egress is maintained.
Remove all associated finishing fixings from partitions inclusive of skirting boards, architraves, doors and frames.
Ensure any associated electrics or plumbing pipe work are removed and made safe.
Make a manual hole cut into the plasterboard from metal or timber studwork in-situ.
Manual handballing of plasterboard to be used to lower onto floor level area previously cleared to accept debris.
Following plasterboard removal, studwork to be cleared methodically via unfixing any screws or proprietary fixings and lowering to floor level for disposal of skip.
Use a designated route to man handle any debris to waste skip / vehicle.