

Waste Management Plan

Kingston Lodge, Kingston Rd, Didsbury, Manchester.

Towerhouse Systems Ltd

The main objective of waste management on a construction site is to minimise the waste generated as part of the construction proceeds, hence reducing the need for the storage and off-site transportation of waste materials.

In order to do this, we will at all time endeavour to order materials at the most accurate sizes and quantities that are required. Where this is not possible, and materials are cut to size on site we will where possible re-use the materials or send them for recycling.

All spoil from the development will be removed using a registered waste transfer Company who will provide Waste transfer notes, along with a copy of their Duty of care policy.

A copy of the site investigation report will be provided to the Company in advance of the collection.

All General waste will be held in a builders skip within the boundary of the site as indicated on the plan at appendix 1 of the Construction Management plan. The skip will be secured with Harras fencing when not being loaded. The Waste Management company that collects the skip and its contents will ensure that the waste is covered before leaving the site on their vehicle and a Waste Transfer note is provided.