



Existing windows with timber boarding - boarding to be carefully removed and window to be repaired in accordance with **item 11** in the external repair schedule.



Areas of vegetation growth on elevation- existing vegetation to be carefully removed and hacked out from joints with hand tools only. localised area to be sprayed with weedkiller. Jointing to be repointed in accordance with **item 3** in the external repair schedule.



Areas of repointing
Mortar to be carefully hacked out and replaced where missing as per NBS C41/810-860 and **item 3** in the external repair schedule
L Indicates window decals to be retained.

Working at height on roof, within lightwells and when installing new lifts.
Risks:
- falls from height;

Generally
non-original and redundant fittings to be carefully removed by hand

Stone and brick to be cleaned with the Doff system in accordance with **items 12 and 13** of the external repairs schedule (NBS clause M40)

① numbers on elevations refer to works on the external repairs schedule

COPYRIGHT OF ATELIER MB LTD
DO NOT SCALE FROM THIS DRAWING
DIMENSIONS TO BE CHECKED ON SITE

All dimensions to be checked on site prior to any commencing work.

KEY

- Existing
- Proposed
- Downstand beams
- Existing to be removed
- Drawing reference 1/312 (TBC)

CDM Hazard Identification. Refer to C(812) CDM Risk Assessment and C(813) CDM ID Sheet for details.

Note: Drawing to be read in conjunction with 1665 C(423), 1665 C(802) NBS the External works repair schedule and the window repair schedule.

B	Window references added.	RD	AB
NY1			
A	Drawing updated following 19/11/2020 scaffold survey	AB	AB
Rev	Note	DRN	CHK

8-16 Newton Street

Dale Street
Proposed Strip Out

scheme	1665
drwg no.	C(231)
revision	B

scale	1:100 @ A3
date first drawn	Jan 19
drawn	VC

SK sketch E existing P proposed T tender C construction FI final issue

www.ateliermb.co.uk
t 0161 236 0051
e architect@ateliermb.co.uk

