



NOTES

The proposed works to the windows of these properties includes for the removal of all timber framed single glazed windows and replacement with double glazed UPVC windows. All windows would have their style replicated like for like which would include for all arched windows, casement windows with varied styles of openers and fan light windows above doors.

The proposed works to the doors of these properties includes for the removal of existing security doors with timber finishes to external entrances to the properties and replacement with new composite doors. The style of the proposed doors would be similar to the existing with a timber finish and colour to match the property.

Notes:

This drawing and design are copyright and may not be reproduced without the written consent of the JYM Partnership.

All dimensions are to be checked and verified on site prior to commencement of any works, and/or preparation of any shop drawings. Sizes of and dimensions to any structural elements are indicative only. See structural engineers drawings for actual sizes / dimensions. Sizes of and dimensions to any service elements are indicative only. See service engineers drawings for actual sizes and dimensions.

This drawing to be read in conjunction with all relevant Architect's drawings, specifications and/or bills of quantities as issued with other Consultants' information. If in doubt please ask.

DO NOT SCALE FROM THIS DRAWING.

Rev	Date	Revision
JYM partnership Oak House 28 Sceptre Way Bamber Bridge Preston PR5 6AW Tel : 01772 323666 Fax : 01772 338611 Email : jym@jympartnership.co.uk www.jympartnership.co.uk		
project: Hadfield Close Window & Door Replacement		
client: Realty Management		
drawing title: Proposed Works Notes		
scale: NTS		
drawn: LM		checked: CS
date: SEPT 2020		
project no. 1904.13	drg. no. 02	rev. -