PROPOSED MANHOLES											
MH REF	CL (mAOD)	IL (mAOD)	DEPTH TO SOFFIT (m)	DS PIPE DIA (mm)	MH DIA (mm)	MH TYPE	COVER SIZE (mm)	COVER CLASS	COMMENTS	EASTING	NORTHING
FW1	37.40	36.38	0.870	150	450	PPIC	450X450	B125	SINGLE SEALED RECESSED COVER	384296.09	397217.14
FW2	37.32	36.40	0.820	100	450	PPIC	450X450	D400	SINGLE SEALED RECESSED COVER	384308.05	397223.53
FW3	37.30	36.47	0.730	100	450	PPIC	450X450	D400	SINGLE SEALED RECESSED COVER	384335.66	397230.16
FW4	37.38	36.36	0.920	100	450	PPIC	450X450	D400	SINGLE SEALED RECESSED COVER	384345.32	397228.57
CW1	37.40	36.40	0.850	150	450	PPIC	450X450	A15	DOUBLE SEALED RECESSED COVER, EXISTING PIPE LEVEL UNKNOWN, ESTIMATED LEVEL SHOWN	384311.79	397201.36
CW2	37.40	35.76	1.490	150	450	PPIC	450X450	A15	DOUBLE SEALED RECESSED COVER, RESTRICTED ACCESS 350DIA	384335.31	397213.72
CW3	37.40	35.67	1.580	150	450	PPIC	450X450	A15	DOUBLE SEALED RECESSED COVER, RESTRICTED ACCESS 350DIA	384337.97	397213.02
CW4	37.40	36.78	0.470	150	450	PPIC	450X450	A15	DOUBLE SEALED RECESSED COVER	384317.88	397219.14
CW5	37.36	36.16	1.050	150	1050	TYPE 2 PCC	750X675 MIN	D400	DOUBLE SEALED RECESSED COVER	384299.45	397223.11
EX238	37.07	36.06	0.860	150	1800	TYPE 2 PCC	750X675 MIN	D400	DOUBLE SEALED RECESSED COVER	384313.62	397228.12
SW01	37.37	36.56	0.660	150	1050	TYPE 2 PCC	750X675 MIN	D400	SINGLE SEALED RECESSED COVER	384349.79	397220.21

EXISTING MANHOLES
IF IT IS FOUND THAT BENCHING CANNOT BE CONSTRUCTED SATISFACTORILY WITHIN MANHOLES TO BE RE-USED, THEN THESE MANHOLES WILL REQUIRE RECONSTRUCTING.

LANDSCAPE ARCHITECT TO CONFIRM REQUIREMENTS FOR RECESSED COVERS.

EXISTING EXTERNAL MANHOLE COVERS TO BE ADJUSTED TO MATCH PROPOSED LEVELS

INTERNAL MANHOLE COVERS MAY REQUIRE REPLACEMENT, NEW MANHOLE COVERS HAVE BEEN INSTALLED AFTER CCTV SURVEY, SIZES TO BE CONFIRMED

GENERAL NOTES:

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND ENGINEERS DRAWINGS AND SPECIFICATIONS.
2. DO NOT SCALE THIS DRAWING. ANY AMBIGUITIES, OMISSIONS AND ERRORS ON DRAWINGS SHALL BE BROUGHT TO THE ENGINEERS ATTENTION IMMEDIATELY. ALL DIMENSIONS MUST BE CHECKED / VERIFIED ON SITE.
3. ALL DIMENSIONS ARE IN METRES UNLESS NOTED OTHERWISE.
4. COVER LEVELS, GULLY POSITIONS, AND BUILDING LOCATION ARE APPROXIMATE AND SHALL BE CONFIRMED BY ARCHITECT/LANDSCAPE ARCHITECT. CONTRACTOR TO ALLOW FOR ADJUSTMENT TO SUIT AGREED POSITIONS AND FINISHED LEVELS, AND CONFIRM ALL COVER LEVELS ON SITE.
5. ALL PROPRIETARY PRODUCT TO BE INSTALLED IN STRICT ACCORDANCE WITH THE MANUFACTURERS REQUIREMENTS, INSTRUCTIONS AND RECOMMENDATIONS.
6. ALL INTERNAL COVERS TO HAVE MECHANICALLY JOINTED CORNERS AND DOUBLE SEALED WITH RECESSED TRAY TO ALLOW FOR FINISHES.
7. ALL MANHOLE COVERS IN BLOCK/SLAB AND EXTERNAL PAVING AREAS TO HAVE RECESSED COVERS OF THE APPROPRIATE GRADE TO ACCEPT ARCHITECT'S PAVING PROPOSAL. TBC BY LANDSCAPE ARCHITECT
8. COVER LEVELS BASED ON LANDSCAPE GENERAL ARRANGEMENTS P3000415-BDP-00(9-)L201 REV P1
9. FOR DRAINAGE LAYOUT & FULL NOTES REFER TO DWG 071857-CUR-00-XX-DR-C-92500

Rev:	Description:	Date:	By:	Chkd:
C03	SW01 COORDINATES UPDATED	18.05.20	MW	MW
C02	MANHOLE NAME CHANGED TO FW1	01.05.20	MW	MW
C01	STAGE 5	30.04.20	MW	MW

curtins
Merchant Exchange, 17-19 Whitworth Street West, Manchester, M1 5WG
0161 236 2394
manchester@curtins.com
www.curtins.com
Civils & Structures • Transport Planning • Environmental • Infrastructure • Geotechnical • Conservation & Heritage • Principal Designer
Birmingham • Bristol • Cambridge • Cardiff • Douglas • Dublin • Edinburgh • Glasgow • Kendal • Leeds • Liverpool • London • Manchester • Nottingham

Status: STAGE 5

Project: MMU INSTITUTE FOR SPORT

Drg Title: MANHOLE SCHEDULE

Size:	Date:	Drawn By:	Designed By:	Checked By:
A2	30.04.20	MW	MW	MW
Scale: N/A				

Project No:	Originator:	Volume:	Level:	Type:	Role:	Category / Number:	Rev:
1016B	CUR	00	XX	DR	C	92510	C03

\\mafs02\Projects\071001 - 072000\071857-MMU Accommodation for Growth\04-Production\4A-Models-Drawings\CIVIL\92\