

**Manchester Central
Petersfield
Manchester
M2 3GX**

For the Attention of: Tom Gowland - Venue and Facilities Project Manager

Reference: 147843 – Manchester Central – Painting to the Front and Rear Gables

Date: 23/12/2019

Taziker acknowledges and thanks you for this valued enquiry and takes pleasure in submitting the following quotation in line with your email request to paint the front and rear gables at Manchester Central.

Specification/ Methodology Basis

Taziker has based our quotation on option 3 of the technical report dated 13/01/15 – REV 3. For indicative purposes please see the below outline methodology/sequencing: -

- Contract award.
- Prepare and submit the following documents for your approval: -
 - I. Risk assessments and Method Statements (RAMS).
 - II. Scaffold Design.
- Procurement of materials.
- Mobilise to Site i.e. install combi cabin, delivery of scaffolding and materials etc.
- Erect scaffolding and encapsulation (monoflex sheeting only). This will be carried out by our internal scaffold company, Network Scaffold.
- Painters to mobilise to site upon completion of scaffolding erection.
- High pressure jet washing to all surfaces to remove any existing contaminants i.e. oils, salts, grease etc. Please note that TI intend to tie into Manchester Centrals water supply free of charge (FOC).
- Prepare the steel work via a combination of: -
 - I. Mechanical St3, needle gun and grinders, up to 20% of the surface area.
 - II. General abrasion, sandpaper, 80% of the remaining surface area.
- TI has allowed to apply the following paint system as nominated by International Paints: -
 - I. Interseal 670 HS @ 100µm DFT.
 - II. Interseal 670 HS @100µm DFT.
 - III. Interthane 990 @ 50µm DFT.
 - IV. Please see the attached data sheets.
- Wash down of gable windows.
- Disposal of monoflex sheeting
- Dismantle of scaffolding.
- Demobilise from site leaving a clean and tidy area.