Create It Studios
Architecture | Planning | Visualisation

8 Withington Road

September 2019

Material Schedule: A1163-Z100-A-01

Rev	Date	Reason For Issue	A1163-Z100-A-01 MATERIAL SCHEDULE
-	18 September 2019	INITIAL ISSUE	

MATERIAL	DESCRIPTION	LOCATION	COLOUR	TYPE	PRODUCT SAMPLE IMAGE	NOTES
EXTERNAL FINISHES						
BRICKWORK	Reuse Bricks from Existing Shed	Extention and Outbuilding	RED	RED		TO MATCH EXISTING BRICKWORK To be constructed in accordance to manufacturers
WINDOW & DOORS	New windows from treated softwood with hardwood sills. Timber sashes and box frames to be exact copy of the original	New Window to Existing Building	WHITE	SASH TIMBER		TO MATCH EXISTING COLOUR AND STYLE OF WINDOWS/DOOR To be constructed in accordance to manufacturers requirements
WINDOW & DOORS	Grey Aluminium Framed Window and Door to Extension	New Window to Existing Building	DARK GREY	ALUMINIUM		To be constructed in accordance to manufacturers requirementshttps://www.roofglaze.co.uk/products/bifold-doors/?gclid=EAIaIQobChMIy8H61tDa5AIV2YjVCh250Q83EAQYByABEgLbdfD_BwE

8 Withington Road

September 2019

Material Schedule: A1163-Z100-A-01

Rev	Date	Reason For Issue	A1163-Z100-A-01 MATERIAL SCHEDULE
-	18 September 2019	INITIAL ISSUE	

MATERIAL	DESCRIPTION	LOCATION	COLOUR	TYPE	PRODUCT SAMPLE IMAGE	NOTES
RAINWATER GOODS	PFC Rainwater aluminium & cast iron gutter Black cast iron rainwater RWP:square section to match existing Soil Pipe: round section Gutter: half round section gutters	Roof facia / external wall	BLACK	CAST IRON		TO MATCH EXISTING To be constructed in accordance to manufacturers requirements http://www.pfcrainwater.com/