Supplier Name		**Customer Name**	
Quote Date		**Your Ref**	Kennedy Street Manchester
Quote Reference		**Site Address**	Kennedy Street Manchester
Reactive/PPM		**Contact**	

Quote Detail

Item 1

Engineers to attend site and install 3No double doors to the building line of the building opening in. Remove the existing door leaves to allow full clearance. Specification below 2500mmx 3800mm double doors with louvers and louvered fixed over panel. Test the operation and leave in good working order.

1- Louvred Over Panel 2490 X 1550 MM
1- Double Louvered doors 2490mm x 2240mm
1- 96mm Industrial Door Threshold - 3000mm length
1- Briton 5510 Cylinder Deadlock
1- 3* High Security 70mm (35/35) Euro Cylinder -
KA 2- Briton 5510 Cylinder Deadlock
2- 3* High Security 70mm (35/35) Euro Cylinder -
KA 1- 19mm dia D Pull Handle - 300mm c/c / SSS
1- 9206 - Slimline Extreme Heavy Duty Door Closer -
E 4- 762 x 762mm - Louvre Panel
4- Insect Mesh 762 X 762 MM
2- 450mm Monkey tail bolts

Item 2

Engineers to attend site and replace the single fire exit door with a new equal double doorset fixed to the building line. Test the operation and leave in good working order.

1- Equal Double fire exit door
1- 96mm Industrial Door Threshold - 1390mm
length 1- Briton 378 Single Point Panic Latch - Silver
1- Briton 376 Two Point Panic Bolt - Silver

Lead Time	25-30 Working Days
	Please note the above stated lead time is measured on how soon the work can be completed once the quotation is approved
Waste Disposal Charge (Optional)	*This disposal charge covers the cost of labour loading/unloading waste, waste carrier license and yard skip hire etc.*