

Notes:

Drawings are based on survey data and may not accurately represent what is physically present.

Do not scale from this drawing. All dimensions are to be verified on site before proceeding with the work.

All dimensions are in millimeters unless noted otherwise.

Purcell shall be notified in writing of any discrepancies.

Key Plan
not to scale

To be read in conjunction with Existing GA Plans and Elevations 100 series and NBS Specification

Key

- Approximate Extent of Repair
- Line of new building abutting existing building
- (A) Indent new stone as C41*/111*
- (B) Indent new brick as C41*/502*
- (C) Repoint as C41*/225*, C41*/556*
- (D) Pin crack as C41*/126*
- (E) Iron fixing requires treatment as C50/241
- (F) Remove cable/pipework as C41*/125A
- (G) Remove fixture/fitting and make good as C41*/125A
- (H) Lift and rebed coping C41*/106*
- (J) Hydrofluoric acid clean as C40*/231*
- (K) DOFF clean as C40*/121*
- (L) TORC clean as C40*/241*
- (M) Poultice as C40*/232*
- (N) Poultice as C40*/233*
- (O) Renew cast iron airbrick as F30/160
- (P) Bed joint reinforcement as C41*/285*
- (Q) Dress of friable stone and make good as C41*/116*
- (R) Remove vegetation as C40*/110*
- (S) Mortar repairs as C41*/116*
- (T) Take down and repair cast iron pipework as R10/602 and redecorate as M60/193*
- (U) Renew cast iron pipework as R10/380 and decorate as M60/193*

ISSUE	DATE	DRAWN	CHECKED	DESCRIPTION
A	24/08/2018	SS	SS	WS4 Issue
First Issue	27/10/2017	AJ	SS	

CLIENT University of Manchester

PROJECT Manchester Museum Courtyard

DRAWING TITLE 6137-PUR-MMC-XX-DR-A-0150
External Repairs - Rutherford Building

SIZE & SCALE A1L 1:50 @A1

DRAWING STATUS ISSUED FOR TENDER

JOB NUMBER 237010

DRAWING NO. 150

REVISION A

PURCELL

Carver's Warehouse, 77 Dale Street, Manchester, M1 2HG , T:+44[0]161 300 7747, Emanchester@purcelluk.com
© PURCELL 2012. PURCELL ® IS THE TRADING NAME OF PURCELL MILLER TRITTON LLP

1
150
Rutherford Building
1:50 @A1