

Note: M+E layout and dimensions indicative only. Please refer to consultant specs.

Horizontal part of proposed window closer to ceiling level to have a louvred panel for ventilation purposes. Please refer to consultant spec.

Top horizontal part of proposed curtain wall line facing Back Piccadilly to have obscured glass panel to provide architectural continuity. For details please refer to PS.F.23 - Proposed Detailed Section.

Level 5F - GA Proposed

1 : 100

1 0 1 2 3 4 5

SCALE 1:100 m

Schedule - Room - Proposed 5F		
Level	Name	Area
LEVEL 5F	Bedroom	27 m²
LEVEL 5F	Bedroom	26 m²
LEVEL 5F	Bedroom	26 m²
LEVEL 5F	Bedroom	28 m²
LEVEL 5F	Bedroom	29 m²
LEVEL 5F	Bedroom	23 m²
LEVEL 5F	Bedroom	24 m²
LEVEL 5F	Circulation	55 m²
LEVEL 5F	Core 01	26 m²
LEVEL 5F	Core 02	16 m²
LEVEL 5F	Store	7 m²
LEVEL 5F	Store	3 m²
LEVEL 5F	Suite	40 m²
LEVEL 5F	Suite	40 m²
LEVEL 5F	Terrace	31 m²
		403 m²

Proposed roof terrace structure and horizontal bandings to have corten cladding.

Revision: Doors&windows resizing and BP roof amendment. 15.06.2018

Revision: M&E Refinements. 08.03.2018

CLIENT	PROJECT	TITLE
Cairn Hotel Group	Proposed Hotel Extension 2 Little Lever Street Manchester	Proposed GA 5F Plan

PROJECT NO.	DRAWING NO.	REV.	DRAWN BY	DATE	SCALE @ A3
6886.	PS.F.09.	B	FI	03 Nov 2017	1 : 100

street design partnership
architecture urban design interiors
16 brewery yard deva centre trinity way salford m3 7bb t: 0161 8347262 e : info@street-design.net