

Typical examples Newton St.



Typical examples Back Piccadilly St



Typical examples Dale St



Typical examples Mangle St

ALL ELEVATIONS - to be read in conjunction with 1665 P(212-217)

40. Windows to be rubbed down, cleaned and repaired. Blocked windows to be reinstated. Glass to be replaced where necessary.

41. Removal of plant growth, Carefully remove from joints voids and facework, plants, roots and associated soil/debris. Where growths cannot be removed completely without disturbing the brick/stone work seek instruction. Where removal of root system is not possible or desirable, cut through stem as close to ground as possible. remove bark from stump and apply herbicide past. Leave stump to wither

42. Erosion. Where mortar joints have been eroded/missing, carefully rake back to min 25mm (No power tools are allowed) wet existing brick and repoint with mortar to match existing

43. Damaged window glazing and glazing with non-original fittings fixed to it (ducts, vents, lettering, timber boarding etc) to be carefully removed taking care not to damage existing window frames. To be replaced by new 6mm thick single pane glazing. Existing glazing to be cleaned and scraped to remove paint and dirt build up. Window frames to be retained, carefully rubbed down to remove all loose material and debris and to be repainted.

COPYRIGHT OF ATELIER MB LTD
DO NOT SCALE FROM THIS DRAWING
DIMENSIONS TO BE CHECKED ON SITE

All dimensions to be checked on site prior to any commencing work.

Rev	Note	DRN	CHK
-	-	-	-
-			

8-16 Newton Street

Repair Stragety - No.4
All Elevations

scheme	1665
drwg no.	**P(423)**
rev	-
scale	**1:200@A3**
date first drawn	Nov 17
drawn	ZS

SK *sketch* ***P*** *proposed* ***T*** *tender* ***C*** *construction* ***AB*** *asbuilt*

www.ateliermb.co.uk
t 0161 236 0051
e architect@ateliermb.co.uk

Atelier MB
Urban Architects