Details of proposed cabling – Manchester Central

The lighting will be attached to the galvanised gratings of the 1988 foyer extension using a bracket. No fixings will be required to be attached to the original wrought iron framework. Cables will be run from the lighting units to the existing joint boxes, as illustrated below.



