NAPLES STREET

1:100 / 200 SCALE BAR
0m 5m 10m 15m

N

BUILDING '2'

BUILDING '3'

Conservation rooflights over stairs

EMERGENCY EGRESS WINDOW

EMERGENCY EGRESS WINDOW

BUILDING '4'

BUILDING '5'

APT 19
2 BED
75.2m²
809ft²

APT 20
2 BED
54.8m²
590ft²

APT 21
2 BED
55.2m²
594ft²

APT 22
2 BED
54.3m²
585ft²

TH 1
GF 22.3m²
240ft²

TH 2
GF 24.4m²
263ft²

TH 3
GF 25.0m²
269ft²

TH 4
GF 52.5m²
565ft²

TH 5
GF 33.7m²
362ft²

WALK-ON ROOFLIGHT

EXTERNAL TERRACE above original courtyard

Exposed / open roof structure

MVHR

FR GLAZING 60EI

VOID

Retention of original tile finish to corridor wall

RL

ROOF OVER LGF

LIFT 13p

CHANGING

ATRIUM VOID

WALKWAY

GLAZED SKYLIGHTS OVER

Fill in former lift door opening

Flat roof over atrium with glazed light slot, level with existing archway

New window

RISER

AOV TO PLENUM AT HIGH LEVEL

CORRIDOR 1 (vent via atrium)

APT 13
1 BED
45.2m²
487ft²

APT 11
1 BED
44.2m²
476ft²

STAIR 2

0.8m² AIR INLET AT CEILING

APT 17
2 BED
64.1m²
690ft²

APT 16
2 BED

APT 15
2 BED

APT 18
2 BED
80.0m²
861ft²

65.1m²
700ft²

62.4m²
672ft²

APT 14
1 BED
49.1m²
529ft²

APT 12
1 BED
52.4m²
564ft²

STAIR 1

Art Nouveau screen/doors retained

Art Nouveau screen dismantled and reinstated up to new fire rated soffit

SECONDARY ENTRANCE

Glass screen making cast iron column visible. Can open for cleaning

Stair existing entrance doors removed/ void infilled and window added

FX and secondary access

BUILDING '1'

NEW MOUNT STREET

LUDGATE STREET

SCHOOL STREET

Revision

AXIS architecture

Talbot Chambers 2-6 North Church Street Sheffield S1 2DH
tel: +44(0)114 2490944 fax: +44(0)114 2490966 www.axis-architecture.com

23 New Mount Street

Manchester

HOMEZZZ LTD.

Proposed Ground Floor
GA PLAN

A1 Scale	A3 Scale	Date	Drawn By
1:100	1:200	JULY 2018	AXIS

RIBA Chartered Practice

Drawing Number
27005(02)102

Revision

PLANNING

© COPYRIGHT EXISTS ON ALL DESIGN AND INFORMATION SHOWN
DO NOT SCALE for manufacture. Verify all dimensions prior to construction