LeachRhodesWalker
Architects

LRW-7664-Central House Column Schedule

This schedule is to be read in conjunction with drawing L(35)1091 A.

Column 1 – Column will be exposed within the unit fitout.

Column 2 – Column will be exposed within the unit fitout.

Column 3 – Column is virtually exposed and only a small section is embedded within the wall. This is because the new wall lines through with the existing.

Column 4 – Wall moved to fully expose the column to the stair lobby side.

Column 5 – There is a section of the column exposed within the corridor. The bedroom walls are fixed to suit the interior layout and the client's requirements, therefore space cannot be taken from the rooms to expose the columns anymore.

Column 6 – Boxing out to the existing drainage stack to be reduced as much as possible to expose a section of the column.

Column 7 – Due to the existing underground drainage the column has to be surrounded to encapsulate the services.

Column 8 - Due to the existing underground drainage the column has to be partially covered to encapsulate the services. Column and capital exposed to bedroom.

Column 9 - Due to the existing underground drainage the column has to be partially covered to encapsulate the services. Column and capital exposed to bedroom.

Column 10 - Due to the existing underground drainage the column has to be partially covered to encapsulate the services. Column and capital exposed to bedroom.